The OFFICIAL Amstrad Magazine

April 1986 £1.00

AMSTRAD COMPUTER USER


AUS $3.95
recommended
NZ $4.95

Battle lines Re-drawn

Drawing packages compared

Making Movies

Animation made easy






Plus: News, Reviews, Listings and More.

Game of the Month

NEW RELEASES

Bond... Basildon Bond



"THE ADVENTURES OF BOND . . .
BASILDON BOND"

Starring
RUSS ABBOT
Featuring
COOPERMAN, BLUNDERWOMAN, BOND

Under strict and confidential orders from P, who has been re-named B, to confuse the KGB, Bond has been assigned to rescue Russ who is being held captive by a rival comedy act, in the dungeons of the television studio.

Traps, puzzles, jokes, fight sequences and famous characters are combined to produce a funny and slightly hilarious arcade adventure.

Featuring Russ Abbots New Single
"LETS GO TO THE DISCO"

NEW

Available for the Commodore 64 and Amstrad 464/664/6128.
£9.99 cassette
£13.99 disk
Soon available for the Spectrum & Amstrad

The Devils Crown


The most amazing arcade adventure to be released for the Amstrad is NOW available for the Spectrum.

Amstrad Action Review – A.A. Rave
Graphics 94% Sonics 75% Grab Factor 85%
Staying Power 89% AA Rating 87%

Amstrad £9.99 Cassette. £13.99 Disk
Spectrum 48K £8.99



Screen shots from Amstrad version



PROBE SOFTWARE
155 MITCHAM ROAD, LONDON SW17. Tel: 01-672 9179
Selected titles available from
W.H. Smith Boots Laskys and all good software retailers

CONTENTS

REGULARS

5 **News**

9 **Letters**


14 **Gallup Chart**
The official Amstrad Top 20

90 **Least Significant Bit**
Full list of Amstrad happenings

FEATURES

17 **Animator**
Create your own cartoons

26 **Goin' Loco**
Alex Martin gets tied up with strings



29 **Adventure column**
Mindshow and Lord of the Rings

47 **Software Competition**
The great £2,000 Amsoft shareout

49 **Windows**
Dick Sargent presents the last bit of code

54 **6-8-4-5 Who do we appreciate?**
One of the most powerful chips in the Arnold can be used to generate spectacular effects

80 **Screen flipping**
Secret RSXs in Bank Manager. Making the most of the 664 & 6128 ROM

89 **Awards**
Who do you think are the best, the worst, the greatest and the cleverest?

OFFERS

78 **Amstrad User Special Delivery**
Dodgy deals from ACU

REVIEWS

33 **Epson FX85**
The FX80 was the No. 1 printer, is this a worthy successor?

37 **In the picture**
Mouse vs Grafpad vs Rembrandt



43 **Romboard Rivals**
Honeysoft vs Britannia

61 **Games reviews**
More reviews than ever before

ABC

III **Editorial**
The 8256 is a huge success, but not everything is perfect

V **Living with Joyce**
New features in Locoscript

XIII **Who are you?**
William Poel examines the results of the survey in ABC No. 1

XIX **Getting inside your PCW 8256**
How to redefine the character set

XXIX **Competition**
Win the full set of Caxton software

AMSTRAD COMPUTER USER

169 King's Road, Brentwood, Essex CM14 4EF.
Telephone: 0277-234434. Telecom Gold: 72:MAG012

Editor: Simon Rockman
Advertisement Manager: Jane Nolan

The OFFICIAL magazine for users of Amstrad computers

News trade distribution: Europress Sales & Distribution Ltd, 11 Brighton Road, Crawley, West Sussex RH10 6AF. Tel: 0293 27053.

© **Amstrad Computer User:** *No part of this publication may be reproduced without permission. While every effort is made to ensure the accuracy of all features and listings we cannot accept any liability for any mistakes or misprints. The views and opinions expressed are not necessarily those of Amstrad or Amsoft but represent the views of our many readers, owners, members and contributors. We regret that Amstrad Computer User cannot enter into personal correspondence.*

cp software


SPECTRUM • SINCLAIR QL • COMMODORE 64 •

AND NOW for ANY AMSTRAD

THE STRONGEST VERSIONS OF THE CLASSIC GAMES . . . from good retailers or by mail order

3-D VOICE CHESS

WITH SOFT SPEECH — PATENT APPLIED FOR



NEW STUNNING TECHNICAL INNOVATION!

Unique new program by Superchess 3.5 Author Chris Whittington. Brings you all the playing power of our original Amstrad Superchess, plus **SPEECH** and **brilliant 3-D graphics**. Specially developed program available only on Amstrad that brings you all the strengths of Superchess enhanced by the latest developments of sound and vision. Saves to Disc.

Beginners to expert levels and classic helpful features:

- ★ Analyse mode
- ★ Problem solving
- ★ Large opening library
- ★ Help Menu
- ★ Change colours
- ★ Recommended move

ANY AMSTRAD
Cassette £12.95
Disc £15.95

BRIDGE PLAYER 3

THE STRONGEST AMSTRAD BRIDGE PLAYER



NOW a truly EXCELLENT Bridge program for the Amstrad, written by the Author of our immensely successful Bridge 2 and the new Bridge 3 for the Spectrum.

Play a CHALLENGING AND REALISTIC game of Bridge against the computer with exceptionally strong bidding and play of cards. The Computer can play as DEFENDER or DECLARER, generates random hands, and allows proper bidding in the ACOL system including the Stayman and Blackwood conventions. Then it takes you on, playing both your opponents' hands.

Ideal as a tutor for beginners, and will give highly skilled players an engrossing game.

FEATURES

- ★ Versatile bidding routines gives you a worthy opponent
- ★ Improve your game – Post-mortem facility allows rebidding and replaying of any hand
- ★ You can review bidding or play to previous tricks while playing a hand
- ★ Input a hand or contracts of your choice to test yourself
- ★ Comprehensive ON SCREEN INFORMATION displays – contract, tricks won so far, cards played in current and last trick, score
- ★ Option to bias the deal to give you and your "partner" more high card points if you prefer to play as declarer
- ★ At any time CLAIM THE REST OF THE TRICKS
- ★ RESTART the play of the cards

A REALLY STRONG OPPONENT FOR A REALLY GOOD GAME OF BRIDGE

ANY AMSTRAD
Cassette £12.95
Disc £15.95

DRAUGHTS / CHECKERS

FOR AMSTRAD AND SPECTRUM



Never underestimate the brains needed to master the classic game of ordinary men throughout the world. This dynamite program by Chris Whittington takes you from beginners level to what *Sinclair User* called **'the Karpov of the Draughts world'.** Complete with strategic hints, kings and several levels to challenge you.

ANY AMSTRAD £8.95

BACKGAMMON

FOR AMSTRAD AND SPECTRUM

Easy to learn but plenty to challenge you in this high-speed version of the great dice classic. Superb graphics and a very intelligent playing strategy which gives you a run for your money. Complete with rules and tactical hints.



ANY AMSTRAD £8.95

NEW RELEASES

STOP PRESS . . . STOP PRESS . . .

PCW 8256

3-D CLOCK CHESS — £19.95
Written in consultation with International Grandmaster Jon Speelman (British Chess Champion 1978 and 1985). Many features plus special Against the clock mode' and brilliant 3-D Graphics.

8256 BRIDGE PLAYER — £19.95
Sophisticated and realistic Solo Bridge with powerful Bidding and Play and numerous other features.

AVAILABLE NOW ON DISC FOR PCW 8256

SPECIAL OFFER . . . . . £1 off any two programs, £2 off any three, by mail order only

PINBALL WIZARD

FOR AMSTRAD, COMMODORE 64 AND SPECTRUM



Superb, colourful fast-action graphics and sound give this game the feel of a real arcade pin-table. Realistic launch, flippers, bumpers, high-score, bonus scores and freeball features. Be a Wizard!

". . . I thought that a few minutes would suffice, and then found that a couple of hours had passed and I was still at it. Excellent . . . Pinball Wizard has it made"
CRASH MAGAZINE

"A brilliant idea that's totally absorbing and so addictive . . ."
YOUR SPECTRUM

"The display is well-designed and colourful and ball movement is very realistic."
PERSONAL COMPUTER GAMES

ANY AMSTRAD £8.95

MAIL ORDER Simply state which programs and send cheque, postal order or Access/Visa number (with expiry date). Telephone for instant credit-card orders. Send SAE for catalogue for catalogue and return postage for submitted programs.

DELIVERY by soonest post. Post free in UK. Europe add 80p per program. All other places add £1 per program for surface mail or for Airmail add £2 for first program and £1 for each additional.

WANTED! Strong and original programs of an intelligent nature for any of the above computers. Top royalties paid by this reliable company.

cp software

Dept AMU10,
15 Despard Road, London N19 5NP
Tel: 01-272 2918 Telex: 57784 MCCL G

User News...

City surprised

Amstrad surprised one of the most conservative organisations in the world, the City of London, with its figures for the first half year's trading. Amstrad made £27.5 million compared with less than £10 million in the same period last year.

Conclusions

There's so much more to be said (and, don't worry, we'll be saying it) that ACU will be devoting a complete series to 'Living with Joyce'. There won't be too many available in the UK this year (mainly through Dixon's on the high street), so place your order now.

There's no doubt the machine will be the hottest seller in the market in 1986. Remember that Amstrad shares stand at around 82p at the time of the launch, check them out in 12 months time.

Flashback to last October's ACU

Most of the profit was due to the success of the computer division and the Joyce (PCW 8256) in particular. Joyce's impact is even more remarkable when you consider that it had been on sale for only two and a half months.

The City had predicted an annual profit of £35 million, now hurriedly uprated to £45 million. The effect of the figures on share prices has been dramatic. At the beginning of the year the shares were trading at around £1.80, a week after the results they approached £3.50, *Amstrad User* predicted a price rise in the October issue, when the shares stood at 82p. The Editor just wishes he had taken the author's advice.


Firebird unleashes the Empire

British Arnold owners can thank the international nature of the Amstrad market for adding to the range of top-notch games available for their computer.

Empire is the newest game on the Firebird Gold label. It was initially planned as a Spectrum and Commodore 64 title, to be converted to the Amstrad if it sold well enough. However a large order from Germany has pursuaded Firebird to reconsider and an Amstrad version of Empire should be available at any moment.

Empire is a shoot-em-up in space. You pilot a ship from solar system to solar system, landing on planets to mine them and visiting starbases to trade or be assigned a mission.

The space sequences are in 2D while the planet scene uses 3D. All the ship's controls are designed to look like something out of Flash Gordon. The view is through a porthole and most of the gauges use liquid levels. The price has not yet been decided.



CPC 6128 dedicated game

Software houses have been understandably reluctant to write games which take advantage of the second bank of RAM in a 6128, as games which use this memory cannot be run on a 464 or 664. Alligata have broken with this line and produced a disc-only game for the 6128 but with a cut-down tape version for 464 owners.

Meltdown uses 170k on disc and all of the 6128's memory. The layout is Knightloresque 3D and the extra RAM is used to store speech, which does not require any extra hardware.

The game involves a lot of puzzle solving. To move from one 64 room level to the next you need to win a mini-game. The program costs £8.95 for the CPC 464/664 tape and £14.95 for the full-blown 6128 version.



PCW 8512 fact or fiction?

Rumours abound that Amstrad are to launch an expanded version of the PCW 8256. Although Amstrad have confirmed the existence of such a machine they refuse to be drawn on the details, price and specification.

It is certainly possible to upgrade an 8256 to 512k, although this will invalidate the guarantee. With so much RAM it could be expected that the PCW 8512 would have a second disc drive, although this is just speculation.

Amstrad are very coy about discussing new releases, but have confirmed that the PCW 8256 will not be discontinued.

SJB The MASTER Disk Distributor

3" MICRODISKS

10 Amsoft 3"CF2 Microdisks

Suitable for **all** Amstrad Disk Drives

Only

£34.95

Inc. VAT

Officially Appointed Distributor
For AMSOFT 3"CF2 Microdisks

SAVE £5

1 MEGABYTE DISKS

10 Amsoft 3"CF2-DD

1 MEGABYTE Microdisks

Suitable for your PCW 8256 Second Drive

Only

£59.95

Inc. VAT

Officially Appointed Distributor
For AMSOFT 3"CF2 Microdisks

.FREE 24HR Delivery in the UK...Same Day Despatch.

Please Send Cheques/PO's to:

SJB DISKS LTD

[Dept AU] 11 Oundle Drive Nottingham NG8 1BN


Hotline 0602-782310

Access VISA

Great games from Activision

If you have seen Master of the Lamps you will probably find it hard to believe that Activision have anything amazing up their sleeves. How wrong you are. There are two great games in the pipeline.

Rescue on Fractalus is an established classic on the Atari 800 and Commodore 64. It will be available for the CPC computers very soon. You fly a



small spaceship over the mountainous surface of a planet, looking for and rescuing the pilots of crashed spacecraft. Aliens are out to prevent this and will shoot at you from their UFOs and gun emplacements.

Eidolon is a second Activision newie, similar in feeling to Fractalus but this time you fly through a complex of caves, battling against a host of aliens.

Activision's plans go further, they have signed up the rights to six blockbuster films for the next year. The titles are a closely guarded secret but we believe that they will include Ghostbusters II and Alien II.

A bit on the side

The PCW 8256 is principally designed for word processing, but as a computer it offers a host of attractive features, one drawback for the businessman is the width of the printer, it is too narrow to take A4 paper on its side, or landscape as photographers call it.

A solution is to save the text in a file and then use a special program to print the document as a graphics dump, with all the characters rotated through 90 degrees.

Such a program is available from Trinity Business Systems, it costs £19.95, and offers a variety of fonts. Trinity can be contacted on (0603) 812195.



Nick Alexander, MD of Virgin Games, making a clean sweep.

Virgin Games on the ball

Virgin Games, voted Software House of the Year in the Amstrad User readers poll, have announced their latest release. F.A. Football is based on years of research by Tony Williams. There are some novel features – including an eight player option, but initial reaction to the game from ACU reviewers is that it is another boring football simulation.

Virgin have some much more exciting stuff in the pipeline. The first is Shogun, a Japanese combat game. Virgin also have a project based on the Eagle comic hero Dan Dare.

Got any Elite bugs?

Two hours into Elite, just about to zap your seventy second Thargoid and what happens?

Nothing. There is a bug in early versions of Elite which causes it to lock up.

Firebird are very sorry about this and will replace any bugged copies free of charge. They will also give you a discount voucher for future Firebird products.

Have we got a video?

Orpheus have moved Rick, Mike, Vyvian and Neil on to the CPC 464. These early screen shots show how the game will look. The aim of the game is to control your character and get out of the house.











Vive l'Amstrad!



In the UK Amstrad is the No 3 computer, although it is rapidly rising to challenge those at the top of the ladder. It's a different story in France, which has a funny television system, reducing the impact of Commodore and Sinclair computers which needed to be heavily modified to work on the French Secam system. The native computer is a Thompson, but even that is No 2 to Amstrad.

The first Amstrad computer show was recently held in Paris, under the auspices of Amstrad magazine. As with the London shows, Amstrad Expo was an overwhelming success – 1,000 people were locked out on the first day.

The show may not have been as big as the London ones but there was just as much enthusiasm. The Joyce is a much more expensive machine in France (around £600) and was not nearly as popular as the Arnolds. This is surprising because l'8256 has an azerty keyboard as beloved by French typists.

We had expected to see a lot of translated English software and some pretty ropey French software (the Ed's xenophobic attitude). What we had not expected was some red hot home grown stuff. The best game we came across was Le 5eme Axe, which is reviewed in this issue. Other games of note were Crafton and Xunk, which is shortly to go on sale here from PSS and Warrior, a disc-based dungeons and dragons.

Music was very popular. There was a large display of Midi synths and a couple of Music System type composing packages. Pinball machines are much more popular in France than in the UK. Macadam Bumper has already crossed the Channel, while the Cobra pinball game has stayed put. Cobra demonstrated their game to good effect by building an Arnold into a pin table.

Despite the heavy (French) accent on games there were some more serious applications. A 464 on the Amstrad stand was running Minitel – the French cross between a telephone directory and Prestel.

The best bargain at the show was DBase II, an advanced database language which sells for £390 here but the price for the French version was a mere £70 for exactly the same thing save the translated prompts.

The show was spread over three days. It was good to meet so many enthusiastic Amstrad owners in a place where Amstrad is the No 1 computer manufacturer.


DAVE and PAM

by ALEX & SPITAL



Write to reply

Please bear in mind that the views expressed herein are not necessarily those of Amstrad or Amsoft. Be assured that all your views are given thorough consideration. This letters section is the Amstrad Computer User's own forum.



A town called Amstrad

This letter is being sent to you from the far flung colony of Australia. I am formerly from Aldershot in Hampshire. In 1966 I emigrated to the colony of Australia to help bring Christianity to the black heathens, at which I failed miserably, most of them are still running around naked, brandishing their Woomera's (no ribald puns please) and swilling down large quantities of plonk from what they term their 'plagons', which is a twisted form of flagon.

Having been exiled in this god forbidden country of deserts, swamps and dingos for the last 18 years, I have obtained a little solace from purchasing an Amstrad 464 and disc drive, which I got from a passing trader on the camel route from Alice Springs. It cost me two fine horses, ten sheep and a signed photo of Boy George. I believe I won out in our bartering as I forged Boy Georges signature to the photo. (Besides it wasn't Boy George, it was André the Giant in drag).

Anyhow after several months, Amstrad User magazines started to appear at the outpost store. I quite naturally snaffled these up, so that I could read about how they are being used in civilisation. In fact I went so far as to order it on a regular basis, and even received one in this manner.

All of a sudden, after many months of anxious waiting, I was informed by the store keeper that Gordon And Gotch the suppliers from the big settlement in Melbourne, could no longer supply it, not even the back issues that I requested six months previous. Now my life is barren again. I am waiting to find out if Australia's equivalent of Prestel, over here it's Viatel, will be brought out on the Amstrad. The dreaded Commodore has it, but not the Ham Spread (affectionate term for Amstrad).

I could even have joined the Amstrad Club here in Australia, being run by AWA, only I lost the card I was supposed to send in (I secretly believe the house boy ate it). Is it possible for you to send me a regular subscription of Amstrad user mag. Is it possible to get all the back issues. Is Amstrad going to make it possible to plug into Viatel. How much? (moolah is this going to set me back). Well I must go now as the natives are having a Corroboree, which they say is going to bring the young men of the tribe to manhood, they remove something from them, and I'm their star guest.

Dennis O'Neill,
Nollamara 6061,
Western Australia.

ACU: Well that has just alienated half our Australian readers. Retail supplies of ACU should improve down under (Note the AUS $ price), since AWA have just doubled their order. Subscription is faster and more reliable – see the special delivery at the back of the magazine. We reviewed a collection of serial interfaces last month, if Viatel is the same as Prestel then they should work.

DR – 0 User – 0 (No score draw)

I should be interested to hear from any other PCW 8256 user who has tried to run DR Draw on the machine. Lured by the compelling advertisement from Digital Research which claimed that the program was "ready to run now on your CP/M bundled PCW 8256" I sent off a cheque and looked forward to the prompt arrival of a program that I could start to use straight away.

I was soon disillusioned. Not only did it take over six weeks for the package to arrive, after ceaseless prodding of elusive people in Basildon and Hungerford, but it also proved impossible for a person of my limited experience to load it. Like many PCW 8256 users I am a newcomer to the world of computers and the language of Basic. The instructions for preparing an operating disc which came with the package were beyond my limited comprehension.

When I buy a program, particularly at these artificially elevated prices I expect to be able to use it, and I expect the words used in the advertisement to mean what they say.

Am I alone in this respect? It seems to me that Digital Research have got a lot of explaining to do if they want to keep the PCW 8256 market.

W.G. Crampton.

***ACU:** DR have been known to do some funny things, but think how the poor (rich?) people who paid £200 feel.*

Perpetual Music

I must congratulate Fred Gray on his fantastic music from Ocean's "The Neverending Story". I could sit and listen to it all day. I think it is a very good adventure with great graphics and very well presented.

I would recommend anyone to buy it.

Richard Devlin.

***ACU:** You forgot to say that you are not the programmers' cousin and haven't got shares in Ocean.*

Friend of Joyce

For years I worked as a consultant in WP for Wang, IBM and ICL. I left two years ago to have a baby and began writing novels a few months ago. I was destined for the typewriter and horrors I bought one and it did not get on with me at all. What was this silly thing that required carriage returns so as not to shoot off the end of the paper?

My husband recently purchased an Amstrad WP and I had my doubts, I can tell you because of the price. But minus one or two bits which time will improve, it is perfect. Particularly the manuscript layout, it more than meets my requirements and is obviously the work of a genius.

The Amstrad, of course, is the result of a bit of thought and careful analysis of what the public really want or need. Not something computer people are very good at generally. I bet there is a lot of jealousy, I have heard some of it myself. All you competitors will have to go back to the drawing board won't they?

Anyway, I am in love with the thing and I want to give it a name which just



THINKING THINK



TASWORD 6128
THE WORD PROCESSOR

TASWORD 6128 for the Amstrad CPC 6128 disc £24.95

Brilliant value for money.
AMSTRAD ACTION
December 1985.

A powerful and easy to use word processor and a superb data merge program. AMTIX December 1985.

TASWORD 6128 is the word processor especially developed to utilise the extra memory in the CPC 6128.

The program uses ALL the additional 64K of memory in the CPC 6128 as text space. This means that text files can be around ten thousand words long.

TASWORD 6128 includes a built-in data merge program. Mail merge, in which a letter is printed any number of times, each individually addressed to a different person, is just one of the applications of this powerful facility.

The notepads are a unique feature of TASWORD 6128. Four separate notepads are available. Typing reminders and storing letter headings are just two possible applications for the notepads.

Up to one thousand characters can be stored in ten user definable keys allowing commonly used words, sentences, or even paragraphs to be typed with a single keypress.

TASWORD 6128 has comprehensive customisation features. These allow many of the program facilities to be changed to personal requirements. A customised program can be saved and includes the notepads and user definable keys.

TASWORD 6128 is fully compatible with TAS-SPELL and TASPRINT. It will also read in data from Masterfile 6128. It can even be used to enter and edit your own Basic programs.

With all standard and many extra word processing facilities TASWORD 6128 is the most powerful of the TASWORDS.

TASWORD 464
THE WORD PROCESSOR

TASWORD 464 cassette £19.95

"There is no better justification for buying a 464 than this program"
POPULAR COMPUTING WEEKLY, NOVEMBER 1984

Your 464 becomes a professional standard word processor with TASWORD 464. Supplied complete with a comprehensive manual and a cassette which contains both the program and TASWORD 464 TUTOR. This teaches you word processing using TASWORD 464. Whether you have serious applications or simply want to learn about word processing, TASWORD 464 and the TUTOR make it easy and enjoyable.

TASWORD 464-D
THE WORD PROCESSOR – WITH MAIL MERGE!

TASWORD 464-D disc £24.95

This is the new TASWORD especially developed to utilise the capabilities of the CPC 464 and 664 disc drives. The additional facilities include a larger text file size and automatic on-screen disc directories during save and load operations. A major new feature is the mail merge facility. This gives multiple prints of your standard letters, forms, etc., with each copy containing, for example, a name and address automatically taken from a disc file containing the data. This data can be entered using TASWORD 464-D, or created using the Masterfile Program Extension package. A powerful and useful conditional printing facility is included – parts of a document can be printed according to user-specified criteria. TASWORD 464-D will only run on, and is only supplied on, disc.

Available from good

Tas
SOFT

Springfield House, Hyde Terrace,

Overseas. The following distributors of Tasman products may be contacted for the address of local suppliers. Many products are supplied in translated form. FRANCE & SWITZERLAND Semaphore Logiciels, CH 1283 La Plaine, Geneva. SCANDINAVIA Kelly data, Postboks 43, Refstad, Oslo. NETHERLANDS Filosoft, PO Box 1353, 9701 BJ Groningen. U.S.A. Ramex International.

SOFTWARE?...

TASMAN



TASPRINT 464
THE STYLE WRITER

TASPRINT 464 cassette £9.90
disc £12.90

A must for dot-matrix print owners! Print your program output and listings in a choice of five impressive print styles. TASPRINT 464 utilises the graphics capabilities of dot-matrix printers to form, with a double pass of the printhead, output in a range of five fonts varying from the futuristic DATA-RUN to the hand-writing style of PALACE SCRIPT. TASPRINT 464 drives the dot-matrix printers listed below and can be used to print AMSWORD/TASWORD 464 text files. TASPRINT 464 gives your output originality and style. Completely compatible with the 664 and 6128.

COMPACTA - bold and heavy, good for emphasis
DATA-RUN - A FUTURISTIC SCRIPT
LECTURA LIGHT - clean and pleasing to read
MEDIAN - a serious business-like script
PALACE SCRIPT - a distinctive flowing font

Typical Tasprint output shown at approximately half size. Please note that different makes of printer produce different sized output.

TAS-SPELL
THE SPELLING CHECKER

TAS-SPELL disc £16.50
for the Amstrad CPC 464 and 664 running TASWORD 464-D and for the CPC 6128 running TASWORD 6128

Spelling mistakes and typing errors spoil any document whether it is a private letter or your latest novel. With TAS-SPELL you are free to be creative in the confident knowledge that your spelling won't let you down.

TAS-SPELL checks the spelling of TASWORD 464-D and TASWORD 6128 text files. TAS-SPELL has a dictionary of well over twenty thousand words which it compares with the words in your text. If a word is not recognised then the relevant part of your text is displayed with the suspect word highlighted. You can correct the word, ignore it (it might be a name), or even add it to the TAS-SPELL dictionary.

Please note that TAS-SPELL will only work with TASWORD 464-D and TASWORD 6128.

TASCOPY 464
THE SCREEN COPIER

TASCOPY 464 cassette £9.90
disc £12.90

A suite of fast machine code screen copy software for the CPC 464, 664 and 6128. Print high-resolution screen copies in black and white and also large 'shaded' copies with different dot densities for the various screen colours. TASCOPY 464 also produces 'poster size' screen copies printed onto two or four sheets which can be cut and joined to make the poster.

TASPRINT 464 and TASCOPY 464 drive the following dot-matrix printers:

AMSTRAD DMP1	MANNESMANN	STAR DMP501/5/515	SHINWA CP-80
EPSON FX-80	TALLY MT-80	BROTHER HR5	COSMOS-80
EPSON RX-80	BROTHER M1009	DATAC PANTHER	AMSTRAD DMP2000
EPSON MX-80 TYPE III	NEC PC-8023B-N	DATAC PANTHER II	

TASWORD UPGRADES

TASWORD 464 and Amsword owners: send your original cassette or disc (not the packaging) as proof of purchase and £13.90. Your original will be returned together with TASWORD 464-D or TASWORD 6128 on disc.

stockists and direct from:

man
WARE

Leeds LS2 9LN. Tel: (0532) 438301

If you do not want to cut this magazine, simply write out your order and post to:
TASMAN SOFTWARE, DEPT AU, SPRINGFIELD HOUSE, HYDE TERRACE, LEEDS LS2 9LN

I enclose a cheque/PO made payable to TASMAN SOFTWARE Ltd OR charge my ACCESS/VISA number: .....

	ITEM	DELETE	PRICE
NAME _____	_____	disc/cassette	£ _____
ADDRESS _____	_____	disc/cassette	£ _____
_____	_____	disc/cassette	£ _____
_____	_____	disc/cassette	£ _____
_____	Outside Europe add £1.50 airmail per item:		£ _____
Telephone Access/Visa orders: Leeds (0532) 438301		TOTAL £	_____

Please send me the FREE TASMAN brochure describing your products for the Amstrad CPC 464, 664 and 6128. ☐ *tick here.*
All prices include VAT, postage and packaging. AU

GERMANY Profisoft, Sutthauser Str 50/52, D 4500 Osnabruck. BELGIUM Easy Computing, Avenue Guillaume Lefever 30, 1160 Brussels. PORTUGAL Informova, Campo Grande 28 4 A, 1700 Lisbon. AUSTRALIA Dolphin Computers, 99 Reserve Road, Artarmon, New South Wales 2064. NEW ZEALAND Software Supplies, PO Box 865, Christchurch. USA 7620 26 Mile Road, Washington MI 48094.

All TASMAN 464 software is fully compatible with the 664 and 6128.

goes to show what a darling it is. *(Joyce? – Ed).*

Thanks a lot for saving me from terminal boredom at my typewriter.

Diana Lunt.

Longer life ribbons

Until I read Mr Gerrard's article I had no way of knowing that you could get 360k on a PCW 8256 disc. Amstrad keep it quiet, so thank you very much. He makes as a reference, tongue-in-cheek, to saving on ribbons but surely since the wear appears only to be along one line this is poor design – or is it done deliberately because typewriters have always worked this wasteful way?

Of course one can use a ribbon ad nauseam in conjunction with Wiggins Teapes self-contained carbon flimsies for single sheet pulls, but that's not the point at issue. Still, an article on printing would be welcome.

Eric Ambrose.

ACU: *The printer ribbons are designed with a twist at the end, so that the whole width of the ribbon is used. Another solution that can rejuvenate ribbons is to apply WD-40 silicon fluid to the ribbon surface and leave to soak for a few hours. You are advised to keep the printer head free of excess fluid.*

Amstrad Sardine Show

Well somebody has got to say it! We were told "This year we've got it right – bigger venue etc" but the organisers' crystal ball was not properly programmed again. Something must be done to eliminate problems like nowhere near enough space, the stands were too small and close together and the room was stiflingly hot.

One exhibitor should be eliminated, they were selling the DMP 2000 at a special price of £169.95 *(racist bit deleted here – Ed)* so I'm still waiting patiently but happily for my printer from another supplier.

Despite all this, the show was very worthwhile and the Novotel's facilities were excellent, but for heavens sake Amstrad, get it right next time.

Ah well – third time lucky.

ACU: *The Amstrad computer shows are nothing to do with Amstrad, they are officially endorsed but the involvement stops there. Predicting the success of a show is always difficult. The second show was very much bigger than the first, if you were too hot there was plenty of room downstairs where you could sit and relax.*

Stand space is expensive, an hotel has to cope with hefty overheads, if the stands were made much bigger then many of the smaller companies could not afford to exhibit. It would be illegal for Amstrad, or anyone else, to fix the sale price of the DMP 2000. The company you named sold all their printers on the first morning, leaving many potential customers without a printer. Perhaps the price was too low. That is the way the laws of supply and demand work.

Socket to 'em

I own a PCW 8256 and a screwdriver, now that may not sound very exciting, but by combining the two I found something that is pretty exciting – sockets. Inside my PCW is a whole row of empty sockets – which I assume can be used to upgrade the RAM. Will Amstrad be offering an upgrade service?

ACU: *There are rumours that Dictaphone will offer a suitable upgrade, although ACU can't be sure. The ubiquitous NewStar company will offer an upgrade soon but for the moment the only way to expand your Joyce is through Prism Electronics who can be reached on 01-445 9796. Remember that opening up any Amstrad computer will invalidate the guarantee.*

ACU

REMs

Arrrgghhh!

I have a definition of computer torture: I have been banned from my Amstrad for a whole week because I wouldn't let my sister go on it! And what's more I've just got a new game. (Aah!). (J.J. Trice, Molescroft, N. Humberside.)

The strange case of the missing case

When I used tape based machines it always annoyed me that the software suppliers would often not supply the proper case for the cassette but rather a variety of oversize cases or no cases at all. This meant that I had to buy spare cases so that the software would fit into my storage cases.

Now that I only use discs I find that the same problem occurs. Of five recent disc based software purchases only one company (Hisoft) supplied the proper case. The other companies supplied me with plastic bags! Is there a black market in 3in disc cases, are they so valuable that leaving them out substantially reduces the cost of software or is there a law against 'pushing' them to the users? What is the point of buying neat storage boxes if suppliers will not adhere to the proper storage standards?

Do you know where I can buy spare cases and also the sticky labels? (D.R. Halliwell, Oxton, Merseyside.)

Where can I get? . . .

I would very much like to obtain the Head-Line Communications tapes on LocoScript referred to in an article in the ABC Review section in the March issue of the User Magazine.

Please could you give me the address to write to and if possible, the price of the tapes. (Mrs G. Carey, Bulford, Wilts.)

ACU: **The Headline tapes can be obtained from all good software shops and from Newstar Software, price £9.95.**

Cartoon Fun?

Drivel!! I refer of course to your pathetic attempts to reply to CASH's criticisms of the Dave and Pam cartoon.

You base your defence around the claim that cartoons derive their humour from stereotypes. If this is so (let me point out that I think it ain't), why don't you go the whole hog and portray Pam as black and get her to talk with a comic accent. Now dat am funny, I don't think!

Let's face it; the Dave and Pam cartoons are only slightly more humorous than a weekend watching paint dry. So, unless you can find some jokes for them which rely on something more than mocking stereotypes for their laughs, why don't you just forget it?

As a forum for reviews of software and hardware and articles on how to get more out of the Amstrad Machines, ACU is doing a good job. As a comic it isn't.

In other words: Cobblers! Stick to your last! (Terry Booth, Kings Norton, Birmingham.)

ACU: **At least our jokes are new.**

REMs

AMSTRAD PROFESSIONALS FROM DIGITAL RESEARCH

First, two powerful software development languages at just £49.95 each.



Both as complete packages of standard Amstrad 3" disks. Both configured to load and run **now** on your CP/M bundled Amstrad PCW 8256 or CPC 6128. Both offering you the applications portability and development power of professional CP/M programming languages from the creators of CP/M, Digital Research. Both at an extraordinary price, fully in keeping with Amstrad's own value for money philosophy. Both available for the first time directly to Amstrad users.

Amstrad Professionals from Digital Research will progressively expand the capabilities of your Amstrad by providing you with an armoury of professional languages, tools, utilities and graphics packages of unrivalled power and value for money in the small computer field. (See also DR GRAPH and DR DRAW overleaf, both released simultaneously with the above Amstrad Professionals titles.)

Full support available from BELL TECHNICAL SERVICES LTD

Start building your Amstrad armoury now with Amstrad Professionals from Digital Research.

Send your order and cheque or credit card number to:
DIGITAL RESEARCH (UK) LTD
Unit 12, Fenton Way
Southfields, Basildon
Essex SS15 6SL

Or contact your local Amstrad dealer.

DIGITAL RESEARCH®
The creators of CP/M™

GALLUP



This chart is based on the MicroScope chart as compiled by Gallup.

MicroScope: GALLUP

MicroScope is the weekly trade paper of the microcomputer industry. If your computer store doesn't display the latest MicroScope chart, ask the manager to call Mark Salmon on 01-631 1433 – we'll send a copy every week.


	TITLE Publisher	4 weeks up to 8/2/86	Last Month				Months in chart	Market Strength
1	**THEY SOLD A MILLION** Hit Squad		1	-	664	D	3	100
2	**YIE AR KUNG FU** Imagine		2	-			3	90
3	**FORMULA ONE SIMULATOR** Mastertronic		4	▲	???		4	85
4	**FINDERS KEEPERS** Mastertronic		6	▲	???		7	69
5	**CAVES OF DOOM** Mastertronic		8	▲	???	-	3	68
6	**GRAND PRIX 3D** Amsoft		3	▼	A	664 D	4	67
7	**SOUL OF A ROBOT** Mastertronic		5	▼	???		4	64
8	**SKY FOX** Ariolasoft		ne	▲	664		1	57
9	**ELITE** Firebird		ne	▲	664	D	1	54
10	**COMPUTER HITS (10)** Beau Jolly		7	▼	???		3	52
11	**WHO DARES WINS 2** Alligata		14	▲	???		2	46
12	**SPELLBOUND** Mastertronic		19	▲	???		2	44
13	**HYPERSPORTS** Imagine		ne	▲	???	D	1	39
14	**ONE MAN AND HIS DROID** Mastertronic		ne	▲	???		1	38
15	**TORNADO LOW LEVEL** Vortex		ne	▲	664	D	1	35
16	**CHILLER** Mastertronic		11	▼	???		7	35
17	**NONTERRAQUEOUS** Mastertronic		12	▼	664		7	33
18	**SPITFIRE 40** Mirrorsoft		16	▼	A	664 D	2	32
19	**BARRY MCGUIGAN WORLD CHAMPIONS** Activision		ne	▲	664		1	31
20	**SCRABBLE** Leisure Genius		9	▼	664	D	6	29

D Available on Disc — 664 CPC 664/6128 Compatible — A Available from Amsoft — ??? Untested


SOFTWARE CHART

AMSTRAD PROFESSIONALS FROM DIGITAL RESEARCH

Now, two interactive graphics packages at just £49.95 each.



DR GRAPH



DR DRAW



Both as complete packages of standard Amstrad 3" disks. Both configured to load and run **now** on your CP/M bundled Amstrad PCW 8256 or CPC 6128. Both offering you the creative potential and professional impact of presentation graphics from the creators of CP/M, Digital Research. Both at an extraordinary price, fully in keeping with Amstrad's own value for money philosophy. Both available for the first time directly to Amstrad users.

Start building your Amstrad armoury now with Amstrad Professionals from Digital Research.

Send your order and cheque or credit card number to:
DIGITAL RESEARCH (UK) LTD
Unit 12, Fenton Way
Southfields, Basildon
Essex SS15 6SL

Or contact your local Amstrad dealer.

DIGITAL RESEARCH
The creators of CP/M™

Full support available from BELL TECHNICAL SERVICES LTD

New: Prospero's professional language compilers for the Amstrad PCW8256

PRO PASCAL & PRO FORTRAN FOR AMSTRAD!

£75
END-USER VERSION

Incredible value!

ISO-PASCAL
Pro Pascal is validated to ISO 7185 Class A (no errors) on the Z80 processor under CP/M. No other Pascal compiler for the Amstrad provides this guarantee.

FORTRAN 66
Pro Fortran is a full implementation of ANSI Fortran 66 with no omissions and many useful extensions

Ideal for
- schools and colleges
- students of computing
- development of personal skills
- solving technical problems
- training institutions

USE THE LANGUAGES THE PROFESSIONALS DO: PASCAL AND FORTRAN

NO BUGS YOU DON'T HAVE TO FILL IN ALL THE HOLES

Lazy I/O
All files closed on exit from procedure

PASCAL ⟷ FORTRAN
INTERLINKABLE OBJECT CODE

Compilers include: compiler, linker, run-time libraries, librarian, X-ref program, sample programs, 200 page manual.

Allows program chaining.


16 digit
Single and double precision IEEE format arithmetic gives 7 or 16 digit precision

✓ Produces compact efficient code

"Pro Pascal is not only ISO-validated, it is also a superb-quality and very full software development tool."
Personal Computer World Nov 1985

Also available from Amstrad specialists & distributors

At Prospero we specialise in writing language compilers. We produce the best possible compilers, conforming to the appropriate standard, and giving programmers a secure base on which to build.



BIG
Compiles big programs
>10000 lines...
>1000 identifiers...
Separate compilation to build libraries and massive program suites

Used at 5000 sites around the world

Prospero Software Ltd
190 Castelnau, London SW13 9DH
England. Telephone 01-741 8531.
Telex 8814396 PROSOF G.

It's easy to order!

Credit card holders phone 01-741 8531
Access, Visa, Diners & Amex taken.


Mail order

Send this coupon with cheque to Prospero Software, 190 Castelnau, London SW13 9DH, England.
Post free in UK - add 15% VAT.
Overseas orders no VAT - add £3 post and packing.
Allow 28 days for delivery.

Please supply ____ copies Pro Fortran at £75
Please supply ____ copies Pro Pascal at £75.
I enclose payment for £____

Name _____
Address _____
_____
Telephone no _____
In case of query ring 01-741 8531 or telex 8814396

ACU 4/86



A·N·I·M·A·T·O·R

Chris Wood presents a program to give your computer a touch of the Walt Disneys.

At last, this month I have for you the final, complete, all-singing, all-dancing Animator. The reason I didn't have it ready for you last month is because it was decided (by the Editor) that it wasn't fast enough dammit! You may have noticed yourself that as the lines lengthened, the routine slowed down, which meant it was not as spectacular as it could have been.

Faster lines

Do not let that put you off. This month everything is as promised, and more! The problem was that although the rest of my code was OK the slowest thing was the actual line drawing, and that was being done by the firmware. There was nothing for it but to trace the ROM's line drawing routine and see if it could be improved. It couldn't.

The ROM is fine for drawing ordinary lines, and is much more friendly than say, the Spectrum, in that it is quite happy to let you draw lines that are not even on the screen, and it has to cope with the screen rolling about in memory as well.

Friendly this may be, but it was not as fast as we want. So I have written my own line drawing routine. It is about four times faster in mode two, eight times faster in mode one and sixteen times faster in mode zero. I don't check for lines going off the screen, which means you must make sure your lines always stay on screen. The routine is fairly tolerant and generally the lines go off one side of the screen and wrap round to the other, but sometimes they don't, so be careful. The frame editing program does some checking, but it can't check everything.

I will explain where you should be careful when I describe the commands. In modes one and zero I halve and quarter the length of the line and only plot a half or a quarter of the points that I would in mode two. So I am happy, you will be happy, and most important of all the Editor is happy.

What does the program now do? Well, using the editor you can design as many frames consisting of up to 50 lines (although about 20 is a usable maximum) and then "tie" them together in any order you like. Say you design five frames. One is your first name, one is your last name, another is a Porsche, the fourth is a tree, and the last one is a man. By tying them together with varying speeds you can have your first name turn into the Porsche in 10 moves, the Porsche turns into your last name in 30 moves and so on. You can vary the speed, and so the smoothness, that one frame pans to the next, and you can have them going around in an endless loop, or just go from start to finish and then stop.

With enough frames you could easily



design a small cartoon. It is very easy to enter the key frames of a man walking, and have the in-betweening done by the program. The possibilities are endless, and great fun to watch.

If you don't feel up to typing in the frame editing program to start with, then you can first type in the small demo program (Listing II) to see what can be achieved. Type in the first program to generate the machine code and then run the second little program to see it in action. What it does is pick random points for five lines to go to, animates them smoothly there and then picks five more points and animates from the last set to the new ones.

If you want to skip the demo you must still type in Program I. As usual it is extensively error-checked. When that is safely done and you have no errors, save the program and type in Program III. Run the program and you will be asked which mode you want the display to be in, and how many lines you want to play with. I suggest you start with 10 lines and choose mode one. It just so happens that 10 lines is exactly the right number to make the letters ACU, which are the letters I used last time, and by an even bigger coincidence are the initials of this magazine.


Using the editor

For the purposes of guiding you through the use of the editor I am going to assume you are going to design these letters, but feel free to choose your own. You will be greeted by left and up arrows (Hello says the arrow) at the bottom of the screen, with the number zero next to both of them, two number ones below them and the word ON next to these. There will also be part of a flashing cross in the bottom left hand corner. What you have here is an empty frame, so you must initialise it.

Press the O key for a list of options, press I for initialise and wait a few seconds. You will see a small cluster of dots in the middle of the screen and the flashing cross. Use the cursor keys with Shift to move the cross about the screen. You will see it is rubber banding the line. As you move the line you will see the coordinates at the bottom of the screen changing. If you move the cross without using Shift the cross moves by smaller amounts.

The cross moves up and down by one

pixel line, and left and right by one pixel in mode two, half a pixel in mode one, and a quarter of a pixel in mode zero. This means that even though the coordinates change when you move left and right, the cross moves a half or a quarter as fast for fine tuning. The program stops you moving off the screen when you move one pixel at a time but it doesn't check when you are using the



Shift key so make sure you stay on the screen.

Move the cross an inch or so from the cluster of dots and press the Copy key. The cross will move to the other end of the line, and you can move that into position.

OK, now about those two ones and the ON. The first one tells you which line the cross is currently attached to and the second tells you which frame you are editing. Use the ◁ and ▷ keys without pressing Shift to move from one line to the next. Hold down the ◁ key until you are at line 10. You can't go past the largest line you chose, and you can't go past one in the opposite direction.

Whenever you move from one line to another the cross is always put at the start of the line, that is the line is drawn from A,B to C,D and the cross is put at the A,B end. This is useful, as I will explain later.

Now stretch a few lines about the screen. As your lines get longer, movement about the screen will get slower because of the work Basic has to do between each update. It gets quite slow to move about the screen. By pressing Space the only thing that will be drawn is the cross, which you can position where you want before pressing Space again to see the result. This makes moving about the screen a good deal faster.


Frame to frame

Now design ACU or whatever takes your fancy in the middle of the screen. Not too big, about two inches by four. Press Enter and you will be asked "Which frame now?" Enter 2 and you will get the same blank screen as before. Press O and I to initialise again. Now press O again and this time select T for Tie together. Enter 1 as your first frame and it will be drawn. Enter 2 for your second frame and 12 for the number of steps. Just press Enter for the next two options.

Select 1 again for the next frame. This will make the program animate from 1 to 2 to 1. This time select 48 as the number of steps and again just press Enter for the next two options. When you are asked "Which frame next?" for the third time enter 999. You will see your letters growing slowly out of a cluster of dots and quickly back again. This will repeat until you press ESC ESC to break into the program. I have not checked any keys here because I want maximum speed.

Run the program as before, enter the mode and number of lines. This time you will be greeted by your first design. Press Enter and select frame two again. Now we are going to copy frame one to frame two. Press O and select the C option for Copy and enter 1 as the frame.

You can now alter your design. Redesign it to look similar, but with the lines in a different order, instead of the first four lines making up the A of ACU spread them about. When you have done this or something similar, you can slide your design around the screen. Press O



and select S for Slide. You now have the option to slide the line that the cross is attached to or to slide the whole design.

Select A for All and enter X and Y increments. Enter a positive number to move right or up, and a negative number to move left or down. Be careful to make sure that you don't give too large an offset as the design could move off the screen and you'll confuse the line drawing routine. If in doubt move in two or more stages.

Flippin' lines

Now you can press Enter and select frame three. Copy either of the two previous frames and alter frame 3. You can flip the ends of a line, so it is drawn from what was C,D to A,B. This is so you can simply slide a line from left to right, or have it rotate into place. To do this press O and select F for Flip.

You can turn a line through an angle by selecting A from the options menu and entering the angle to rotate through. Zero degrees is a straight line to the left and 90 degrees is straight up. The angle is always rotated from the A,B end of the line so if you want to rotate from the other end you must flip the line before you rotate it. Selecting P from the options menu will allow you to change the pen colour for the current line. M from the menu will allow you to magnify the length of a line, numbers less than zero will shrink the line. This means that a value of 0.5 will halve its length and a negative number will draw it in the opposite direction from the start point.

The line is always magnified from the A,B end of the line, so as with rotate, you have to flip it if you want to magnify it from the other end. You should make sure the line stays on the screen, so if in doubt, move it back. With magnify and rotate you can have your design spin from a small one up to full size. Pressing R from the options menu will return you back to the editor if you change your mind.

You should now have three frames which you can slide so they are spread about the screen. Now select T from the options menu and watch them pan from one to the other as before by selecting 999 as the last frame. You can, of course, animate in any order of frames, and you don't need to use all of them. If you had 10 frames if would be quite valid to select 3, 5, 1, 3, 999. Press ESC ESC and run the program again. This time you can try and select how many lines that you want to animate.

Designing a background

Always bear in mind that if you have fewer lines animating in a frame than in previous frames some will be left behind until the frame ends.

You can prevent this happening by making the stationary lines disappear. This is achieved by shrinking the lines down to a single dot, and then positioning them in the same place as another line, so that they can't be seen.


Stationary lines can be very useful if you want to build up a scene on the screen. For instance you could have a cartoon which starts with a dot in the centre of the screen. The dot grows into a house in one frame, but stays on the screen while another dot grows in to a



tree. A car could drive across the screen before turning into a road. You decide whether a line is to be erased or not by answering 1 (or any other than zero) to the question "Erase lines?" You will then be asked if you want each line to be erased at the end of its animation, to which you reply Y or N for each line in turn.

The program will then temporarily modify the frame data so that the machine code doesn't erase the last frame when it moves to the next one. If you decide to re-animate and select all lines to be erased when they had previously not been, press O for the options menu in the editor and select option E to erase. This will set all the lines in a frame back to the normal "erase at end of frame" mode.

You will notice that if you animate between two frames all the lines seem to get erased as normal, even if you want some to remain. This is because when



frame two goes back to frame one on its return journey its first frame coincides with what was its second-to-last frame on its first journey, and by erasing itself it erases the lines that were to be left behind.

This is true of any lines that you set to get left behind. If a line passes over or through them they will be erased, either slightly or completely. If one of your frames does erase something you wanted left behind, you can refresh some of your animations by copying the frames you wanted to another frame and animating it. You need as many copies of the "refresh" frames as you need to do the refreshing, as each frame can only lead to one other frame, and you cannot link in a frame twice – you have to use a copy of it.

I said that the lines are not erased on the last frame of animation, and this is true, but since the last frame of one animation is one step before the first frame of the next (otherwise one set of lines would get drawn twice) you may find that the lines are not left quite where you want them to be.

This is not a problem, as there is a very simple solution. It involves you having one extra frame which consists of all the lines simply made into a single dot which you put somewhere out of the way. You then animate from frame one to frame two, but you want frame two to stay behind. Now animate to the extra frame in one step choosing which lines you want to remain. As the first animation of frame two is also the last, it stays exactly where you want it. You can now either animate to your next frame in one step with or without erasing the lines, or you can animate with as many steps as you want, and on with your cartoon.

When you are choosing which of your lines to be erased or not erase, remember that you are choosing which lines remain of the *previous* frame when it moves to the present one, which is the one you see on the screen.

Saving a frame

When you have everything to your satisfaction you can press ESC ESC and type GOTO 2150. You will then be asked the number of lines you initially selected and the number of frames. This is the total number so if you only used 1, 5, 10, 3 out of the 10 you may have designed then enter 10 and not four or you will lose some of them. The routine at 2150 will give you the start and length of code to use in a save command.

```
SAVE "THING.BIN",b,14993,3330
```

You then only need to type:

```
MEMORY 14000:LOAD "THING.
BIN":LOAD "DESIGNER"
```

to continue where you left off. If you only want to watch your masterpiece animating then you can type in, save and run the very small Program Four, which you will notice is the same as lines 2120-2140 of the main designer. Alternatively you could also do GOTO 2120 but then you need the whole designer in memory.

Well, that's all about how to use the program, now for those of you who are interested, is a brief description of how the routine works. As I explained the month before last:

X starting coordinate=100,
Finishing coordinate=150
Number of steps=10: (150–100)/10=5 pixels each step.
X starting coordinate=100
Finishing coordinate=155
Number of steps=10: (155–100)/10=5.5 pixels each step.

In machine code you can't move by 0.5 of a pixel or any other fractions of pixels, so they get lost and at the end of the animation the frame would be 10 * 0.5 = 5 pixels out from where it should be. But if you have another counter in your machine code that stores the decimal fraction and increases the coordinates whenever a whole number is formed, then everything will be fine.

Storing the fraction to one decimal place is enough for reasonable accuracy, but because 16 is a round binary number you can get two nibbles of four bits in one byte. This gives an accuracy 16 times better than using integers. All the calculations are made in Basic, the offsets are calculated to add to each position, and each time around the loop the coordinates are increased when the value held in the nibble goes over the half byte in size, keeping the line accurate.

I said in the previous article that I would get the data for each line down from 16 bytes to six, but with all the features I have added, such as different pens, the floating/fixed point and various other little obstacles, the 16 bytes that the program required grew to 25. However I managed to get this com-

I Initialise a frame with random dots in the centre of the screen.

S Slide a line or a whole frame around the screen, enter an inc/decrement in the x and y co-ordinates.

M Magnify a line. Give a number greater than one to enlarge, between zero and one to shrink a line, and a negative number to reverse its direction.

P Pen. Select a new pen colour, just as in Basic.

A Angle to rotate through. The angle is calculated from the start of the line. Use Flip to rotate from other end.

C Copy a whole frame to the present one.

F Flip a line. Make the line draw from the other end. It doesn't look any different but will make a line spin when animating.

T Tie frames together. Defines the order in which to animate the frames and the number of steps/lines to go through/draw. Putting a zero as the last frame will run from start to finish and then stop. Putting 999 as your last frame will cause it to go in a continuous loop. Bear in mind when putting in a zero that if you select 1, 2, 3, 4, 1, 0 it will animate to the second-to-last animation of frame two and then stop. It will never get to the others because of the zero, but 1, 2, 3, 4, 1, 999 is valid. If you really want to go 1, 2, 3, 4, 1, 0 then copy frame one to frame five and do 1, 2, 3, 4, 1, 0 then copy frame one to frame five and do 1, 2, 3, 4, 5, 0 instead.

E Erase flags. Use this if you have previously selected certain lines in a frame not to be erased and you want to change your mind, or copy it to another frame where you do want the lines, or other lines to be erased.

R Return to Editor. If you change your mind when you select the Options menu.

Summary of Editor commands

pressed down to 12, which is not too bad.

Each line in a frame uses 12 bytes, each frame consists of the number of lines plus one extra space for a line that is not used. The first two bytes point to the front of the frame, the next byte points to the next frame number, and the fourth byte contains the number of lines to be animated in the frame. The last eight bytes are not used.


The two bytes before the first frame contain the maximum number of lines in a frame, and the number of the first frame to animate. They don't have to be in order or even start at the first one. This is called a linked list where each item leads to another one. As you have about 20k available for frames, you can calculate the maximum number of frames by using the formula:

20000/(12*(number of lines +1))

A 10 line frame uses 132 bytes, so 20000/132 will allow 151 frames. Some animations look better if a delay is inserted between frames. To do this put a FOR-NEXT loop in line 2130 between the two CALL instructions:

. . . . . :CALL 14993:FOR z=0 to 300:NEXT z:CALL 20000: . . . . .

I hope you have as much fun using this program as I did writing and using it, I am sure you will.



```
10 'Program 1.                                          1010 DATA 0A,A7,C8,47,F3,C5,CD,A7, 1260
20 'ANIMATOR CODE GENERATOR                             1020 DATA 3A,C1,10,F9,FB,C9,DD,21, 1222
30 'BY CHRIS WOOD FOR ACU 4/2/85                        1030 DATA 6F,3D,06,08,C5,DD,22,11, 655
40 '                                                    1040 DATA 3B,CD,C2,3A,DD,2A,11,3B, 855
50 MEMORY 14000:h=14993:DIM s(8)                        1050 DATA 01,19,00,DD,09,C1,10,EC, 701
60 lin=1000:add=h:FOR t=1 TO 936 STEP 8                 1060 DATA C9,AF,32,8C,3C,CD,F0,3A, 1129
70 chk=0:FOR b=0 TO 7                                   1070 DATA CD,6D,3C,CD,F0,3A,CD,78, 1202
80 READ a$:a$=UPPER$(a$):n=1                            1080 DATA 3C,DD,2A,11,3B,CD,02,3B, 665
90 IF LEN(a$)<>2 THEN GOTO 240                          1090 DATA DD,2A,11,3B,DD,7E,18,32, 760
100 b$=MID$(a$,n,1)                                     1100 DATA 8C,3C,CD,F0,3A,CD,6D,3C, 1077
110 GOSUB 220:IF a=0 THEN GOTO 240                      1110 DATA CD,F0,3A,CD,78,3C,C9,DD, 1310
120 n=n+1:IF n=2 THEN GOTO 110                          1120 DATA 5E,00,DD,56,01,DD,6E,02, 735
130 p=VAL("&"+a$):POKE add,p                            1130 DATA DD,66,03,01,04,00,DD,09, 561
140 add=add+1:chk=chk+p                                 1140 DATA C9,06,04,C5,CD,13,3B,01, 692
150 s(b+1)=s(b+1)+p                                     1150 DATA 02,00,DD,09,C1,10,F4,C9, 886
160 NEXT b: READ a                                      1160 DATA 1E,3E,DD,5E,00,DD,56,01, 715
170 IF a<>chk THEN GOTO 240                             1170 DATA DD,6E,08,DD,66,09,19,DD, 917
180 PRINT "Line";lin;"OK":lin=lin+10                    1180 DATA 7E,10,47,DD,7E,11,80,47, 776
190 NEXT t:FOR n=1 TO 8:READ a                          1190 DATA E6,0F,DD,77,10,78,FE,10, 991
200 IF s(n)=a THEN NEXT:END                             1200 DATA 38,01,23,DD,75,00,DD,74, 767
210 PRINT"VERTICAL CHECK ERROR":END                     1210 DATA 01,C9,CD,11,BC,47,3E,02, 747
220 a=INSTR("0123456789ABCDEF",b$)                      1220 DATA 90,32,6C,3C,FD,21,6C,42, 822
230 RETURN                                              1230 DATA 3A,AC,3A,47,C5,DD,22,11, 828
240 PRINT"ERROR in Line";lin:END                        1240 DATA 3B,CD,67,3B,DD,2A,11,3B, 765
1000 DATA DD,21,6F,3D,C3,3B,3B,3E, 801                  1250 DATA 01,19,00,DD,09,01,0C,00, 269
```

Listing I

STOP PRESS

8256 MEMORY/RAM DISC UPGRADE TO 368k £60

EXPANDABLE INTERFACE FOR THE AMSTRAD CPC 464/664/6128

DUAL RS232 – FULL EXPANDABLE INTERFACE (For Modems, Printer, Touchpad)
2 Ports – 25 Pin Socket with Modem Handshake Signals 5 Pin Domino, uses BBC Serial Cable. Dual RS232, 8 Bit Printer Port, 8 Bit Parallel 1/0 User Port, Software on Rom, 2 × Sideways Rom Sockets. **£89.00**

CPM FILE TRANSFER SOFTWARE
To enable file transfer from Apricot, IBM, Mainframe, many other CPM Machines. Also enables use of Telecom Gold, Micronet and other information systems.

TIMDISC 5¼" 2nd DISK DRIVE
Software Portability, can read and write S/S CPM Disks for IBM and Compatibles (156K).
(Please specify for 464/664 or 6128 **£149.00**
Also Available 3" Second Drive **£89.00**
New 1MB 5¼" Disc Drive (6128) **£249.00**
includes multi format software.
8256 2nd Drive **£159 + VAT**

X ROM EPROM PROGRAMME/SIDEWAYS ROM CARD
464/664/6128 with 4 × Sideways ROM sockets – Programmes 2764 and 27128 Eproms **£69.00**

8256 in stock **6128 in stock**

OVER 500 AMSTRAD CASSETTE TITLES OVER 200 NOW ON DISK IN STOCK.

FULL BUSINESS SOFTWARE RANGE includes:
6128, 8256, Software - Inc - Wordstar, £119.00

Neword	£69.95		
Supercalc II	£49.95	Sage Popular Accounts	£99.95
Cardbox	£99.95	Sage Payroll	£69.95
Turbo Pascal	£69.00	Cash Trader	£114.95
Nevada Fortran	£39.95	Camsoft Payroll	£39.00
Cobol	£39.95	Database	£39.00
Pascal	£39.95	Invoicing	£39.00
Dr. Pascal	£49.95	Brainstorm	£49.95
Quest ABC, Business Suite	£149.95	Touch and Go	£29.00

Many other Titles in Stock, Please enquire.

SIDEWAYS ROM

Arnor Maxam Assembler on Rom	£49.00
Arnor Maxam Rom (Fits Timatic Interface)	£39.00
Arnor Disc Utility on Rom	£29.95
Arnor Word Processor on Rom	£39.95
MicroPro Rom Card	£39.00
MicroPro Programmers Toolkit Rom	£39.00
Prestel Rom (Fits Timatic Interface)	£19.95

All the latest games as soon as released.
Speech Synthesizers – From **£29.95**

TAPE TO DISC TRANSFERS
MODEMS, CPC 464, CPC 664, CPC 6128, PRINTERS
AMSTRAD RS 232 – **£49.00**
8256 – RS232/CENT – £59.00 + VAT

Please send sae for full list to:


Mail order welcome, All Prices include VAT.

TIMATIC SYSTEMS LTD

DEALER ENQUIRIES WELCOME

FAREHAM MARKET
FAREHAM, HANTS
Tel: FAREHAM (0329) 236727
(0329) 239953

TRANSFORM LTD. Amstrad



COMPUTER AND MONITOR

Amstrad 464 64k complete with green monitor and cassette	**£199.00p**
Amstrad 464 64k complete with colour monitor and cassette	**£299.00p**
Amstrad 6128 128k complete with green monitor and disc	**£299.00p**
Amstrad 6128 128k complete with colour monitor and disc	**£399.00p**
Amstrad 8256 complete with green monitor and disc	**£458.85p**

JUMBO BOX
£17.00
HOLDS 40
ADD £1.00

£13.25
ADD £1 P&P



- 3" Disc storage Box
- Holds 20 3" discs
- Lockable
- Brown with tinted removable lid

WORDPROCESSING

TASWORD D 464-664-6128
Wordprocessing program complete with full screen prompts and tutor. This program will allow you to produce letters forms etc fully compatible with all printers. Features include page numbering, search and find, search and replace, block copy, block move and mail merge. The tutor will give full training on the use of the above functions.

CASSETTE without mail merge **£19.95p**
DISC **£24.95p**

TASPRINT
The Tasword style writer allows you to print 5 extra fonts with dot matrix printers including COMPACTA bold and heavy for emphasis, DATA-RUN a futuristic script LECTRA LIGHT clean and pleasing to read Median a serious business like script, Palace Script a distinctive flowing font.

CASSETTE ..... **£9.90p** **DISC** **£12.90p**

TAS SPELL
This is a spelling checker for Tasword D word-processor. The dictionary contains 20,000 words and grows as you use it, simply select the "K" option the Tasword menu.

DISC **£16.50**

SCREEN COPIES

TASCOPY
This program will allow you to copy your screen with shaded printing, including poster size screen copies using 2 or 4 sheets.

CASSETTE ..... **£9.90p** **DISC** **£12.90p**

DATABASES

MASTERFILE
This database has set the standard for micro computers. With 100% machne code it will allow 240 characters per field 40 fields record 34000 characters per file. This will enable you to keep a record of 500 full names and addresses. Features include full search facilities, sort in ascending or descending order, column totals, 1 or 22 records per screen.

CASSETTE ..... **£21.25p** **DISC** **£25.45p**

MASTERFILE EXTENSION
For those who want to stretch Masterfile, this packed import, export files to Tasword, merge files, data handling and many other features allowing calculations between fields etc.

CASSETTE ..... **£9.95p** **DISC** **£13.95p**

DISC-DRIVES

Disc drive without controller	**£99.00p**
Disc drive complete with controller	**£159.00p**

SPREAD SHEET

MASTERCALC
Spread sheet program from the same software house as Masterfile. Features include 3000 cells 8 byte floating precision 40-80 column display, direct totals and sub totals 3 bar histograms, cursor direction keys, add or delete columns-rows high resolution screen copies on Epson compatible printers.

CASSETTE ..... **£21.25p** **DISC** **£25.45p**

MASTERCALC EXTENSION
Allows you to transfer data from MasterCalc to Tasword and user access to MasterCalc data.

CASSETTE ..... **£9.95p** **DISC** **£13.95p**

PRINTERS


	Ex VAT	Inc VAT
DOT MATRIX		
Brother M1009	**£163.00p**	**£187.45p**
Epson LX80	**£199.00p**	**£228.85p**
Taxan Kaga KP810	**£250.00p**	**£287.50p**
DAISY WHEEL PRINTERS		
Brother HR10	**£245.80p**	**£282.67p**
Brother HR15	**£349.00p**	**£401.35p**

Please add £5.75p delivery.

PCW8256·6128 SOFTWARE

Sage popular Accounts	**£99.99**
Sage popular Payroll	**£69.99**
Payroll with Accounts	**£149.99**
Supercalc 2	**£49.95p**
Sales Ledger Invoicing, Stock Control	**£84.15p**
Purchase Ledger	**£28.05p**
Nominal Ledger	**£28.05p**

£199.00
plus VAT



EPSON LX80

- Near Letter Quality
- 100 characters per second
- 1k buffer
- Friction feed
- Tractor feed (optional extra)
- Sheet feed (optional extra)

MEMORY EXTENSION

Extend your 464/664 to 6128 with this memory extension **£49.95**

DISPLAY LANGUAGE

DLAN
Advertise your products, services with this program by Campbell Systems. The print facility allows you to produce leaflets, labels, menus using 15 different fonts.

DISPLAY LANGUAGE

CASSETTE ..... **£9.95p** **DISC** **£13.95p**

ACCESSORIES

ACCESSORIES

Centronics Lead	**£9.90p**
3" discs	**£4.95p**
Modulator	**£29.95p**
RS 232 interface	**£49.95p**
Epson LX 80 tractor feed	**£20.70p**
Epson sheet feed	**£55.00p**
M1009 tractor feed	**£15.18p**
M1009 roll holder	**£7.18p**

Mail Order Only

Access

TRANSFORM LTD (Dept.**AU**) 01-658 6350
24, West Oak, Beckenham, Kent BR3 2EZ

VISA

```
10 REM PROGRAM 2
20 REM DEMO PROGRAM FOR ANIMATOR
30 REM BY CHRIS WOOD FOR ACU 4/2/86
40 RANDOMIZE 1
50 NUM=5:POKE 15020,NUM
60 st=10:fp=16:addr=17004:DTST=15727
70 FOR W=1 TO NUM:PENS=(W MOD 16)
80 GOSUB 300
90 XC=A+1024*PENS+((64*256) AND YSN<>0):
   IF XSN<>0 THEN XC=XC+128*256
100 yc=b+256*(g*16+h)
110 xyst=e+256*f
120 num=xc:GOSUB 370
130 POKE addr,lo:POKE addr+1,hi
140 num=yc:GOSUB 370
150 POKE addr+2,lo:POKE addr+3,hi
160 num=xyst:GOSUB 370
170 POKE addr+4,lo:POKE addr+5,hi
180 GOSUB 300
190 XC=A+1024*G:IF XSN<>0 THEN XC=xc+128
    *256
200 YC=B+1024*H:IF YSN<>0 THEN YC=YC+128
    *256
210 XYST=e+256*f
220 num=xc:GOSUB 370
230 POKE addr+6,lo:POKE addr+7,hi
240 num=yc:GOSUB 370
250 POKE addr+8,lo:POKE addr+9,hi
260 num=xyst:GOSUB 370
270 POKE addr+10,lo:POKE addr+11,hi
280 ADDR=ADDR+12:DTST=DTST+17:NEXT
290 CALL 14993:POKE 15001,ST:CALL 15000:
    GOTO 50
300 A=PEEK(DTST)+256*PEEK(DTST+1)
310 B=PEEK(DTST+2)
320 DTST=DTST+4
330 C=INT(RND*639)+1:D=INT(RND*199)+1
340 e=(c-a)/st:f=(d-b)/st:xsn=(e<0):ysn=
    (f<0)
350 g=INT((e-INT(e))*fp):h=INT((f-INT(f)
    )*fp)
360 e=ABS(INT(e)):f=ABS(INT(f)):RETURN
370 hi=INT(num/256):lo=num-(hi*256):RETU
    RN
```

Listing II

```
10 REM PROGRAM 4
20 REM FRAME ANIMATION EXECUTION PROGRAM
30 REM BY CHRIS WOOD FOR ACU 4/2/86
40 start=17004:CLS:A=PEEK(START-1):LINES
   =PEEK(START-2)
50 IF A<>0 THEN ADDR=(START+12*(LINES+1)
   *A)-12:POKE 15175,PEEK(ADDR):POKE 151
   76,PEEK(ADDR+1):POKE 15001,PEEK(ADDR+
   3):POKE 15020,PEEK(addr+4):CALL 14993
   :CALL 15000:A=PEEK(ADDR+2):GOTO 50
60 END
```

Listing IV

```
10 REM PROGRAM 3
20 REM FRAME DESIGNER PROGRAM
30 REM BY CHRIS WOOD FOR ACU 4/2/86
1000 INPUT "WHICH MODE";MD
1010 INPUT "HOW MANY LINES";LINES:IF LIN
     ES>50 OR LINES<1 THEN GOTO 1010
1020 MODE MD:POKE 15020,LINES:START=1700
     4:POKE (START-2),LINES:FRM=1:GOSUB
     1620
1030 GOSUB 1530:LOCATE 10,25:PRINT"ON ":
     DEG
1040 LOCATE 1,24:PRINT CHR$(246);CHR$(31
     );CHR$(10);CHR$(24);CHR$(244)
1050 st=32:fp=16:
1060 DR2=DR
1070 GOSUB 1410:' READ KEYS
1080 IF DR<>DR2 THEN GOSUB 1570
1090 C=0:D=0
1100 A=AA:B=BB
1110 IF DR=0 THEN GOSUB 1150 ELSE GOSUB
     1260
1120 PLOT AA-3,BB*2,1:DRAWR 7,0:PLOT AA,
     BB*2-3:DRAWR 0,7
1130 IF DLN=0 THEN LOCATE 2,24:PRINT AA;
     " ":LOCATE 11,24:PRINT BB*2;" ":LOC
     ATE 1,25:PRINT LNUM+1:LOCATE 5,25:P
     RINT FRM+1:CALL 14993
1140 GOTO 1060
1150 GOSUB 1370
1160 XC=A+1024*PENS+((64*256) AND YSN<>0
     ):IF XSN<>0 THEN XC=XC+128*256
1170 yc=b+256*(g*16+h)
1180 xyst=e+256*f
1190 num=xc:GOSUB 1400
1200 POKE addr,lo:POKE addr+1,hi
1210 num=yc:GOSUB 1400
1220 POKE addr+2,lo:POKE addr+3,hi
1230 num=xyst:GOSUB 1400
1240 POKE addr+4,lo:POKE addr+5,hi
1250 RETURN
1260 GOSUB 1370
1270 XC=A+1024*G:IF XSN<>0 THEN XC=xc+12
     8*256
1280 YC=B+1024*H:IF YSN<>0 THEN YC=YC+12
     8*256
1290 XYST=e+256*f
1300 num=xc:GOSUB 1400
1310 POKE addr+6,lo:POKE addr+7,hi
1320 num=yc:GOSUB 1400
1330 POKE addr+8,lo:POKE addr+9,hi
1340 num=xyst:GOSUB 1400
1350 POKE addr+10,lo:POKE addr+11,hi
1360 RETURN
1370 e=(c-a)/st:f=(d-b)/st:xsn=(e<0):ysn
     =(f<0)
1380 g=INT((e-INT(e))*fp):h=INT((f-INT(f
     ))*fp)
1390 e=ABS(INT(e)):f=ABS(INT(f)):RETURN
1400 NUM=INT(NUM):hi=INT(num/256):lo=num
     -(hi*256):RETURN
1410 PLOT AA-3,BB*2,0:DRAWR 7,0:PLOT AA,
     BB*2-3:DRAWR 0,7
1420 AA=(AA+(1 AND INKEY (1)<>-1)+(15 AN
     D INKEY (1)=32) AND AA<640)
1430 AA=(AA-(1 AND INKEY (8)<>-1)-(15 AN
     D INKEY (8)=32) AND AA>0)
1440 BB=(BB+(1 AND INKEY (0)<>-1)+(7 AND
      INKEY (0)=32) AND BB<200)
1450 BB=(BB-(1 AND INKEY (2)<>-1)-(7 AND
      INKEY (2)=32) AND BB>0)
1460 IF INKEY(34)<>-1 THEN GOTO 1650
1470 IF INKEY (9)<>-1 THEN DR=(DR=0)
1480 IF INKEY(31)<>-1 AND LNUM<>LINES-1
     THEN ADDR=ADDR+12:LNUM=LNUM+1:GOTO
     1530
1490 IF INKEY(39)<>-1 AND LNUM<>0 THEN A
     DDR=ADDR-12:LNUM=LNUM-1:GOTO 1530
1500 IF INKEY(47)<>-1 THEN DLN=(DLN=0):L
     OCATE 10,25:IF DLN=0 THEN PRINT"ON
     " ELSE PRINT"OFF"
1510 IF INKEY(18)<>-1 THEN GOSUB 1600
1520 RETURN
1530 A1=PEEK(ADDR)+256*((PEEK(ADDR+1)) A
     ND 3):B1=PEEK(ADDR+2)
1540 C1=PEEK(ADDR+6)+256*((PEEK(ADDR+7))
      AND 3):D1=PEEK(ADDR+8)
1550 pens=(PEEK(addr+1) AND 60)/4
1560 AA=A1:BB=B1:DR=0:DR2=DR:GOTO 1520
1570 IF DR=0 THEN GOTO 1590
1580 A1=AA:B1=BB:AA=C1:BB=D1:RETURN
1590 C1=AA:D1=BB:AA=A1:BB=B1:RETURN
1600 WINDOW #1,1,80,25,25:CLS #1
1610 INPUT #1,"WHICH FRAME NOW";FRM:IF F
     RM=0 THEN GOTO 1600
1620 FRM=FRM-1:ADDR=START+12*(lines+1)*F
     RM:NUM=ADDR:GOSUB 1400
1630 CLS #1
1640 POKE 15175,LO:POKE 15176,HI:LNUM=0:
     GOTO 1530
1650 WINDOW #1,1,80,25,25:CLS #1
1660 PRINT #1,"I,S,M,P,A,C,F,T,E-R"
1670 K$=INKEY$:IF K$<>"" THEN GOTO 1670
1680 A$=INKEY$:IF A$="" THEN GOTO 1670
1690 A$=UPPER$(A$):SP=INSTR("ISMPACFTER"
     ,LEFT$(A$,1)):IF SP=0 THEN GOTO 165
     0
1700 CLS #1:ON sp GOTO 1710,1730,1820,19
     00,1860,1910,1930,1940,1850,1840
1710 FOR n=1 TO lines:a=INT(RND*20)+320:
     b=INT(RND*10)+100
1720 pens=1:GOSUB 1150:GOSUB 1260:addr=a
     ddr+12:NEXT:FRM=FRM+1:GOTO 1620
1730 CLS #1:INPUT #1,"ALL OR ONE (A/O)";
     A$:A$=UPPER$(A$+" ")
1740 SP=INSTR("OA",LEFT$(A$,1)):IF SP=0
     THEN GOTO 1730
1750 ON sp GOTO 1760,1800
1760 GOSUB 1810
1770 GOSUB 1530:a1=a1+xi:b1=b1+yi:c1=c1+
     xi:d1=d1+yi:GOSUB 1560
1780 a=a1:b=b1:GOSUB 1150:a=c1:b=d1:GOSU
     B 1260
1790 RETURN
1800 GOSUB 1810:ADDR=START+12*(lines+1)*
     FRM:FOR n=1 TO lines:GOSUB 1770:add
     r=addr+12:NEXT:FRM=FRM+1:GOTO 1620
1810 CLS #1:INPUT #1,"x inc/decrease";xi
     :CLS #1:INPUT #1,"y inc/decrease";y
     i:CLS #1:RETURN
1820 CLS #1:INPUT #1,"MAGNIFICATION";MM:
     IF MM=0 THEN GOTO 1820
1830 CLS #1:GOSUB 1530:X1=C1-A1:Y1=D1-B1
     :C1=A1+(X1*MM):D1=B1+(Y1*MM):GOSUB
     1560:GOTO 1780
1840 CLS #1:RETURN
1850 ADDR=START+12*(LINES+1)*FRM:FOR W=1
      TO LINES:GOSUB 1530:GOSUB 1780:ADD
     R=ADDR+12:NEXT:RETURN
1860 CLS #1:GOSUB 1530:X1=ABS(A1-C1):Y1=
     2*(ABS(B1-D1)):X1=X1*X1:Y1=Y1*Y1:Z1
     =SQR(X1+Y1)+0.5
1870 CLS #1:INPUT #1,"ANGLE ";ROT:IF ROT
     <0 OR ROT>360 THEN GOTO 1870
1880 CLS #1:C1=A1+INT(Z1*COS(ROT)):D1=B1
     +INT((Z1*SIN(ROT))/2)
1890 GOSUB 1560:GOTO 1780
1900 CLS #1:INPUT #1,"WHICH PEN";pp:GOSU
     B 1530:pens=pp MOD 16:GOSUB 1150:CL
     S #1:RETURN
1910 CLS #1:INPUT #1,"COPY FRAME";CC:IF
     CC=0 THEN GOTO 1910
1920 CC=CC-1:LNUM=0:ADDR=START+12*FRM*(L
     ines+1):NUM=START+12*CC*(lines+1):F
     OR N=0 TO 12*LINES:POKE ADDR+N,PEEK
     (NUM+N):NEXT:CLS #1:GOTO 1530
1930 CLS #1:GOSUB 1530:TA=A1:TB=B1:A1=C1
     :B1=D1:C1=TA:D1=TB:GOSUB 1560:GOTO
     1780
1940 CLS:INPUT "FIRST FRAME   (ENTER TO
     RETURN)";F:IF F=0 THEN CLS:RETURN
1950 CLS:PRINT F;:POKE START-1,F:FIRST=S
     TART+12*(LINES+1)*(F-1):STORE=(STAR
     T+12*(LINES+1)*F)-12
1960 NUM=FIRST:GOSUB 1400:POKE 15175,LO:
     POKE 15176,HI:CALL 14993:WINDOW #1,
     1,80,23,25
1970 CLS #1:INPUT #1,"WHICH FRAME NEXT
      (0 TO FINISH 999 FOR CONTINUOUS)"
     ;NFR
1980 SECOND=START+12*(LINES+1)+(NFR-1):N
     UM=FIRST:GOSUB 1400:POKE STORE,LO:P
     OKE STORE+1,HI:IF NFR=999 THEN GOTO
      2120
1990 POKE STORE+2,NFR
2000 IF NFR=0 THEN GOTO 2120
2010 CLS #1:INPUT #1,"HOW MANY STEPS";ST
     :POKE STORE+3,(ST-1)
2020 CLS #1:INPUT #1,"HOW MANY LINES
     (0 FOR ALL)";TNL:IF TNL=0 THEN TNL=
     LINES
2030 POKE STORE+4,(TNL MOD (LINES+1))
2040 CLS #1:INPUT #1,"ERASE LINES    (0
     FOR ALL)";ELN
2050 PRINT NFR;:CLS #1:PRINT#1,"   CALCU
     LATING"
2060 TEMP=SECOND:NUM=SECOND:GOSUB 1400:P
     OKE 15175,LO:POKE 15176,HI:CALL 149
     93:FOR W=1 TO LINES
2070 addr=first:GOSUB 1530:a=a1:b=b1:add
     r=second:GOSUB 1530:c=a1:d=b1:addr=
     first:GOSUB 1150
2080 addr=first:GOSUB 1530:a=c1:b=d1:add
     r=second:GOSUB 1530:c=c1:d=d1:addr=
     first:GOSUB 1260:EF=PEEK(FIRST+7):P
     OKE FIRST+7,(EF AND 191)
2090 IF ELN<>0 THEN PRINT#1,w;:INPUT #1,
     "ERASE THIS ONE (Y/N)";E$:E$=UPPER$
     (E$+" "):IF LEFT$(E$,1)="N" THEN EF
     =PEEK(FIRST+7):POKE FIRST+7,(EF OR
     64)
2100 first=first+12:second=second+12:NEX
     T:FIRST=TEMP:STORE=(START+12*(LINES
     +1)*NFR)-12
2110 GOTO 1970
2120 start=17004:CLS:A=PEEK(START-1):LIN
     ES=PEEK(START-2)
2130 IF A<>0 THEN ADDR=(START+12*(LINES+
     1)*A)-12:POKE 15175,PEEK(ADDR):POKE
      15176,PEEK(ADDR+1):POKE 15001,PEEK
     (ADDR+3):POKE 15020,PEEK(addr+4):CA
     LL 14993:CALL 15000:A=PEEK(ADDR+2):
     GOTO 2130
2140 END
2150 INPUT "NUMBER OF LINES";LINES
2160 INPUT "NUMBER OF FRAMES";FRM
2170 PRINT 14993,(17003+12*(LINES+1)*FRM
     )-14993
```

Listing III

Kuma

Serious software on Disc and Cassette for the Amstrad CPC464, 664, 6128 microcomputers.

DATAFILE II

The powerful, user friendly Database.
Disc £19.95 Cassette £14.95

- ★ Menu driven – easy to use
- ★ 20, 40 or 80 characters per line
- ★ Variable file and field size
- ★ High speed search, sort and find options
- ★ Label, Summary and dump print options
- ★ HELP menu available at all times

STOCK CONTROL and INVOICING

Disc £29.95

- ★ 1000 records on single disc (1500 on double)
- ★ Linked invoicing facility
- ★ Re-order, stock and stock value reports
- ★ Buying and selling price lists
- ★ Current stock level and value

MUSIC MINSTREL

High quality Music Composition program.
Disc £19.95 Cassette £14.95

- ★ Menu driven – easy to use
- ★ 150 pages of music with 16 chords per page
- ★ Musical features include slurs, crescendos and accelerandos
- ★ Keys can be changed during the course of a musical piece

Kuma FORTH

A comprehensive implementation of FIG FORTH with many added features.
Disc £24.95 Cassette £19.95

- ★ Floating point
- ★ Genuine cursor controlled Screen Editor
- ★ Virtual memory system for both tape and disc versions
- ★ Support for RS232 interfaces
- ★ Colour Graphics and Sound ★ Function key support

ARTWORK

An easy-to-use but powerful Graphics design package.
Disc £16.95 Cassette £9.95

- ★ Line, Box, Circle and Ellipse routine
- ★ Screen may be scrolled in any direction
- ★ Useful HELP option available at any time
- ★ Fast fill option ★ Text mode for diagram labels

BRIDGE

A challenging version of Contract Bridge.
Disc £13.95 Cassette £8.95

- ★ Stayman and Blackwood conventions
- ★ Helpful screen layout and prompts
- ★ Single key operation for highest and lowest
- ★ Fast reaction time – no annoying pauses in play

HERCULE

Exceptionally friendly O-level French teaching program.
Cassette only £8.95

- ★ 500 word and phrase vocabulary for translation
- ★ Automatic random retest for wrong answers
- ★ Exceptionally user friendly
- ★ An invaluable revision aid for all O-level students

ARGO NAVIS

Disc £12.95 Cassette £6.95

Your spaceship has been overrun by aliens and your only hope of survival is to collect and set the twelve self-destruct bombs deep in the heart of the vessel, return to the airlock and escape to safety. Sounds easy, doesn't it? – but beware – this exciting, addictive, multi-scenario game abounds with hidden dangers both inside and outside the ship!

RENEGADE

Disc £12.95 Cassette £6.95

You must negotiate your way through a large, heavily guarded maze to steal a priceless jewel, hidden on the tenth level. Having reached this crystal you must fight your way back out of the maze to ensure your ultimate revenge. A superb multi-level, addictive game with lots of devious surprises!

CREDIT CARD HOTLINE 07357 4335

Please send me:

	Disc	Cass.	Qty	Total
DATAFILE II				
STOCK CONTROL				
MUSIC MINSTREL				
BRIDGE				
ARTWORK				
Kuma FORTH				
HERCULE				
ARGO NAVIS				
RENEGADE				

TOTAL PAYABLE _____

Send to: Kuma Computers Ltd, 12, Horseshoe Park, PANGBOURNE, Berks RG8 7JW

Name .....
Address .....
(to agree .....
with credit .....
card account) ..... Post code .....

Cheque enclosed for £ ..... Or charge my ACCESS/BARCLAYCARD A/c. ☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐

Signed ..... Expiry date of card .....

Arnor Ltd

PROTEXT

FOR AMSTRAD 464/664, 6128

THE ULTIMATE AMSTRAD WORD PROCESSOR!!

PROTEXT is without doubt the most sophisticated word processor you will find on any home micro. It is of comparable standard to business packages costing over £200 but has been developed for the AMSTRAD 464/664 and 6128 machines and is 100% machine-code. We know that PROTEXT is the fastest program of its type currently available (eg global search and replace on a three page file in under a second!). Bearing in mind the range of features included and their ease of use, this package is rightly acclaimed as the No. 1 word processor for Amstrad owners. Compare these features and benchmarks with any other similar products.

PROTEXT FEATURE SUMMARY

File commands – Super fast Load, Merge and Save, Cat, Print (to printer/screen/file).
Cursor Movement – By character/word/line/paragraph/screen, to start or end of line, to start or end of text, to line number, to place marker, to margin.
Inserting and deleting – Insert/overwrite mode, insert character or line, delete character forwards or backwards, delete word.
FIND and REPLACE – Wildcards, all or part of text, case specific, whole word or part of word, find control codes.
Block commands – Move/copy/delete/save/print/format.
Markers – 2 block markers and 10 place markers may be set anywhere.
Formatting – Word wrap, right justify, variable left and right margins.
Ruler lines – Unlimited number of ruler lines to define margins and tabs.
Print options – Headers/footers, page numbers, variable line spacing, variable page length and margin sizes, conditional page throws, odd and even page features, continuous or single sheets, multiple copies.
Printer features – Including emphasised, condensed, double-strike, elite, italics, enlarged, pica, NLQ, subscript, superscript, underline. Built in Epson printer driver. Ability to easily define your own printer driver and save to disc.
Help features – Optional on screen command summaries.
Built in character sets – Danish/French/German/Italian/Spanish/Swedish.
Other features – Non break space, display tabs, returns and hard spaces, soft hyphens, word count, case conversion, copy ruler. 40 page easy to read manual with full index and glossary of terms.

BENCHTESTS

A standard file of 775 words (4,785 characters) was used to carry out the following benchtests (all timings are in seconds):

	PROTEXT	TASWORD/AMSWORD
1 LOAD text file	4.7	10.2
2 SAVE text file	4.9	18.9
3 Re-FORMAT paragraph (85 words)	0.4	15.3
4 Re-FORMAT entire text	2.5	Not Possible
5 Move directly to start of text	under 0.1	2.2
6 Move directly to end of text	0.2	2.2
7 REPLACE 'the' with 'THE' (45 occurances)	1.7	34.1
8 SCAN entire text	2.2	7.2
9 MERGE file to centre of text	4.0	Not Possible
10 MERGE file to end of text	3.8	12.4
11 MOVE 85-word paragraph	under 0.1	6.8
12 PROGRAM LOAD TIME DISC ROM	12.9 Instant	14.6 Not Available

"I AM STUNNED AT PROTEXT — IT KNOCKS POCKET WORDSTAR INTO A COCKED HAT" — AMTIX ISSUE 1
"DON'T MISS IT. IT IS SUPERB" — POPULAR COMPUTING WEEKLY
"MILES AHEAD OF THE AMSWORD TYPE PROGRAMS" — AMSTRAD USER

NOW TWO POWERFUL NEW ADDITIONS TO YOUR WORD PROCESSING SYSTEM:-

PROSPELL

Checks your spelling!
Proof reads your documents

● **Works directly from PROTEXT** ●

A single command brings the spelling checker into action.

Correct errors while viewing the document.

Add new words to dictionary disc either as they occur or all together for extra speed.

PROSPELL works with all ASCII files from other word processors as well.

● **Many Options** ●
Including — add words to dictionary / ignore word / correct spelling / delete words / list words / word count / analysis of words in text / copy dictionary / initialise new dictionary / plus lots more!!

● **Version A . . . PROSPELL on DISC** ●

Thousands of words on dictionary disc.
Add your own words up to around 100,000 per dictionary disc
Any number of dictionary discs can be used

● **Version B . . . PROSPELL on DISC and ROM** ●

Program and dictionary of common words on ROM
Main dictionary on disc.
More text space and incredible speed.
Thousands of words have been packed into 16K ROM for really fast operation.

And you thought PROTEXT was fast!!

PROMERGE+

This major addition to the PROTEXT word processor combines a fully flexible mail merge program allowing PROTEXT to produce individualised documents in one single print run.

(a) COMPREHENSIVE MAIL MERGE

Read data from file or keyboard.
Merged fields of varying lengths are automatically reformatted.
File merge — insert file while printing.
Conditional printing — select from input data (eg you could print letters to all customers whose name is not Smith).
Compatible with Masterfile extension.

(b) PROTEXT ENHANCEMENTS

Background printing — edit one file while you print another.
Print file direct from disc or memory.
Two file editing — switch between two files in memory.
Cut and paste — any block of text can be moved to any position — allows multiple column layout.
Auto configuration — you can set up a disc to configure PROTEXT to your preferred options with a single keystroke.
Typewriter mode — for envelopes etc.
BASIC program editing — direct from memory.
Calculator — a simple on-screen calculator for those invoice totals, etc.

● **6128 OWNERS** ●

These features make full and sensible use of your extra 64K memory but also function with smaller files on the 464 and 664 machines. **DISC £24.95**
ROM £34.95

MAXAM ASSEMBLER

Now recognised as the industry standard assembler/monitor/editor. Used by all the leading software houses, computing magazines and widely used throughout industry.

"This piece of software should be held up as an example of what can be done by programmers who care. It is brilliant."
ELECTRONICS & COMPUTING

"MAXAM is a superb ROM which is recommended for all serious machine code programmers. It contains a powerful assembler and an excellent editor which is a joy to use."
COMPUTING WITH THE AMSTRAD

"ARNOR are to be congratulated on a superb job . . . definitely the best."
HOME COMPUTING WEEKLY

"A product no serious Amstrad user can afford to be without."
YOUR COMPUTER

Why make machine-code difficult?
Why use anything less than MAXAM?

PROTEXT and **MAXAM** are available on cassette, disc, rom and plug-in cartridge.

CASSETTE AND DISC
The inexpensive introduction to the Arnor professional software.
Cassette £19.95 **Disc £26.95**

ROM
For those people who already own a rom expansion box. Just plug in a rom and off you go. Arnor roms are compatible with all other rom boxes.
EPROM £39.95

PLUG IN CARTRIDGE (AD2)
Complete Plug-in-and-go ROM cartridge containing either PROTEXT or MAXAM. NO ROM BOXES REQUIRED! In addition, the cartridge has a thorough connector for further peripherals and an extra socket for expanding the system with our own 4 way rom board. The AD2 cartridge plugs directly into the 464, 664 or 6128, fitting snugly into the expansion port. Fitting a PROTEXT cartridge means that as soon as you switch your Amstrad computer on, PROTEXT is instantly ready and waiting for you to use.

Consider the price of our cartridge system. Just £10 onto the price of the rom software and no extra hardware required. Why pay twice as much to get started?

AD2 cartridge (PROTEXT or MAXAM) with no extra hardware required **£49.95**
4 WAY ROM CARD (plugs into cartridge) **£15.95**

REMEMBER . . . ROM and cartridge software gives you a massive 40K text space!!

UTOPIA

FOR AMSTRAD 464/664, 6128

* EXTEND THE POWER OF YOUR AMSTRAD
* 50 NEW COMMANDS — ONLY £29.95
* CAN YOU WORK WITHOUT THEM?

Written by the author of **MAXAM**, **UTOPIA** is the complete utilities package. Available to both the disc users and BASIC programmers, it inlcudes all the most useful commands you will need to increase the power of your Amstrad. All the commands below are accessible from BASIC, MAXAM or PROTEXT.

* NOW INCLUDES 27 SHADE GRAPHICS SCREEN DUMP

(For Epson/DMP2000 Printers)

DISC UTILITIES

Instantly from BASIC you can perform the following:-

FORMAT	Format a disc
COPY	Copy files (1 or 2 drives)
DELETE	Selective file deletion
LOAD	Load any file to any address (no setting HIMEM)
DUMP) **TYPE)** **LIST)**	Any file to screen

Utopia also contains a very powerful disc editor:-

DEDIT	You can display/change any byte of information on any disc. Essential for saving part of a corrupted disc or restoring deleted files.
DISCOPY	Copy a disc (1 or 2 drives)
ACCESS	Protect/Unprotect Sys/Dir files
INFO	Displays load, exec addresses and file length
SAVE	Save block of memory as binary or ASCII

PLUS MANY OTHER USEFUL COMMANDS

PROGRAMMING UTILITIES

Invaluable commands for BASIC or machine code programmers

FIND	Find any BASIC keyword or ASCII string
REPLACE	As FIND with replace option, Selective or Global
VARS	List all variables
ARRAYS	List arrays
FNS	List functions
CALL	Call machine code routine, allowing setting of registers
MEDIT	Powerful memory editor
MOVE	Move BASIC lines
STATUS	Display info on current BASIC program, eg size, HIMEM etc
TOKENS	Display function key definitions
NOKEYS	Cancel UTOPIA function keys — see below
C	Calculate expression
MDUMP	List memory (hex/ASCII)

PRINTING & FUNCTION KEY COMMANDS

GDUMP	Full 27 shade graphics screen dump for DMP2000 and all Epson compatible printers
PRINTON	Echo all screen output to printer
CDUMP	Very fast character dump from screen to any printer
PRINTOFF	Switch off PRINTON

UTOPIA also sets up the function keys to contain useful definitions, eg:-

CTRL + ENTER	Gives RUN "DISC" if disc drive is fitted
CTRL + f0	Sets colours for 80 column work on colour screens
CTRL + f1	LIST
CTRL + f2	Set to 80 column mode
CTRL + f3	CAT
CTRL + f4-f8	. . . etc
CTRL + f9	Erase backup files

You will be surprised how much time all these function keys will save!!

AND FINALLY

Now you are in the world of ROM software, we have included some extra commands to make your ROMs easier to use.

HELP	List ROMs showing version number and workspace address
HELP,n	List all commands in ROM n
HELPR	List all RSX commands
ROMOFF	Turn off selected ROMs
ROMON	Turn on selected ROMs
U	Execute UTOPIA command
XROM	Execute command in specified ROM

(U and XROM get over the problem of command name duplication)

"A POWERFUL RANGE OF COMMANDS AT A BARGAIN PRICE" — POPULAR COMPUTING WEEKLY

Available from selected branches of

Boots **WHSMITH**

and all good computer stockists, or directly
(Specify machine model)

COMPLETE PRICE LIST

	Cassette	Disc	Eprom	ADS Cartridge
PROTEXT	£19.95	£26.95	£39.95	£49.95
PROMERGE+	—	£24.95	£34.95	—
PROSPELL	—	£24.95	£34.95	—
MAXAM	£19.95	£26.95	£39.95	£49.95
UTOPIA	—	—	£29.95	See AMTIX! Magazine

From: **ARNOR LTD**
THE STUDIO
LEDBURY PLACE
CROYDON CR0 1ET
01-688 6223

24 HOUR CREDIT CARD HOTLINE – ACCESS/VISA VISA

GOING LOCO

By ALEX MARTIN

THIS month I'm taking a break from plodding through the alphabet looking at each keyword, to take a look at strings.

Thin, thick or saisal?

Strings are a computers way of storing text, and many useful things can be done with them.

If you think about it, a sentence is a series of words strung together. And a word is a series of characters strung together. A computer has to have precise information to deal with, it can't handle a sentence of text unless it has all the characters that appear in it. If you were to type the sentence "I'm forever blowing bubbles" on to your computer screen you would be creating a string 27 characters long. It is important to remember that even spaces where no character appears, and also single quote marks and other punctuation symbols, are counted as characters.

Halfer$ makes no cents

Let us now look at string variables. These have ordinary variable names but end in the dollar symbol, for example:

```
a$
bill$
fred$
zap$
```

When you assign a string of characters to a string variable, you do it like this:


```
fred$="Hello my name is Fred"
```

Notice that the actual string is held between two sets of double quotes. This tells the computer that the information between them is a string of data. The Amstrad allows you to omit the second quote mark at the end of a string if the string is the last item in the line.

```
RUN"disc
```

Old strings are a load of garbage

The computer now knows that fred$ contains 21 characters and it stores the string away in memory. The next string created will be placed next to fred$ like a long row of Scrabble letters. If you now



added characters to fred$ like this:

```
fred$=fred$+" Smith"
```

fred$ will no longer fit into its allocated space. When this happens Basic puts fred$ into a new space and marks the old space for deletion. This means that every time you make an assignment such as fred$= a piece of memory is being used up.

As memory fills up and runs out, Basic goes back through all the old strings and deletes them, moving the remaining strings into the reclaimed space. This process is called garbage collection and is the cause of baffling pauses in large programs that make use of a lot of strings.

It can be very annoying to have to wait for quite long periods during a program. Garbage collection can be avoided but this is tricky and you will need to understand the commands and functions to do with strings.

How long is piece of string?

Twice as long as half. Or you can use the command LEN. Try this:

```
PRINT LEN(fred$)
```

and this:

```
PRINT LEN("1234567");LEN(x$)
```

As you can see, LEN returns the number of characters in the various strings. A string with no characters in is called a null string. A null string is often represented as "" and contains 0 characters. The maximum length a string can be is 255 characters long.

Cutting the strings

There are some useful functions to cut out bits of strings. These functions work by allowing you to say which character of the string to begin at and how many characters you want. The result is then assigned to another string.

MID$ is the most important of these. Look at these examples:

```
PRINT MID$("abcdefghijklm",5,3)
PRINT MID$("abcdefghijklm",5)
```

These show various parts of the string being chopped out. The first example takes three characters from the string. The second takes all the characters up to the end of the string.

The two other commands for cutting strings are RIGHT$ and LEFT$. These examples should make it clear how they work:

```
PRINT RIGHT$("abcdefghijklm",5)
PRINT LEFT$("abcdefghijklm",5)
```

Chopping without changing

We've just been looking at ways of making new strings out of old ones. Using MID$ it is possible to alter existing strings without creating a new one. It is worth reminding ourselves about garbage collection at this stage. If we can alter a string without creating a new one we can avoid Basic doing a garbage collection.

In the examples above, MID$, RIGHT$ and LEFT$ end up on the right hand side of the line of program. When MID$ is used on the left it can modify an existing string, for example:

```
a$="abcdef":MID$(a$,2)="123":PRINT a$
```

There are some subtleties that should be noted about this example. A string must exist before it can be modified. So you cannot put the string abcdef into the MID$ expression, it has to be assigned to a variable first. The characters in a$ are replaced by the characters of the string 123. As 123 does not completely obliterate all the characters in a$, some will remain unchanged.

What happens when the string being pushed in is longer than the string being pushed into? Also what happens when the MID$ command has the third parameter set, specifying the length of the gap being pushed into? And what happens when there is no space at all or MID$ is told to push characters into a character position beyond the end of the string?

Are you paying attention? Now we're asking questions

Here are some examples to try out for yourself. See if you can work out what the result will be before you enter them. Watch out for improper arguments (values not in the range 1 to length of a$).

```
a$="abcdefg":MID$(a$,5)="123456789":PRINT a$
a$="abcdefg":MID$(a$,5,2)="123456789":PRINT a$
a$="abcdefg":MID$(a$,2,5)="123":PRINT a$
a$="abcdefg":MID$(a$,2)="12":PRINT a$
a$="abcdefg":MID$(a$,0,LEN(a$))="1234567":PRINT a$
a$="abcdefg":MID$(a$,1)=SPACE$(LEN(a$)-LEN("123"))+"123"
a$="abcdefg":MID$(a$,9)="123456789"
```

Well, did you get them all right? I hope so. Understanding and using MID$ in this way can help you get the most from Locomotive Basic.

This doesn't work!

To illustrate the advantages of using this technique, here are two examples of reading a key from the keyboard:

```
10 CLS
20 LOCATE 10,10
30 PRINT"Memory being used:";FRE(0)
40 a$=INKEY$
50 GOTO 20

10 CLS
15 a$=CHR$(255)
20 LOCATE 10,10
30 PRINT"Memory being used:";FRE(0)
40 MID$(a$,1)=INKEY$
50 GOTO 20
```

In the first example every time you press a key you lose some memory. With a short program like this it's not important. With 41000 odd bytes available you would need to press a key 41000 times before Basic did a garbage collection. In a longer program, however, with more strings, it is useful to use this as there is less free memory available.

If you put REMs into line 20 and change line 30 in the above examples to PRINT a$, you'll be in for a bit of a shock. The second, better example that I've given you doesn't work properly. It carries on printing characters even after the key has been released. Well of course it does, a$ still contains a character.

INKEY$ automatically returns a null string when no key is pressed. In the first example a null string is being printed every loop. In the second, a$ with a null string pushed in, is being printed.

There are ways round this. Having printed a$, reset it to contain a character not obtainable from the keyboard. Then this character can be tested for and not printed.

Line 30 would look like this:

```
30 If a$<>CHR$(255) THEN PRINT a$;
   :MID$(a$,1)=CHR$(255)
```

Boy is this complicated. Don't panic! If we put a character that doesn't print anything on the screen into a$, it will still be the same length but nothing will appear on the screen and we won't have to test it.

Change line 30 to do this:

```
30 PRINT a$;:MID$(a$,1)=CHR$(0)
```

Now do this

Just to test whether you've taken any of this in, here's a little exercise to try before playtime.

Write a routine that will accept any length of string and reverse the order of the characters in it, without using more than one string variable. ACU

AMSTRAD PAYMASTER

ADVANCED PAYROLL SYSTEM

FROM AMSOFT

- ★ PCW8256
  Single or twin disc operation
- ★ Menu driven with extensive help facilities
- ★ 500 employees (single disc 100 employees)
  Up to 10 departments
- ★ Weekly, bi - weekly or monthly payruns
- ★ Handles P.A.Y.E. National
  insurance and S.S.P. payments
- ★ Produces P.45 P.60 P.11 forms
- ★ Pay listings include: Pay register
  Financial summary
  Coin and note analysis
- ★ Year end procedures
- ★ Six levels of password protection
- ★ Available for new S.S.P. rates in April

IDEAL FOR 1ST TIME USERS
AVAILABLE NOW FROM YOUR LOCAL AMSOFT STOCKIST

All this for just £49.95 inc. V.A.T.



SEEK AND YE SHALL FIND...

Into adventures with Bill Brock

At last . . .

After what seems like a lifetime, but is in fact only a few years, Melbourne House have finally released The Lord of the Rings. Was it worth all the effort on their part and the build-up of anticipation on ours?

The Hobbit remains a classic adventure, not only was it the first to have really good graphics but it also launched a new era of games that included independent characters that could be influenced, but not compelled, to follow the commands of the player. It was also the first adventure game to be linked so firmly with a well known book.

In our world of computer adventures, it is difficult to be so innovative all in one package. There was the odd bug in the original Hobbit program, but nothing that could alter its tremendous success, in fact an adventurer's library is not really complete unless it contains a copy.

This success gave Melbourne House a reputation for good software that they never lost, even though subsequent adventure programs never quite reached the same levels as The Hobbit. Shortly after the public had got their teeth into that adventure came rumours of something bigger and better still, The Lord of the Rings. This, as if you didn't already know, is professor J.R.R. Tolkien's epic trilogy about Middle Earth, of which The Hobbit was only intended to be a children's introduction.

Rumours flourished – everyone wanted to believe them – and finally became reality, at least one third real, as The Lord of the Rings computer adventure will be published, as were the books, in three separate parts. The first program is massive and is split into two parts on two cassettes. It is based on book one, The Fellowship of the Ring, which is included with the software.

The reverse side of the first cassette has a beginner's level game. This is much smaller, with fewer locations and objects to find or use but with hint messages – not help, as the instructions say – and a score facility, neither of which are in the main game. It is useful for the novice as it emphasizes the need to draw maps and in a small way hints at the puzzles to be found in adventure games. If anything it is a little too simple to solve.

True to the book

The main games may be played as independent adventures, but on completing the first part you are told to save that position. This will ensure that when starting the second part you retain your companions and objects that you have found so far. The instructions do say that it should not be impossible for an experienced adventurer to complete the second half on its own.

The accompanying 32 page booklet presents a fairly clear picture of what is expected of you, together with an explanation of Inglish. This is similar to that used in The Hobbit, allowing you to input quite complex sentences and also talk to other characters. The vocabulary is large, with many hundreds of words being understood.

On loading the main program – about 10 minutes – you are offered the choice of which of the four Hobbit characters – Frodo, Sam, Pippin or Merry – you wish to play (control). Those that are not under player control will generally follow the master character.


There is provision for the control of more than one character, so permitting more than one player joining in the adventure. Merry is waiting for you across the River Brandywine, take too long in getting to him and he goes off in search of you, so it might be worth having him under separate control anyway.

The graphics are few and far between and when displayed are pretty poor – blocks of colour in general, rather than detailed pictures. There are a number of semi-independent characters within the story. Most are important to the correct outcome of the game and their actions may be influenced by the player by talking to them and giving them some form of command.

The storyline generally follows the book remarkably well, with obvious changes in detail to create the puzzles



Title screen from Lord of the Rings



Frodo in action in Lord of the Rings

that make the game worth playing. The Hobbits' journey through the Old Forest, their meeting with Tom Bombadil and the Barrow-wight are all there – none of which were included in either the film or the radio versions.

Section one takes the Hobbits towards the elven retreat at Rivendell, section two, from Rivendell, through the Mines of Moria, the wood elves' realm in Lothlorien and on towards the parting of the fellowship by the River Anduin.

Mapping is, as always, very important, more so with this program than some because often directions are somewhat strange, with a number of one-way paths. One expects odd things to happen in adventures but this "movement jungle" does seem to be a bit overdone. The mazes are good too – make sure you have a guide to travel through the marshes.

Oh so slow . . .

The screen display has almost a full depth scrolling text window, this is flanked to the left by three narrow vertical windows in which are displayed the pictures of the other principal characters not present at that location, the overall effect being of four overlapping pages.

As you move your master Hobbit from one location to another those with him will briefly appear in the nearest of these windows, while they make up their minds to follow the leader, and are still at the original location.

This sounds more complicated than it is, the system is quite clear to understand in practice. The major problem being the speed, or rather lack of it, with which all this is carried out. One cannot escape the fact that the program is diabolically slow. Type in N, for Go North, and you can wait for over 20 seconds before you can give another input command – and that is with only three characters with you. After Rivendell you could have eight or nine.

What aggravates the situation is that having waited for Sam to make up his mind to follow the others you finally see "Sam enters" on the main screen, but still you cannot type in a command for several seconds (no input cursor is present) and you cannot type ahead as there is no keyboard buffer facility.

Those with nimble fingers will now be cursing because they will have started to type something in, only to have the last few letters of the command accepted, which of course will not be understood.

To give a command to another character you use the format: Say to Sam "Get the rope". This also poses problems to start with, as there is an appreciable delay in the cursor reappearing after typing in the " sign. It is very easy to have the first couple of letters after this missing.

I guess that these long delays are caused by a combination of the complexity of the parser and deciding which independent character is doing what. Then the question is: Is this inefficient programming or just a by-product of a complex program? There are some other strange results too, if you "Climb tree" all is well, but "Climb down" and you get "You climb down the map".

Several such bloomers will cause a smile to players – lots of programs that try for complex parsing occasionally exhibit such funnies. Some are not so funny, such as when you have a sword but cannot use it. What is not funny at all is when the program crashes out completely and you have to wait 13 minutes to get playing again (10 for the main program and 3 to load a saved game).

Whoops . . .

I have spotted two locations that have repeatedly been the area for a crash, one is the dark tunnel to the Old Forest where my program crashes if I have no means of lighting the way, and the second was when I dragged Tom Bombadil with me into the barrow to protect us from the Barrow-wight. He is not the answer!

Regular saves are well worth while, even if it does take three minutes. It takes longer than that to repeat your steps. Also beware of friends leading you into the path of the black riders. If you lose the magic ring to the enemy your quest is over, and because of the complexity of the program, you have to load in the main program again – another 13 minutes.

Although the above criticisms are fairly damning, I have enjoyed playing The Lord of the Rings, but it is certainly not the game for an impatient player. If you are hooked on Middle Earth you will forgive the program's bad points and enjoy it regardless, but I doubt that the program will succeeed as would befit the sequel to The Hobbit.

Think carefully . . .

Activision have produced a number of good games but until recently have given the emphasis to the Commodore 64. Now they have released Mindshadow, an adventure game for the Amstrad. Let us hope this is the first of many.

The original Mindshadow was a disc-based game for the CBM 64, calling up the graphics from disc each time you moved to a new location. Activision obviously felt that a cassette version would give the game a new lease of life and at the same time converted it for other machines.

You play the part of an agent who has been betrayed

and left to die on a desert island. To complicate matters you are suffering from amnesia. You must extricate yourself from this desperate situation and in so doing gradually piece together the clues to your identity. The action moves to a pirate ship, to England and to Luxembourg . . . enjoy your travels.

The program is in two parts (loading time about 4+ minutes) preceded by an adventure tutorial. This is all good stuff with several ideas to help the novice understand the workings of adventure games. You don't have to load this if you don't want to.

The game is well thought out and has several extra facilities that could well be taken up by other software houses. The Amstrad's numeric keypad is used to provide 10 single key input commands – repeat last command, save and load game position, get all, drop, examine, help, quicksave, quickload and remember.

Most of these are obvious but the last three are of special interest. Quicksave will save your game position into the computer's memory and is particularly useful if you are about to attempt anything at all risky. It is very fast and its use is to be recommended. Quickload will just as quickly restore you to that quicksaved position.

Remember enables you to think about objects or people that you come across in your travels. Hopefully this thinking will trigger off a memory that will help you find your true identity.

Rapid action

Pictures and text are displayed on the screen very rapidly, so enabling players to progress at their own speed, with no delays to interrupt the thought processes. The graphics are colourful and reasonably clear, the text is displayed in 80 column mode at the bottom of the screen. On a colour monitor this is quite readable, but could be better.

Keying Enter with no input removes the picture and shows the previous commands and the replies given. Most commands are given in the usual verb/noun fashion but the parser will recognise a limited range of more complex inputs when the need is called for.


There is also a very useful facility to enter a string of commands at one time, such as N, N, E, E, S, E, GET STONE, W, W, S. This saves a great deal of time if you need to repeat a series of previously determined commands.

Help comes in a strange form – from the Condor, a somewhat enigmatic super-bird. He will only help you three times, but can come in pretty useful if he decides to put his mind to it.

You can always cheat a little if you have used up your three wishes by starting from the beginning and following through the game up to the point where you need help, as in most games the answers to the puzzles are easy to see after you have solved them, so starting from the beginning is no great chore.

I don't think there are any red herrings, so everything you find will have a use at some time. Not all useful objects are described in the text, so look at the pictures carefully.

The locations are divided up into sections, where you are not able to move on to the next section until you have solved the present one. That does not mean that items found earlier will not be needed later.



The sick bay of Mindshadow's pirate ship



Along the world-famous Strausbahn



A welcome at the inn?


The game is not difficult, but again is by no means easy, it utilises many of the adventurer's expected types of puzzles and so should provide a good primer for the newcomer. The clues are there, you have to find them, you also have to take some direct action on occasions and have to stoop to a little theft . . . but I suppose it's all in a good cause.

ACU

HIGH-RES GRAPHICS AT LOW-RES PRICE




FREE-HAND DRAWING ICON SOFTWARE



ELECTRONIC CIRCUIT DESIGN

USING—E.G. COMPUTER GRAPHICS DRAUGHTSMAN PROGRAM



TRACING/FREE-HAND DRAWING



ENGINEERING DESIGN

- **A4 SIZE DRAWING AREA**
- **HIGH RESOLUTION COLOUR**
- **HOME AND BUSINESS USE**
- **VARIETY OF OPTIONAL PROGRAMMES**
- **FREE HAND DRAWING**
- **CIRCUIT DIAGRAMS**



- **C.A.D.**
- **PCB LAYOUTS**
- **EASY TO USE**

FREE ICON DRAWING SOFTWARE WITH EACH GRAFPAD II

Available from most Computer dealers or direct from Grafsales Ltd.
Unit 8, Derby Works, Carey Place, Watford, Herts, WD1 2LR.
Tel: (0923) 43942. Telex: 946024 Open: Mon-Fri 9-5. Sat 9-12.30.

GRAFPAD II—

THE ULTIMATE IN GRAPHIC INPUT DEVICES

FOR THE AMSTRAD 464, 664 AND 6128 MICROS

The first low-cost graphic tablet to offer the performance and durability required for business, industrial, home and educational applications. It's small, accurate and reliable. Needs no adjustment or preventive maintenance. **GRAFPAD II** is a unique product that brings the power of modern technology under the control of the user.

GRAFPAD II:

- A brilliant British invention manufactured in Gt. Britain, unequalled in the world of graphics input.
- Ferranti's space age technology makes the Grafpad II unique in its digitising technique.
- The culmination of 3 years of advanced research to create a final graphical solution for the world computer market.

IT COMBINES IN ONE DEVICE ALL THE FACILITIES OF PREVIOUS ATTEMPTS AT INPUT DEVICES. THE APPLICATIONS ARE AS NUMEROUS AS THAT OTHER COMMONLY HELD DEVICE—A PEN!—AND INCLUDE:

- Option Selection
- Form Input
- Data Collection
- Logic Design
- Circuit Design
- Picture creation
- Picture storage
- Picture retrieval
- Construction design
- C.A.D.
- Text Illustration
- Games
- Pattern Design
- Education
- PCB Design

SPECIFICATION
Resolution:
1280 x 1024 pixels
Repeatability:
1 pixel
Output rate:
2000 co-ordinate pairs per sec.
Interface:
parallel
Origin:
LH corner or selectable
Dimensions:
350 x 260 x 12 mms.

CASSETTE £69.00 inc VAT
DISC £75.50 inc VAT

EXPORT AND DEALER ENQUIRIES WELCOMED

TO: GRAFSALES LTD. ACU4
Unit 8, Derby Works, Carey Place, Watford,
Herts, WD1 2LR. Tel: (0923) 43942 Telex: 946024

Please supply ____GRAFPAD(S) II Cassette £69.00 Disc £75.50 plus £2.50 p+p (or £8 insured delivery) *Please indicate for which machine.

NAME: _____

ADDRESS: _____

_____

_____

Cheque enclosed value £ _____

You can pay by credit card or telephone your order (24 hour ordering service)

Visa			
Access			

Epson FX-85



Jeremy Vine puts the latest in Epson's family of printers through its paces

A nutty old German Professor may be able to print out his thesis quietly in the local library but I bet he can't load paper into the printer. No, I haven't been at the drinks again, this is merely the ravings of a frustrated printer user. Let me explain.

Epson seem to be forever increasing their range and the FX-85 is the latest in the FX-line of high quality dot matrix printers. It has a single parallel (Centronics) port at the rear of the machine with the option of fitting a serial interface. In common with the present trend the FX-85 has a Near Letter Quality (NLQ) mode of operation.

NLQ is becoming standard feature on dot matrix printers and one which is of great importance. The problem which they used to suffer from was that the quality of print was no way near as good as that of a daisywheel printer. This of course was no surprise and those requiring a letter quality printer would purchase the more expensive and less flexible daisywheel. Epson get round this problem by reducing the printing speed and overprinting on the same line in order to emphasise the print. This works remarkably well and the quality of NLQ print is very acceptable.

The FX-85 boasts two main modes of print. A Draft mode which prints at 160 CPS (characters per second) and the NLQ mode which is about two-thirds slower. Although there are a host of character print styles (ie italics) and commands to change the size of print, few are actually available in the NLQ mode (see Figure 1).

The most glaring omission is that NLQ italics are not available. This may not be so much an omission as a

Typestyle Summary		***(D) Draft mode only***	
	Print style (NLQ or draft) Elite characters (D) Pica characters Proportional spacing (D)	Alternative character sets	International character sets Italic (D) User-defined characters (D)
Print size commands	Condensed (D) Enlarged		
Print enhancement commands	Emphasised Double-Strike (D) Superscript	Graphics (bit image) commands	Range of dot densities from 60 dots/inch to 240. The speed of printing varys between 3 to 10 inches a second.

Figure 1

technical difficulty but I found it a great disappointment.

One of the most frustrating problems to people not acquainted with printers, is the way in which control codes are sent to a printer in order to choose a style of print. This at the best of times is confusing and can be quite a problem if the software being used doesn't allow for some easy method of sending these codes. The FX-85 allows styles of print to be chosen from the printer using SelecType. This in itself is a novelty and is a very welcome development of the FX printer.

SelecType makes use of the three buttons on the top right hand side of the printer. These buttons have dual purposes and are marked as follows:

(a) OFFLINE/ONLINE
(b) FF/NLQ
(c) LF/DRAFT

When the printer is ONLINE, pressing the NLQ or DRAFT button will select that particular mode of print. This is very straightforward and an easy way of selecting the quality of print required. Also it negates the need to send a control code from the computer. Selecting other type styles however is not as simple.

To enter the SelecType facility requires the ONLINE and FF/NLQ button to be pressed at the same time. The user can then select a choice of nine print styles. To select style number 7 (underline), the ONLINE button is pressed seven times. Each time the button is pressed, the printer beeps to reassure you that you have actually pressed a key. The function is stored by pressing the FF/NLQ button again, then the LF/DRAFT key and finally the ONLINE button to return the printer to operation.

Choosing any other print style follows the same procedure except the number of key presses is dependant on the type selection. It gets even more complicated if you want such exotic effects such as elite double-strike or condensed underlined where more than one effect is being chosen.

In principle I like the idea of SelecType. But unless you have a photographic memory, you will always need the manual in order to find the typestyle you require. Considering that Epson make large use of LCD (Liquid Crystal Display) screens in their other products, a one line display informing the user which typestyle is being selected, would surely have been no trouble. The lack of visual feedback makes selection awkward and would be so simple to implement. But for all that, it's better than no SelecType at all.

The user can define his own characters or modify existing characters. This facility is only available though in Draft mode. The design of the printer is essentially the same as previous FX models. Above the three control buttons are three LED lights, showing whether the power is on, if the printer is online and ready to print and if the printer is out of paper.

DIP switches can be easily accessed by removing the plastic lid towards the top right of the printer. This allows the user to change the DIP switch settings without the need of dismantling the entire machine, as so many other printers do. The DIP switches are an important part of the printer as you can set up the machine to your own specific requirements.

The manual that comes with the printer is, by printer manual standards, good. Manuals that come with printers are notorious for either their complexity, inaccuracy or both. The FX-85 manual contains all the relevant information and provides step by step instructions. There is a handy reference card at the back of the manual but it lacks the essential summary of SelecType commands. A bit of an oversight. The manual is not great but it's better than most.

My experience with the FX-85 was marred by only one thing – loading paper into the machine. I've never really liked the feeding mechanism on the FX printers (though an improvement over previous models) and Epson have remained faithful to the FX series by keeping this quirky system. Once understood it's manageable but like all printers from time to time, paper gets screwed up inside the machine. This can be awkward to remove and easier access to the feed wheels should have been considered by the design team.

The FX-85 uses a tractor feed mechanism but for a very limited width of paper (242 to 254mm wide). To use fanfold paper of a narrower width, like labels, an optional tractor mechanism must be purchased. This seems to be a problem that was unnecessarily created. Why on earth the built in mechanism couldn't have allowed more flexibility in moving the width of the feed wheels is beyond me. However it is likely that most people will use the standard A4 size fanfold paper, which the FX-85 (unmodified) will accept.

If you're obsessed by the problems of paper feeding, Epson provide yet another accessory for feeding single sheets of paper into the printer. The Cut Sheet Feeder slots neatly on top of the machine and allows a stack of single sheets to be fed into the printer a sheet at a time. Once more I had problems with this unit and never achieved 100% results.


Overall though, the FX-85 is an admirable addition to the FX series. It appears to be slightly quieter against previous printers but is nowhere near as hushed as Epson's new silent ink jet printers. This aside, the FX-85 is a great little beast.

Combining the various print sizes, styles, enhancements, etc, gives the user a range of printing effects to keep most of us happy. And given the odd hiccup, the FX-85 has made me very happy. My sole ambition now is to meet Epson's nutty professor (the one in the TV advert and presenter of BBC2's 'The Great Egg Race) and his mother.

The FX-85 costs £438 +VAT. The optional sheet feed costs £125 + VAT. For further details contact Epson on 01-902 8892.

ACU

MAGIC



Datastar Systems

182 Royal College St., London NW1 9NN
Hotline 01-482 1711

MAGIC MODEM SPECIFICATION

- 300/300 Full Duplex — 1200/75 Viewdata 75/1200 Reverse Viewdata — 1200/1200 Half Duplex Bell Standards (Export version only).
- Auto dialling.
- Auto Answer Option (plug in Module £15 plus VAT).
- Auto Baud Rate Generator.
- Proper RS232 levels.
- 5 LED's: Transmit Data — Receive Data — Carrier — Power — Data Direction (useful for fault finding in half duplex mode).

COMMPANION SOFTWARE

- Menu Driven System.
- 16K with Spool Exec. Printing, Xon/Xoff, Baud rate selection.
- Unique directory system allows single key access to many databases with terminal configuration as required.
- Includes Xmodem file transfer for user to user sessions and downloading files.
- On or off line editing with professional features.
- Full feature Videotex Terminal Emulator.
- All common Prestel functions on single keys.
- Tagging feature for backtracking to large number of pages.
- Save and Load frames from current file system.
- Full specification CET telesoftware downloader, frames can be printed to local Econet printer.
- Econet compatible, except remote.
- Text terminal provides a scrolling host for use with non-video databases.

MAGIC MODEM + COMMPANION SOFTWARE **£99.95** + VAT = **£114.95**

MAGIC MODEM **£79.95** + VAT = **£91.95**

LAUNCH OFFER ORDER FORM — FREE DELIVERY

I enclose £ **FOR AMSTRAD**

Or debit my Access/Visa card no:

Name Signature

Address

MODEM

LAZAHOLD Trading as
AMSTRAD USER CLUB

AMSOFT MAIL ORDER

Super Special Offer

Buy One Get Two FREE!!

Three great tapes for only

£9.95 To Members
Please quote your membership No.)

NON MEMBERS

£11.45

To join the AMSTRAD USER CLUB
Please enclose £19.95 or
Phone on (0783) 673395
for further information.

Victoria House, P.O. Box 10,
Sunderland SR1 3PY.

★ 3D STUNT RIDER
★ GLEN HODDLE SOCCER
★ 3D BOXING

(ALL TAPE BASE ONLY)

I ENCLOSE CHEQUE/POSTAL ORDER FOR £_____

OR DEBIT MY ☐ ACCESS
(TICK AS APPROPRIATE) ☐ VISA

CARD NO. ☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐

EXPIRY DATE _____

SIGNATURE _____

NAME _____
(BLOCK CAPITALS PLEASE)

ADDRESS _____

_____

_____ POSTCODE _____

MEMBERSHIP No. _____

North East Micro Computer Exhibition
26th & 27th April, 1986

TO BE HELD AT

CROWTREE ROAD LEISURE CENTRE

Sunderland

BRING YOUR FAMILY FOR A FUN DAY OUT

If you don't like queuing and would like to SAVE 20% please send £1.50 per person (children under 5 FREE) for advanced booking. Cheques and Postal Orders payable to: VIVAFORCE LTD.

After your visit to the exhibition enjoy the facilities of the centre: Leisure pool with hydro slide, ice skating, childrens play area, catering facilities and licensed bars.

For further enquiries please contact:

TED ROCZYNSKI
on (0783) 671176

Vivaforce Ltd.
72 Durham Road, East Herrington,
Sunderland, Tyne & Wear.

In the picture



Screen Designer still top

Last August Jill Lawson looked at a variety of drawing packages. Since then many new packages have become available – how have things changed?

During the eight months or so since my assessment of the art packages then available – when Screen Designer marginally pipped Artwork at the post – a series of increasingly sophisticated utilities have appeared on the market. The advent of the light pen has brought devices ranging from the (dare I say) ridiculous, to the fibre optic based Dart lightpen which I found great fun, but the "draw everything in pastel colours" limitation (see VAX review – *ACU* March 1986) would preclude my using it regularly as an artistic tool.

1986 sees us entering an era of icons and pull-down menus, graph pads and mice, in a bid to find quicker, easier methods of colouring each of the thousands of pixels that make up a screen display so that the end result is an acceptable image.

Just as the line-and-wash artist would not choose to work in oils and the draughtsman would eschew pastels, *(I prefer the blackcurrant ones – Ed)* the needs of each potential screen designer will vary. I can appraise the following programs only on a basis of their suitability to producing as near a photographic representation of a subject as the resolution of the CPC range will presently allow.

Rembrandt – from Beebugsoft by S. Potter

Rembrandt comes with a glossy 17-page manual which takes you step by step from loading, through simple drawing commands, to more advanced techniques by means of clear, easily understood instructions. All operations are selected from three banks of eight icons, each of whose functions are explained in the order they appear on-screen. This is fortunate, since my copy lacked the promised summary of icons in section 8 – perhaps that is going on page 18.

This program is usable in all three modes on the CPC 464, 664 and 6128 computers and will work with keyboard or joystick. Instructions are given for saving screens to disc or tape and for their use in your own programs.


It may take two or three sessions to become familiar with all the available drawing features. Selection is made with the Esc and Tab keys, cursor movement is controlled with the arrow keys and execution with the space bar. The cross hair cursor can be speeded up by pressing Shift or slowed with Ctrl, Tab and Shift give the current coordinates.

Plotting lines, circles, rectangles, polygons and horizontal-based triangles all use the rubber-band principle, enabling accurate regulation of size and position. Single colour solid boxes and circles can be drawn, overwriting any previous work in normal Ink Mode. The AND, OR and XOR Ink Modes can be used for special effects where new lines, filled boxes and the like overwrite only parts of the existing drawing – a facility with enormous possibilities if one has time to explore it to the full.


The Fill is a joy to use. Perhaps not the fastest I've known, but efficient, and with the option to Unfill if it



Rembrant uses simple icons



A Rembrant still-life



GrafPad pictures are difficult to use from your own programs

escapes or you just don't like the effect. The two-colour Stipple Fill gives a range of 10 possible colours in Mode 1, and if you don't like a solid edge to your stippled area, you can draw and fill in a solid colour, then over-fill with the desired stipple.

Single Pixel Plot can be achieved in either the variable width Freehand Draw or Line modes, but there is a Magnify, in which any small area (40 × 24 pixels in Mode 1) can be blown up to fill the whole screen for detailed work. I found the keys a little sluggish in this mode, sometimes failing to plot a pixel at the first attempt. Since each one must be fixed by pressing the space bar, dealing with large areas is very slow.

Also, given the choice, I would have preferred that it should increase twice the area to half the magnification, since it is easy to lose your bearings when a complex section of the drawing becomes just a mass of huge coloured squares. Still, I'm not going to knock it, since any Magnify is better than none. By plotting in the background colour, small areas can be erased within this mode, while larger areas can be removed with filled boxes.

A variable-size Airbrush will spray random dots if moved around, or try staying in one position while changing colours to produce some nice little six-petalled flowers.

A useful Scroll allows the whole picture to be moved, one pixel at a time, in any direction, and selecting Grid enables cursor movement to be changed to jumps of between one and 32 pixels.

Standard Text and UDGs can be placed anywhere on the screen, but no variation of size or style of text is on offer. A Cut and Paste option enables a part of the picture to be copied or moved elsewhere on the screen, but because this is restricted to a fixed-size area similar to the Magnify box, I would find it of limited use except at an early stage in a drawing.

The program also includes a screen dump to the Amstrad DMP 1 and Epson printers, giving a fully shaded result.

Conclusion

A nicely presented and documented program offering a fair number of the options one might hope for in a 1986 graphic utility, but with room for improvement in the areas mentioned – Magnify, Text, Cut and Paste. It is perhaps surprising that there is no facility to design one's own graphics.

A good, reasonably priced utility suitable for most types of drawing, and the only new one designed for use in all three screen modes, it should meet the needs of most screen artists, although for very intricate detailed drawing Screen Designer still has the slight edge with its quarter screen magnify and ease of plotting.

Rembrandt

Price £13.95 on tape £16.95 on disc. Available from Beebugsoft, PO Box 109, St Johns Road, High Wycombe, Bucks, HP10 8NP.

Grafpad 2 Art from Micro-Draw

The Grafpad is a 235cm × 360cm board with attached pen and an interface that plugs into the expansion port on your Amstrad computer. For CPC 464 owners this means tape-only operation and picture save and load, which can be very time consuming.


A 14-page manual sets out the various functions available under headings showing the icons which appear on the pad around the edges of the drawing area. These are laid out in such a way that the left-handed operator would find them almost impossible to use.

Instructions could have been more detailed in some sections and more stress should be laid on the precise method of holding the pen, since it is possible to hold it near the base in such a way that the device is well-nigh unusable.

Grafpad 2 operates in Mode 1 only. Colour selection is via four boxes at the top of the pad, and changing the four colours to any from a choice of 27 is simple. The drawing area makes use of most of the screen, with a two-line message pad at the foot. A GCOL feature is similar to the logical plotting in Rembrandt.

The regular cursor is a solid, non-flashing cross hair. I would have liked a hole in the middle to facilitate single pixel plotting. A full cursor will give you horizontal and vertical lines right across the screen, crossing at the current drawing point – useful for lining things up correctly.

All modes are selected by pointing the pen at the appropriate icon and pressing the E button on the left side of the pad. Each operation is terminated by



The AMX mouse is best for technical drawing



. . . but can be used for detailed artwork

pointing at the Off box and pressing E.

You will need a fairly steady hand to draw freehand but the Solid Line mode is easy to use and each offers a choice of several line thicknesses. Circle displays the radius rather than the finished circle before final positioning, and Ellipse shows a diamond shape which is difficult to relate accurately to the actual ellipse. But Square, Rectangle and Triangle are straightforward, the latter being particularly pleasant to use. Solid versions of triangles, circles, squares and rectangles can be drawn. Polygons are available and can be moved around before positioning.

Spray mode has eight different patterns but you'll need a bit of practice to achieve the desired results, and it behaves a little oddly near the left-hand edge of the screen.

The Eraser function presents probably one of the most advanced features in this package. The size of eraser varies from one pixel upwards and it rubs out only one colour at a time. This is really useful if you want to use construction lines in a different colour – it is so easy to remove them when the drawing is completed.

In contrast, the Fill is diabolical! In addition to solid colour fills there are two banks of assorted patterns which can be rotated through 90, 180 and 270 degrees – such a waste, when filling is difficult, operating in an upwards direction only from the cursor position (V shapes require very accurate initial placing). Complex shapes need many fills, and if you get it wrong – disaster! Admittedly you can stop the fill by hitting Escape – but this does not remove what has already been drawn, making you doubly grateful for the efficient rub out mode!

Text can be positioned anywhere on-screen, and the angle can be changed with up and down arrow keys. Standard, large, bold, backward and forward italics give a wide choice of sizes and styles. A coloured tail is a further option, but for anything other than standard upright it can be hard to estimate just where it will appear, since you don't see the other styles before printing.

There is a facility to draw horizontal and vertical lines of a given thickness, a ×2, ×4, ×8, ×16 and ×32 grid, an option to create a graphics window and two menus of in-program icons which can be placed anywhere necessary. The accompanying Icon Generator program enables the user to design other icons for his own purposes.

Pictures can be dumped to Epson MX, FX or compatible printers by selecting the P icon – so long as the interface doesn't get in the way when trying to connect the printer cable! No information is given on whether or not screen designs may be incorporated in your own programs. There is no Magnify facility.

Conclusion

If your eyesight is good, your hand steady and you're not given to tearing out your hair when a careless fill loses you your last three hours work, or if you're a CPC 464 owner happy to use cassette-based software or if you're a CPC 6128 user who doesn't mind having to load the program twice and and you're not left-handed, then Grafpad 2 does have a lot of very interesting features – some exclusive to this utility. Change that Fill, include an option to Unfill, and for all but the south-paws it just might be worth spending all that money.

Grafpad 2
Price £69 on tape £75 on disc (including pad and interface). Available from Grafsales, Unit 8, Carey Place, Watford, Herts, WD1 2LR.

AMX Mouse and AMX Art from AMS

The AMX Mouse is easily connected to your computer via the joystick port, drawing its power from the monitor, and can be left in place while the machine is used for other purposes. You'll need a flat surface on which to operate the mouse – if your desk doesn't run to sufficient space (and mine doesn't!) a small board on your knee will do. Once AMX Control is loaded you are asked if you wish to load AMX Art, and pressing Y automatically puts you in drawing mode.

Layout of the art screen is quite complex – four pull-down menus are listed on a bar across the top of the screen and a scrollable window on the right shows icons to determine modes and spray sizes. A similar window on the left displays at any one time seven of the 32 black and white patterns available, with the current pattern in a box at the foot. These windows are not removable, so the drawing area is considerably smaller than the total screen size. The background colour is always white, and the pattern file can be used only in black ink, but a

Pattern Designer is provided to allow the user to design and use new patterns.

Operating the mouse is simplicity itself – just three buttons, Execute, Move and Cancel – and once you've sussed out the fact that the illustration in the manual is of AMX "through the looking glass", you're on your way. Apart from one other small error in the circle-drawing instructions, the manual is clearly written and easily understood.

It takes you through explanations of each of the functions on the file, options, text and lines pull-down menus, and the purposes of the mode icons. The cursor changes form according to the icon selected and may appear as a pencil, a spray gun, a block, a paint roller or a cross hair, which serves as a reminder of your current mode.

Freehand drawing, single pixel plot and rubber-banded line drawing are handled in Pencil mode. Any of the 32 patterns may be sprayed with the spray gun, in 12 sizes (spots, blocks, mist and so on). The small-dot size can be used for freehand sketching. Rubber enables erasure in any of the spray sizes. The paint roller may be used to roll-on a pattern, as in painting.

With the Fill option any of the patterns can be used to fill an area almost instantaneously, and pressing the Cancel button will remove it just as quickly.

Boxes, solid boxes and circles of variable size can be drawn and text can be added in a variety of styles and sizes. Using a rubber-banded box, any area of the screen can be picked out and copied to a new position. Gridlock gives the user the option to move the cursor in 1, 2, 4, 8 and 16 pixel steps.

Operating only in screen Mode 1, a further two colours from a palette of 27 may be added to the drawing. Lines and boxes may be drawn in either Pen 2 or Pen 3, inverted, or in white. In Fill mode you may select a Paint option whereby the pattern window will change to show a selection of hatches, some using all four colours, which may be chosen to fill an area of the screen in the same way as the patterns, but there is no option to redesign them.

If criticism was to be made of the artistic potential of this program, it would be that it is primarily designed to execute drawings in black on a white background, and to have colour added as an optional extra, rather than as a multicolour painting tool.

However, to a great extent this is counteracted by the excellent Zoom which magnifies the area within a box to eight times its size while still allowing you to see the magnified area on the original drawing. Any of the pixels within the box may be altered to another colour, and the box itself can be scrolled across the screen.

If you have used another art program you may find that you have to adopt a different approach to creating a picture, but, once you have mastered the use of this very nice feature, you are limited only by the fact that two of the colours on your palette must be black and white.

The program is not, however, without its minor irritations. Once Save is selected you must go ahead as there is no way of cancelling this option, and I managed to lock up several hours work by accidentally trying to save to a write-protected disc.

Going directly from line draw to fill produced a corrupt cursor with which I could erase the border of the drawing area, and inexplicably I left the odd coloured box behind when zooming while drawing with a coloured pen.

Pictures may be dumped to an Epson printer, and I believe they may be used in your own programs. Of course they will not fill the whole screen but will appear with a white border.

Conclusion

Not the perfect utility, since it would have been nice to have the whole screen area available for drawing. Anyone looking for ellipses, triangles, filled circles, polygons, and any other special features could be disappointed, but – excepting those little hassles I have mentioned – a very nice, sophisticated drawing package which is easy to use and well presented. You get an Icon Designer program too, and the manual contains much information on other uses for the Mouse.

AMX Mouse

Price £69.95 (including mouse and interface). Available from Advanced Memory Systems, Freepost, Warrington WA4 1BR.

Which one should you buy?

These are three very different drawing aids, each with features that were very pleasing and each with room for improvement. If you don't have too much money to spend then Rembrandt provides an excellent basic picture designer at a very reasonable price, and it is the only one of the three which allows you to use all three screen modes.

Grafpad 2 seems overpriced with the present software which offers a lot of distinctive characteristics but also has some serious drawbacks.

If you can live with the colour, mode and screen size limitations then the AMX Mouse is possibly marginally the best buy if price is not a prime consideration, but I'll probably just carry on using Screen Designer until I see what else comes along!

	Rembrandt	Grafpad2	AMX Mouse
General ease of use	9	8	10
Speed	7	6	9
Special features	6	9	9
Freedom from problems	9	5	7
Artistic potential	10	8	9
Value for money	10	6	9
Overall assessment	9	7	9

ACU

BOOKS FOR YOUR AMSTRAD

Understanding & Expanding Your Amstrad 464, 664 & 6128

ALAN TREVENNOR

Starting with an easy but in-depth approach to understanding how the Amstrad computers and Z80 processor work, even those with little electronics knowledge will be able to get to grips with all the important pieces of hardware.

With this knowledge – plus some inexpensive components – exciting projects can be undertaken. A speech synthesizer, expansion ROM board and a 4-channel RS 232 interface are introduced and – for the more adventurous – a complete EPROM programmer and a local area network for office, factory or school. Software to drive each project is included in the book and Assembly language programming is introduced with many examples. The complete kits described in each project, made by Halsted Designs, are readily available if you need them!

To be published March 320 pages £8.95

Practical C for the Home Micro

MARK HARRISON

A C programming course leading up to the most advanced techniques, this book is designed for those with no previous experience as well as competent C programmers wanting to get the most out of the language.

Building on an introduction to C, the reader is offered clear guidance through C syntax, declarations, data types, program flow, program development, structured programming techniques, functions, arrays, strings, preprocessor commands and much, much more.

The author's library of C procedures includes screen handlers, report generators, menu control and database routines.

Practical C for the Home Micro is fully approved by HISOFT, a leading UK supplier of the C language.

February 1986 180 pages £7.95

Amstrad Graphics

The Advanced User Guide

ROBERT RANSOM

The Amstrad CPC computers (464, 664 and 6128) are ideally suited for graphics work. This book shows how they can be used to best effect, with the emphasis on more advanced and exciting applications.

A full range of sample programs and routines covering a wide range of graphics techniques is included. The programs are highly original and useful, especially those for icon-based designs, molecular drawings, three-dimensional drawings and such creative techniques as the use of fractals to produce imaginative effects. There is also a section on business graphics, which includes pie charts, graphs, and two and three-dimensional bar-charts.

December 1985 230 pages £7.95

The Amstrad Disc Companion

SIMON WILLIAMS

The Amstrad Disc Companion introduces the new user to the world of disc computing on the Amstrad micros and provides essential information to help the seasoned user to get the most from AMS DOS and CP/M on the 6128, 664 and 464 (with disc drive).

There are 7 main sections: Using AMSDOS and CP/M commands and utilities; CP/M programming aids – ED; ASM; DDT; PIP; Machine code development using HISOFT's Z80 editor; assembler and monitor; Programming languages, including Dr LOGO and HISOFT Pascal 80; Business application programs including TASWORD 464; MICROSPREAD; MASTER FILE 464; Using sequential files.

To be published March 250 pages £7.95

Mastering the Amstrad PCW 8256

Word Processing and Personal Computing

JOHN M. HUGHES

The Amstrad 8256 is a powerful machine, with far more potential than is apparent at first glance of the user manual.

This book gives readers a thorough grounding in word processing techniques and then goes on to show how the 8256 can revolutionise even the smallest office and bring word processing into the home for less than the cost of a mid-range typewriter.

You'll find advice on care and use of diskettes, security and other fundamentals; a tutorial on word processing illustrating just about every 8256 command with quick reference sections; using the SuperCalc 2 spreadsheet — a powerful system for numerical calculations and financial planning; using the recently announced database packages to store and retrieve information — e.g. for stock control or mailing lists; a guide to other packages including payroll and accounts systems; using CP/M Plus — the operating system provided with the 8256; installation of CP/M packages, including NewWord, the new WordStar style word-processing package, is also covered.

To be published March 210 pages £8.95

CP/M: The Software Bus

A Programmer's Companion

A. CLARKE, J.M. EATON, D. POWYS-LYBBE

Two years ago **CP/M: The Software Bus – A Programmer's Companion** was published. Since then it's sold thousands of copies and is stocked by booksellers and computer dealers alike. Now that's not news. But . . . what **is** news is that Amstrad have given the book a dramatic new lease of life. Being able to use CP/M on the Amstrad means that a lot of Amstrad owners need a reliable and thorough companion text.

The book Amstrad have chosen to recommend to their customers is Andrew Clarke's **CP/M: The Software Bus – A Programmer's Companion.**

Written by founder members of the U.K. CP/M User Group, it runs to 332 pages telling clearly and concisely how to use CP/M to its best advantage. All the important commands and options in the main versions of CP/M (1.4, 2.2, 3.1, or CP/M Plus) are discussed with detailed examples of their use. The major software tools are also described and each has a helpful 'quick reference' guide. There are practical hints and tips for programmers at all levels, and each chapter has a 'fundamentals' section to help the really new user.

October 1983 332 pages £8.95

Powerful Programming for Amstrads

Supercharge your 464/664/6128

WILLIAM JOHNSON

This is an Amstrad book which shows you how to create clean and efficient programs. Many of the topics – for example, 2-3 trees, variable size nested loops, matrix manipulations – are exclusive to this book, enabling you to apply professional techniques to many of your programs.

Containing subroutines concerned with data input and retrieval, and techniques for solving equations, generating data, handling complex numbers, matrices and determinants, the book is ideal for advanced Amstrad computer users, students and programmers with specific problems to solve and concepts to learn.

Illustrations cover crystal shapes, 3-D movement representation, automatic control system stability and permutations, making the best use of the Amstrad features. Video RAM maps are explained clearly – essential for PEEK and POKE operations.

To be published February 200 pages £6.95

Please ask for these books at any bookseller or good computer dealer. He will be pleased to help you. If this is difficult or plain impossible, please write to Lesley Valentine, John Wiley & Sons Ltd., FREEPOST, Baffins Lane, Chichester, West Sussex PO19 1YP, England, enclosing your cheque made out to John Wiley & Sons Ltd; quoting your credit card number and its expiry date; or asking us to send you an invoice for prepayment.

Σ SIGMA PRESS

MARKETED BY JOHN WILEY & SONS LTD

Colleen Ltd.

BANSHEE

An epic Irish adventure. Can you save Colleen from the evil clutches of the Banshees, find the treasures of Ireland and make good your escape.
Over 200 locations.
DISK £12.95

KEYBOARD TUTOR

This comprehensive package takes you from the first steps of note recognition to a comprehensive catalogue of chord types and their inversions.
Eventually allowing you to build up to your own music masterpiece. A must for those wishing to understand the basics of music.
DISK £12.95

MYSTERY VOYAGE

Shipwrecked and left alone in the vast openness of the ocean. You visit strange islands and find yourself in worlds of mystery and fantasy.
200+ locations.
DISK £12.95



Reg. Trade Mark

Unit 7, Highfield Industrial Estate, Ferndale,
Rhondda, Mid-Glamorgan, S. Wales.
Telephone: Tonypandy 435709

Romboard rivals!

Vax looks at a solution when the chips are down

Honeysoft ROM Board

"Review this ROM board for me will you?". Review it? You don't review ROM boards, you plug ROMs in them. Well, this one is sufficiently different to rate a review. It differs from most other boards in two respects; it plugs in to the top of a Maxam board and it only costs twelve quid.

It all comes in a little white box labelled "Honeysoft ROM board" (logical eh?). This box contains a manual and the 3″ × 4″ ROM board.

The board contains four sockets, four sets of links, four capacitors and four resistors. Hence only twelve quid.

The manual contains adequate instructions on the setting up of the board and warns the user against plugging or unplugging the board with the power on, and stirring cups of hot chocolate with it. The manual is however excellent for standing said hot chocolate on.

The board takes either 8k or 16k ROMs, but they must have an access time of 200ns or better. Unfortunately, different manufacturers have different ideas of what 200ns is. Some NEC ROMs claiming to be 200ns did not work in any ROM board. Utopia, Maxam and the Micropower Toolkit all worked fine in it though.

The ROM numbers are selected by swapping small plastic links. These now have a small plastic tail on them to assist extraction. The old ones were almost impossible to extract with the unaided fingernail and tended to be converted into short-range ballistic missiles when prized out with a screwdriver.

The ROMs can be numbered between 0 and 6. ROM 7 is reserved for the disc ROM because Amstrad got there first. This looks like a good point to show some of the more common locations for ROMs:

ROM	Usual Inhabitants
0	BASIC
1	—
2	—
3	—
4	—
5	Maxam
6	SI0 ROM
7	Disc ROM


Now you see why there are only four ROM sockets.

On a 664 or a 6128 you can have 16 ROMs altogether, but not with this board. This tends to result in a ROM getting logged on twice. All is not lost, you use the Maxam ROMOFF command to nobble the extra one. Some ROMs are smart and know when they have been wound up.

The only fault I could find with this board was that the ROM sockets did not contain the usual notch which tells you which way up the ROMs go. As the manual tells you which way round they go anyway, this is not much of a fault. If you have a Maxam and need a ROM board, I have no hesitation in recommending this one, especially if you have a fetish for hot chocolate. Still, let's see what one of the opposition has to offer.

The Britannia ROM Board

This is going to impress a few people, mainly because it has a flashy, colour printed carton and a plastic box



holding all its electronic guts in. Unfortunately, this is about all it does have going for it.

First step is always to read the instructions (yea, well . . .), if you can find them. Their instructions are printed in English, French, Italian and German (wot, no Esperanto?) on the sides of the box. Yes folks, all the instructions are crammed in a 2" by 6" area.

The instructions do not tell you how to plug the gizmo into the back of your 464, 664 or 6128. Do you need to be told? Yes, you do – because the device has a very long ribbon cable coming out of it which has two sockets on the end of it as well as a through bus coming out of the side.

Knowing a bit about the Amstrad RS232 interface, I guessed that the first socket should have an adapter in it for the disc drive. The reason why you don't plug the disc drive into the through bus is that the 464 and its kind do not appreciate long cables, hence the adapter.

All this would not have been so bad if the connectors were keyed. As things stand, it is easy to plug in the unit the wrong way round. The Honeysoft connector is not keyed either, but the instructions for that one tell you which way is up.

Next we have to put in some ROMs. The instructions waffle a bit about the foreground and background ROMs and then tell you to put any foreground ROM in socket one. Now the clever bit: They have not numbered the sockets. They tell you in the instructions what is what, so don't lose the box and ignore the bit of PCB track that just happens to look like a one and is next to socket six.

Which way round do they go? Well, the instructions say that the notch goes on the left. The sockets are not marked as with the Honeysoft board, and the other chips on the board go every which way so don't use them as a guide. After fitting your ROM, you must change a dip-switch and then put the lid back on. Flicking these switches is somewhat easier than fiddling with the Honeysoft links as the dip switches are numbered.

The instructions also mention ROM cartridges, which can be plugged in to the back to expand your machine to "untold limits". Anyone with a firmware manual can tell you that this previously untold limit is 252 ROMs. Unfortunately, I have never seen an expansion ROM of this type, nor have I seen one of the cartridges. I am inclined to think that this idea is a non-starter. A case in point – when did you last see a Spectrum ROM cartridge?

Synopsis

If good looks alone counted, the Britannia offering would probably win. They don't though, and the Honeysoft board wins my vote, even if you do need a Maxam or Protext board to use it. For non machine-code hackers who don't know what a Maxam is, the Britannia board is no worse or more expensive than any of the other run-of-the-mill-units. The Honeysoft ROM board is available from Circuit (0992) 444111. The Britannia board costs £42.50 details from Britannia on (0222) 481135.

LOAD &RUN

THE AMSTRAD SPECIALISTS

See you at stand 10 at the Amstrad Show!

LOAD & RUN, DEPT, ASU
P.O. BOX 123
DARTFORD
DA1 5AA

RING (0322) 73128 FOR ENQUIRIES + LATEST RELEASES

We are continuing our policy of '85 into '86 with this selection from over 400 items in our list.

GAMES

CASSETTE	RRP	OUR PRICE
Barry McGuigan's Boxing	£9.95	£8.45
Blockbusters	£7.95	£6.95
Assault on Port Stanley	£8.95	£6.95
Blockbusters Gold Run	£9.95	£8.45
Bounty Bob Strikes Back	£9.95	£8.45
Bruce Lee	£9.95	£7.95
Chuckie Egg II	£7.95	£6.45
Daly Thompson's Supertest	£8.95	£6.95
Doppleganger	£8.95	£6.95
Fighter Warrior	£8.95	£7.45
Geoff Capes Strong Man	£8.95	£7.45
Glenn Hoddle Soccer	£8.95	£6.95
Gyroscope	£8.95	£6.95
Herbert's Dummy Run	£9.95	£8.45
Hypersports	£8.95	£7.25
Highway Encounter	£8.95	£6.95
Marsport	£9.95	£8.45
Match Day	£7.95	£6.75
Mindshadow	£9.95	£8.45
Sweevo's World	£9.95	£7.95
Raid (Over Moscow	£9.95	£8.25
Sabre Wulf	£7.95	£6.85
Strangeloop	£8.95	£6.95
Spy vs Spy	£9.95	£8.45
Terremolinos	£5.95	£4.95
The Keyfactor	£8.95	£6.95
The Worm in Paradise	£9.95	£8.45
They sold a Million	£9.95	£8.55
Tim Loves Cricket	£8.95	£7.50
World Series Baseball	£8.95	£7.45
Yie'Ar Kung Fu	£8.95	£7.45

DISC	RRP	OUR PRICE
3D Grand Prix	£13.95	£10.95
Beachhead	£13.95	£11.95
Bruce Lee	£14.95	£12.95
Computer Hits 6	£14.95	£12.95

CASSETTE	RRP	OUR PRICE
Highway Encounter	£10.95	£9.95
Jammin'	£12.95	£19.95
Raid (Over Moscow)	£14.95	£12.95
Red Arrows	£12.95	£10.95
Satellite Warrior	£12.95	£10.95
Scrabble	£14.95	£12.95
The Scout Steps Out	£12.95	£9.95
They Sold a Million	£14.95	£11.95
Triple Pack (Alligata)	£12.95	£10.95
Wriggler	£11.95	£10.45

CHEAPIES

	RRP	OUR PRICE
Caves of Doom	£1.99	£1.85
Chimera	£3.95	£3.50
Alkarah	£2.99	£2.75
Formula 1	£1.99	£1.85
Quiz Quest	£4.95	£4.35
Soul of a Robot	£1.99	£1.85
Cylu	£3.95	£3.50

ADVENTURE/STRATEGY

CASSETTE	RRP	OUR PRICE
Arabian Knights	£6.95	£5.50
Battle of Britain	£9.95	£8.45
Cauldron	£8.95	£6.95
Cheops	£8.95	£7.45
Cyrus II Chess	£9.95	£8.45
Elidon	£8.95	£7.75
Never Ending Story	£9.95	£8.45
Seas of Blood	£9.95	£8.45
Southern Belle	£7.95	£6.50
The Boss	£8.95	£6.95
Tombstowne	£8.95	£8.95

DISC	RRP	OUR PRICE
Cyrus II Chess	£13.95	£10.95
Lords of Midnight	£13.95	£11.95

UTILITIES

CASSETTE	RRP	OUR PRICE
Alignment Kit (Robocom)	£4.95	£4.45
Amstest	£4.99	£4.59
Genesis	£9.95	£8.25
Hisoft 'C' Language	£34.95	£31.95
Maxam (Arnor)	£19.95	£15.95
Protext (Arnor)	£19.95	£16.95
Rembrandt	£13.95	£11.95
Taspell	£16.50	£13.95
The Illustrator	£16.95	£13.95

DISC	RRP	OUR PRICE
Hisoft 'C' Language	£39.95	£35.95
Maxam (Arnor)	£26.95	£21.95
Pascal 80 CP/M	£39.95	£35.95
Protext (Arnor)	£26.95	£21.95
Rembrandt	£16.95	£14.95
Tasword 6128	£24.95	£21.95

BOOKS

Please enquire largest CPC range in UK
ALL DISCOUNTED

PCW 8256

SAGE	RRP	OUR PRICE
Popular Accounts	£99.99	£79.95
Popular Accounts+	£149.99	£129.95
Popular Invoicing	£69.99	£59.95
Popular Payroll	£69.99	£59.95
Chit Chat	Please ring POA	

CAXTON	RRP	OUR PRICE
Card Box	£99.99	£79.95
Touch 'n' Go	£24.95	£20.95
Brainstorm	£49.99	£39.95
Smart Key	£49.99	£39.95
Scratch Pad	Please ring POA	
Supercalc II	£49.95	£39.95

HARDWARE

	RRP	OUR PRICE	P&P
A.M.X. Mouse	£69.95	£65.95	
PCW 8256	£458.85	£439.95	£12.00
3" Disc (Amsoft)	£4.95	£4.25	
C15 Blank Tape x 10(")	£4.00	£3.75	
CL1 (cas int'fce lead)	£3.95	£3.25	
CPC 464 (Colour)(*)	£299.00	£287.00	£12.00
CPC 464 (Mono)(*)	£199.00	£189.00	£10.00
CPC 6128 (Colour)	£399.00	£377.00	£12.00
CPC 6128 (Mono)	£299.00	£287.00	£12.00
DDI 1 D/Drive(*)	£159.95	£155.45	£2.50
DL2 (664 d'drive lead)	£6.95	£5.85	
DMP 1 Printer Ribbon	£6.50	£5.45	
DMP 1 Printer (*)	£159.95	£155.95	£3.50
DMP 2000	£159.95	£145.95	£5.00
FD1 Addtnl d/drive (*)	£99.95	£95.95	£2.00
JY2 Joystick	£14.95	£9.95	
LP 1 Light Pen	£19.95	£18.95	
MP1 & 2 PSU & MOD (*)	£29.95	£24.95	£2.00
PL1 Printer Cable	£9.95	£7.95	
RS 232 int'face	£49.95	£45.95	£1.00
SSA1 Speech synth(*)	£29.95	£25.95	£1.00
3" Disc x 10		Only £37.95	

ALSO a range of products by KDS, Cumana, DK'Tronics & others.
Lockable Rexel 3" Disc Box ..... Special Offer £16.50

At last a quality Disc Box we don't mind selling. Made by REXEL in brown with two keys, lift off cover and three dividers. It will take discs either with or without cases.
Paper & Labels. A range of continuous paper & labels are available (some to order). Please send your requirements and we will quote you by return.

Access


UK: All prices include VAT and P&P in UK. Add P&P in brackets for hardware.
For Europe & Overseas: All prices exclude VAT & include P&P in Europe.
Elsewhere add 50p extra for P&P hardware outside Europe add £2.50.
E.&.O.E.

VISA

CAMPBELL SYSTEMS

AMSTRAD CPC

Quality Business Software.



MASTERCALC 128

The Modern CPC6128 SPREAD-SHEET System

This is the sister program to the famous MASTERFILE 128, and is a fast and friendly spread-sheet program with high capacity (over 7,000 cells) and impressive speed. Like MASTERFILE, it is entirely machine coded. Like MASTERFILE, it needs just one disc drive and does not use CP/M (sorry again, PCW8256 people), and it uses the same optimised RAM bank-switch code.

"Another exceptional utility from Campbell ..." said Popular Computing Weekly of the original MASTERCALC. The "128" edition is even more powerful.

All spread-sheet systems allow manipulation of an array of numeric data. What sets MASTERCALC 128 apart from the rest are these features:

Full-screen or split screen windows; variable column display width; variable column formats, 0-7 decimal places; columns can be formatted individually; ultra high-precision floating point arithmetic; direct totals and sub-totals; up to 99 relocatable formulae (usually 10 is ample!); formulae up to 75 characters, any arithmetic expressions, plus conditionals, relative cell references; instant highlight of computed data; store text anywhere; pop-up help menu; 40/80 column mode; auto cursor-advance; text output to printer or to disc for word-processing; fast hi-res histogram of any 3 rows; Epson screen dump; detailed manual with illustrated tutorial.

For the enthusiast, there is even USER BASIC access to the cell data, so that special operations can be performed. For example, it is possible to ship data to/from MASTERFILE 128

UPDATES: Users with original MASTERFILE 464/MASTERCALC can update to "128" by sending us their original disc (which we re-record) or tape (which we exchange for "128" disc). The new versions will read old-version files without problems.

RAM-upgraded CPC464/664: Yes, MASTERFILE/CALC 128 will also work with DK'tronics 64K RAM on CPC464/664. We can even provide the software on tape if you get your RAM before your disc drive!

SUPPORT: Our technical support department are here to help — but please send SAE with any written queries. Unlike most software marketing companies, we have the original programmer right here at the end of the telephone.

64K USERS: Original MASTERFILE 464 and MASTERCALC are still available at "club" prices. For each program there is also "Extensions" option which allows some of the "128" features — but not of course the large file size. "MPX" adds data export, file merge, and User Basic to the MASTERFILE 464, while "MCX" adds data export and User Basic to the original MASTERCALC.

MASTERFILE 128


The Ultimate DATABASE for the CPC6128

This program is accepted as the ultimate database for the CPC6128. Of the original 64K MASTERFILE 464, Popular Computing Weekly's reviewer made the comment "... without question the best I have ever seen". Naturally, the "128" edition is even better. Like most database programs, MASTERFILE 128 can file, sort, search, display and print your data. What sets MASTERFILE 128 apart from the rest are the following ...

Multiple user-defined screen formats; left/right justify; headings; ruled lines; column totals; data-sharing using parent/child relational logic; word-processing; numeric editing; sort ascending/descending, alpha or numeric (probably the fastest sort in the business); search by any criteria (definitely the fastest search in the business!!); bank switching. Up to 50 fields per record, all variable-length from 0 to 240 characters; totally menu-driven; needs just one disc drive; does not use CP/M (sorry you poor PCW8256 users ...).

There is more: data can be routed to other systems, such as TASWORD, PROTEXT, MASTERCALC 128. And for the real enthusiast, file access and update from USER BASIC opens up a whole realm of processing options. MASTERFILE comes with a detailed manual and example files. File capacity is 64K — for example 1,000 names and addresses.

- Forget the expensive, slow and aged CP/M dinosaurs: choose MASTERFILE.



	tape	disc
MASTERFILE 464	£21.25 ☐	£25.45 ☐
MASTERFILE 464 + MPX	£26.25 ☐	£29.95 ☐
MASTERFILE 128		£34.90 ☐
MASTERCALC (original)	£21.25 ☐	£25.45 ☐
MASTERCALC + MCX	£26.25 ☐	£29.95 ☐
MASTERCALC 128		£34.90 ☐
MASTERFILE/CALC update	Original tape + £13.95 ☐	
	Original disc + £10.00 ☐	

NAME _____

ADDRESS _____

Send your order or telephone (01 508 5058) with your VISA/ACCESS/EUROCARD/MASTERCARD number

Prices include VAT & P&P anywhere within Europe

Our normal service is 1st class return of post.

Please make cheque payable to "Campbell Systems".

(01 508 5058) VISA ACCESS

CAMPBELL SYSTEMS
(Dept. ACU)
57 Trap's Hill,
Loughton, Essex IG10 1TD

GARWOOD

Has the Midas Touch!!

Our 'Gold Selection' Catalogue of Amstrad Business Software & Supplies is available free on request

TRADE ENQUIRIES WELCOME

☎ Chelmsford (0245) 460788 (3 lines)

Unbeatable Service. Quality Branded Goods

CP/M Software on 3" Disc (Amstrad PCW8256 & CPC6128)

FINANCIAL MODELLING:

SUPERCALC 2	**£49.95**
CRACKER (with graphics)	**£49.00**

WORD PROCESSING:

NEW WORD	**£69.00**
WORDSTAR 3 (with Mailmerge)	**£99.95**

DATABASE MANAGEMENT SYSTEMS:

CAMBASE	**£39.00**
CARDBOX	**£99.99**

UTILITIES:

SMART KEY	**£49.99**

GRAPHICS:

DR DRAW	**£49.95**
DR GRAPH	**£49.95**

ACCOUNTS/PAYROLL:

AMSOFT ABCS (from £33)	Details on application
CAMSOFT (from £39.00)	
SAGE (from £69.99)	
CASH TRADER	**£114.95**
CASH TRADER WITH ANALYSER	**£149.45**
COMPACT DAYBOOK	**£49.50**
INCOMPLETE RECORDS	**£99.95**
TIME AND COST	**£69.95**

PROJECT PLANNING, STATISTICS:

BRAINSTORM	**£49.99**
SCRATCHPAD	**£69.99**

TRAINING:

TOUCH 'N' GO	**£24.99**
IANSYST TYPING CRASH COURSE	**£24.95**
IANSYST TWO FINGERS	**£24.95**
LOCOSCRIPT AUDIO TUTORIAL	**£9.95**

DISCS

Branded 3" Compact Discs

Single Sided (reversible), Double Density CF2 - Box of 10 **£36.95** Double Sided, Quad Density CF2-DD -**£6.50** (subject to availability)

DISC STORAGE

The superb **ACCO** disc storage box. Holds up to 50 3" discs **£19.95**

RIBBONS

DMP1 **£3.95** DMP2000 **£4.95** PCW 8256 **£4.95**

COMPUTER LABELS

FULL RANGE OF SIZES IN STOCK e.g. 1,000 $3^1/_2$" x $1^7/_{16}$" LABEL TRACK IN FLIP TOP DISPENSER - **£5.75**

LISTING PAPER

WE STOCK A FULL RANGE OF LISTING PAPER AT HIGHLY COMPETITIVE PRICES
e.g. 2000 Sheets of 11" x $9^1/_2$" 1pt. 60g. Plain with micro perforations **£14.95**

ALL PRICES INCLUDE VAT & POSTAGE

On Stand 52 Amstrad User Show Manchester (22nd/23rd March). We will be demonstrating LocoScript driving a daisy-wheel printer!
Our 10 nippled stripper will also be performing. RRP £11.38 but free with every Software order over £100 taken at the show.

Garwood Software

A member of the Garwood group of companies
Registered Office: 45 Plovers Mead, Wyatts Green, Essex CM15 0PS

Access VISA

Amstrad Business Computing

The supplement for Amstrad Business Computer Users

Free
April 1986
Volume One
Number Five

Getting inside your PCW 8256

Programming tips for the Joyce

LocoScript: Hints & Tips

Win: Caxton Software



AMSTRAD COMPUTERS ARE EXCELLENT VALUE

NOW THEY ARE 100 TIMES MORE USEFUL



THE AMSTRAD NETWORK AND HARD DISC GIVES YOU:-

- ★ A hard disc with more than 100 times the capacity of 3" discs.
- ★ A network allowing between 1 and over 100 Amstrad computers to be connected to the same hard disc for sharing of programs, information files, accounts and word processed documents.
- ★ Shared high quality output from daisywheel or laser printers.

TECHNICAL FEATURES

Each 20 Megabyte Amstore supports file and print serving as well as print spooler using the integral parallel printer interface.

The Amstrad network is a true token-passing multi-user ring network with file locking, max length 3km, max 120 stations. Stations include all existing Amstrad computers, 20 megabyte Amstores, printer stations, IBM PC, Apricot, BBC & Apple microcomputers.

The ring system supports modems, telecommunications and mini/mainframe communications.

Files can be copied from one micro to another, even with different computers.

Please send me an Amstrad Hard Disc and networking brochure.

Name: .....

Company/Organisation: .....

Address: .....

.....

Position: ..... Tel. No. .....

Intended applications if known:

Word processing ☐ Education ☐ Accounts ☐
Database ☐ Solicitors ☐ None of these ☐
Communications ☐ Spreadsheet ☐
Other professional applications .....

northern computers

Northern Computers Ltd., Churchfield Road, Frodsham, Cheshire, WA6 6RD Tel: (0928) 35700 **Telex 265871 MONREF G (Quote 84: CXX 123)**

Amstrad Business Computing

The City Page

The Amstrad bandwaggon rolls on. Turn back to the first mention of the PCW 8256 in these pages and at the end of the preview you will see that we suggested that readers should check the Amstrad share price after 12 months of the PCW 8256. At that time (just last September) it stood around 85p. At the time of writing it is around 345p. Amstrad computer news and reviews are now the hottest share tips in the business. Not bad for £1 a month, eh?

Whatever next?

The PCW 8256 is a hard act to follow. There are many attempts at guessing what Amstrad may have on the stocks for their next product. Having trodden the cautious route of one industry standard, CP/M 80, it seems fair to assume that another industry standard is in the sights of Roland Perry and his team.

The magic formula that has worked such wonders thus far could well carry on, since although the industry cynics (remember the carping comments about an "old fashioned" CP/M 80 machine at the launch of the PCW 8256?) will probably dismiss anything that treads a well-worn path, Amstrad has performed the task of preparing their marketplace with consummate skill.

A serious business

Amid the euphoria, don't forget that Amstrad have made the odd miscalculation here and there in the PCW 8256 project. There has been the serial interface fiasco, and despite Alan Sugar's dismissive remark that the interface was designed as a "pundit crusher" and that Amstrad would only sell a handful, any dealer of the machines will tell you that there are an awful lot of pundits out there just dying to be crushed.

The delightful communications software for the PCW 8256 has been starved of custom as a result of the delay in shipping the CPS 8256, and the wiser vendors have only been shipping the interfaces in packages with modems or printers. Users wanting to address external printers have been kept waiting, and the net result has been hassle all round.

If Amstrad are really so dismissive of anyone who regards the machine as anything more than a typewriter substitute, then maybe they could contract the task of "pundit crushing" to one of the brighter add-on support operations such as Pace – who would not only approach the subject with a better appreciation of the customers requirements, but also with the enthusiasm that is lacking in the term "pundit crushing".

Basic bargain

Precious few users of Basic appreciate just what a significant addition the Jetsam file manager on Locomotive's Mallard Basic really is. This ISAM (index sequential access manager) package turns Mallard into something akin to a database authoring system, although to read Locomotive's dismissively dry and laid back documentaiton, the wonder of it all might take a while to sink in.

If you are one of the many PCW 8256 users who has not yet fired up Mallard Basic to have a fiddle, you really are missing out. Most users can create their own database systems given a little persistence and patience – although the gruesome line editor is a definite turn-off to many programmers. Don't forget that NewWord or Wordstar has a non-document mode for program editing (saved using the Ascii save option), and that using NewWord's "Run a program" option, basic programs can be loaded and run "under" NewWord itself so that swapping in and out can be very quick.

Even the Joyce system disc offers an alternative in the form of RPED. It's true that the later versions of LocoScript have an Ascii ouput modem, but since you have to reload the operating system every time you want to edit, and then again to run Basic, this is not actually a practical proposition.

Spreadsheets

There are more spreadsheets available for the PCW 8256 than any other applications program. They all seem to have their own particular appeal, although only one has been really tailored to the hardware. ABC gave space to Ian Searle to describe his Cracker a few issues ago. As a result of the publicity, and the fact that Ian is the only native spreadsheet author, he was approached by one better informed educational authority with a wish list to turn Cracker into the sort of tool that would become a tool for science students.

So instead of boring old Basic the pupils could be taught how to apply computing, much as though a good old fashioned slide was used. Who cares how you print the ink on the wood, as long as it does what you want it to?

Ian Searle has continued to develop the Cracker Spreadsheet. The version Cracker2 now incorporates not only graphics, but XY graphs, date and timer functions, and an I/O control system with user patch area. You can thus use your PCW 8256 or CPC 6128 to control your central heating using this program, taking seasonal climactic variations into account. It hardly seems fair to call all this a spreadsheet.

William Poel

NEW★STAR SOFTWARE:

The solution, not just the software!

VISA Access

1. NewStar has the biggest selection. We can pick the right solution for your problems, not just the *only* one we sell.
2. The best programs *(as well as the rest)*. Ask our opinion and and we will try to sell you the best solutions, not just the ones we make the best margins on! But you can always choose to ignore our advice and still select from the biggest range available!!
3. The best technical installation and additional notes means less hassle for you, and fewer customer support problems for us!
4. Hotline support available until 9 pm most nights. It's cheaper for you to call, and quieter for us.

The time you spend learning to use software is costly. Much more so than the cost of the program in the first place: so you want to make the best investment of your time. NewStar can help by providing the all round service and helpful extras -like self configuring boot discs for many popular programs -as well as the best applications programs in their fields. Most NewStar software for the PCW8256 is available in 16 bit versions for the IBM PC and CPM86 systems. So your investment in learning can be carried forward when you upgrade.

CPM made easy ...for only £5.

A program to make disc and program management easier to understand: the CPM SHELL. A simple to use terminal management system that allows the user to manage CPM commands using a cursor driven menu selections. Available for only £5 whenever you buy a program from NewStar.

Much more also available from NewStar (read the other vendors ad's for details - or get our frequently updated colour catalogue) eg:

SuperCalc2 £49.95
Scratchpad Plus £69
Flexifile with Flexiwrite £49.95
dBaseII £ask
ABCS accounts systems £as advertised

Retailers: you can use our uniquely comprehensive colour catalogue and take advantage of our generous trade terms if you choose to buy all your Amstrad software requirements via NewStar. And since our software range is the biggest and the best, you'll be doing yourself and your customers a favour.

Applications Software for Amstrad, CPM80, IBM, IBM Compatibles, Concurrent CPM86, MSDOS, TurboDos

NewWord3: the ultimate wordprocessing system for most 16 bit micro computers, with in-document spell checking, built-in indexing, sub directory management, correct multiuser file management, conditional merge printing, maths functions, keyboard macros and the most versatile installation scheme you have ever seen.
£249.00 for PCDOS (colour or mono), Concurrent DOS, CPM86, TurboDOS etc.

VP Planner: Adam Osborne's micro revolution continues, with this Lotus 1-2-3 workalike, with the bonus of a multi-dimensional database. Regarded by those who know as better than the real thing.
£99 (that's right - ninety nine!) PCDOS only

NewWord2: the industry-standard wordprocessing system, with built-in conditional mail-merge and the Oasis Word Plus spell check and correction system.
£69.00 for Amstrad CPM
£119.00 for generic CPM80, TurboDos, MPM etc.
£199.00 for IBM PC (colour supported) and 16 bit systems

Microsoft's Multiplan: the world's favourite 8-bit spreadsheet program, allowing the user to automatically link the results of one sheet into another for maximum effective capacity. Over one million Multiplan users cannot be wrong.
£69.00 for Amstrad CPM80
£149.00 for IBM PC

The Cracker2: the imaginative and powerful spreadsheet, mathematical modeller, scientific and statistical analysis tool with integrated graphical capability. Now with a full set of date and time functions, XY graphs, and even I/O control features!
£49.00 for Amstrad CPM80
£69.00 for PC DOS, Concurrent, CPM86, TurboDos etc.

MasterPlanner: a plain language spreadsheet with the best manual and the biggest worksheet in the business. Create models that anyone can read and understand, since relationships are entered in plain english.
£69.00 for Amstrad CPM80
£29.95 Applications Library

StarCom: for the PCW8256 only (at present) full of practical features and facilities such as single or dual screens, dynamic graphics, spool incoming data to disc, easy pop-up menus for setting up parameters. Starcom will make computer communications a practical business tool -not just an enthusiasts' plaything!
£49.95 with terminal and ViewData options
£29.95 for terminal only
£29.95 for viewdata (Prestel) only

TAS: The Accounting Solution - the complete relational database language with compiler. The best all round data base authoring system from the creator of The Sensible Solution. Programs created and compiled on the Amstrad CPM system may be run on a PC using the runtime module -and vice versa!
£99 for Amstrad CPM80
£199 for PC DOS, MSDOS, CPM86, generic CPM80, TurboDos etc

DELTA 1.25: the easy-to-use transactional database system with the most helpful and best written manual in the business. Up to 8 transaction files per header file.
£99.99 for Amstrad CPM80

AtLast!: The end of simple 'filer databases': for the price of a simple database, you have the power of a relational system at your command.
£49.95 for Amstrad CPM80

CAMSOFT2: PCW8256 accounts software for all occasions - hand polished and specifically configured for the Amstrad computer user: not simply unearthed from the archives and rubbed down with an oily rag!! Modules include sales invoicing, stock control, purchase ledger, sales ledger, nominal ledger, incomplete records and payroll.
£49.99 per module
£99.99 per set of three

Compact Accounts: recently arrived. The elegant accounting system with comprehensive data exchange facilities to link to spreadsheets, wordprocessors and databases.
£ask

SAGE: All modules available at advertised prices.

Prices include VAT and PP. We will match any genuine currently advertised price, but you will not be eligible for the additional offers or benefits available from NewStar. Send or call for our latest colour catalogue of software products

New★Star Software Limited, Brentwood, Essex, CM14 4SG
Telephone 0277-220573
Telex 995143 NEWSTA G

ABC
REVIEW

A hands on experience with Joyce

LocoScript is more than just a freebie word processor which has been bundled with a computer to make it easier to sell, it is an advanced program, dedicated to the hardware. Mike Gerrard looks at some of the finer points.

The last article described some of LocoScript's features, and this time we'll concentrate on how some of those features work out in practice, though to begin with I'll confuse the issue and say that there's no such thing as LocoScript.

As with many professional programs, LocoScript is being revised and improved constantly, and at the time of writing I've seen four different versions – 1.0, 1.04, 1.1 and 1.2.

There may well be more, and you can tell which version you have because that's the number preceded by a v which appears on the loading screen as the disc is being read into the PCW.

These updates don't necessarily mean there's anything wrong with the earlier versions. Although Amsoft will replace the first version of LocoScript for you because a bug makes it difficult, although not impossible, to use page numbers, they are under no obligation to provide each and every customer with the later versions which contain one or two features additional to those described in the manual.

I know they'll be very sympathetic if you have a particular need for one of the added refinements, though, as my own and friends' dealings with them have shown.

Ascii and reprint

There have been two major improvements in version 1.2 of LocoScript. The first of these allows you to prepare an Ascii file from any of your LocoScript documents, which means that the text contained in a file stands independently from LocoScript and the file could be passed to a third party – a typesetter, say – who could work from it without needing to have a copy of LocoScript to interpret all the codes for him.

The second improvement allows you to print out selected pages from within a document – previously you had to print a document from the beginning, which if you only wanted a copy of page 37 was a nuisance.

Now when you select the printing option you will be asked if you want to print all pages or some pages of the chosen document, and the "some pages" option allows you to choose the page or sequence of consecutive pages that you want printed. The same applies if your printing has been interrupted through paper jamming or something similar, you can choose at which point you want to start reprinting.

But what of LocoScript generally? Initially the large number of options facing you at any one time seems very daunting, but you can make light work of them by using the menus. If you are an experienced word processor user you can start by learning to type the various style and emphasis codes directly into your text.

From the editing screen I'm currently on while writing this article, I know I can press the f3 key for an Emphasis menu



containing four options – underline, bold, double and reverse video. I can switch them on or off by calling up this menu and pressing the special [+] and [–] keys either side of the spacebar.

I could also call up the master menu containing all the options and set them from that, but by far the easiest way to set these choices is by typing the instruction direct into the text. If I want to start underlining I type [+]ul and the underlining starts, until I type [–]ul when I want to switch it off again.

If you want a word or character emphasised in bold, it's quicker and simpler to type [+]b, two key presses, than to press f3, move the cursor bar down to highlight bold, then press Enter to set the option.

If you learn to do this straight from the start perhaps calling up the master menu if you need to be reminded of the appropriate abbreviations for the codes, then you will soon make many of the function options redundant and LocoScript will become much more manageable.

Another reason for doing this is that some of the function options are rather illogically arranged. There is a last line marker, for instance, which tells both LocoScript and the printer that this line is the final one on the current page (saving you from having to fill the page up with blank lines till you get to the bottom).

However you don't reach this code by pressing f5, the Lines menu, but by pressing f6, the Pages menu. This has been done because it is an End of page marker, but to save you remembering which menu contains which options get into the habit at once of typing your instructions directly into the text.

Forming habits

In fact habit is very important in dealing with LocoScript. Before starting to print out a document get into the habit of pressing the PTR key before pressing the P key to start printing. This allows you to check the printer options. You can waste a lot of time and paper if you frequently begin printing with the wrong options set. Bad habits are hard to break, so try to pick up good ones with LocoScript from day one.

Your daily working habits are very important, and here the manual seems to have misled a few friends of mine in attempting to explain what it refers to as Start of day discs.

I must say that to me the manual seems clear, but I think for the benefit of people new to computers it should have quickly explained how LocoScript is fed into the PCW. Once you have inserted and loaded your disc containing LocoScript, then the program is in the computer's memory and you don't need to keep the disc in the disc drive for



LocoScript to operate.

Some people were under the impression that you had to have a copy of the LocoScript program on each and every disc you planned to use, but this is certainly not the case and would be very uneconomic if it were, as LocoScript takes up about half the memory available on one side of a disc.

I'd suggest you should ignore the idea of Start of day discs, and simply load in LocoScript first thing (always use your back-up copy and keep the original somewhere safe) and then replace the disc with the disc (containing only files) that you want to work on that day.

The main virtue of Start of Day discs according to the manual is that they save you the trouble of swapping discs round, but as it take about 10 seconds at the most to change over discs I don't think this is too worrying.

At the other end of the day, don't forget to think about whether to take back up copies of the discs you've been working on. That's a decision for you alone to take, but don't automatically stick all your discs away without ever considering doing back-ups.

It isn't often that data gets destroyed, but you might easily erase the wrong file or accidentally wipe out all the files on a disc (it's just happened to someone I know who's been using word processors for years, so don't think it can't happen) so imagine how you'd feel if you did lose the data on a particular disc. Let that be your guideline as to whether you should take an extra copy of it or not.

Avoiding a full disc

While talking about the possibility of losing data, it's very important to understand how LocoScript works when it is saving a file to disc.

You might find that you run out of space on a disc when in theory you should still have plenty of memory available. If you're editing a file that is, say, 15k long and you have 16k of space left on the disc, you might think it's an easy matter to add a few pages to the file, just 2-3k, and save the new longer version of the file.

LocoScript doesn't work as simply as that. What it does, quite sensibly, is try to save the new version of the document before it destroys or moves into limbo the old version.

You would be pretty annoyed if it destroyed the old version first and then, due to some technical hitch, was unable to save the new version, leaving you with nothing. In order to do that it needs enough space on the disc to save the complete new version of a file, not just the few additions you may have made to it.

In the example given, if your file is now 18k long, there isn't room for it in the 16k available on the disc, so what LocoScript will do is save as much of it as possible and then ask you to create some space on the disc to allow it to save the rest.

Unfortunately you can't create the space by moving the old version of the file onto the RAM disc until the new version is saved. You have to erase or move another file.

This is usually quite straightforward, though of course it's always risky moving any file into the RAM disc even for a short space of time. Sod's Law ensures that if you're going to get a power cut it will happen in those precious few seconds.


Depending on the size of the files you're dealing with, you might even have to move one on to another disc to create sufficient room to finish saving, and this is when you discover you have no room on any of your other discs and the only blank one available is unformatted. Avoid this by always keeping an eye on the memory remaining on a disc, and bear in mind that you might need twice as much as initially seems likely.

Short cuts make long delays

One habit you shouldn't get into is doing things the wrong way just because it seems simpler, or because you can't take the trouble to find out how to do something the right way.

One example could be in the various templates that LocoScript provides you with initially. Some might almost suit

Nightingale Does It Better!



Communicating with the outside world can present its own special problems. Fortunately help is at hand for Amstrad users in the form of Nightingale and Commstar.

The Nightingale modem has become the standard by which others are judged. Combining simplicity of use with true multi-baud rate operation, Nightingale can provide access to both Viewdata (1200/75 & 75/1200 baud) and full duplex (300/300 baud) systems.



Commstar is **the** communications software and is now available for the Amstrad micro. Commstar is a combination of powerful Viewdata and Terminal communications programs providing full telesoftware downloading facilities. It is fully approved by Viewfax and features window menus, a full eight colours, it can be used under C/PM and is fully compatible with the Amsoft RS232 standard.

Nightingale and Commstar for use on the Amstrad CPC 464, 664, and 6128 are available direct from Pace or from good dealers everywhere.

APPROVED for use with telecommunication systems run by British Telecommunications in accordance with the conditions in the instructions for use.
S/2592/3/E/500065

Nightingale Modem £119.00 **Commstar on disc £29.57**
Nightingale, Commstar (on ROM), plus Serial Interface £150.00

Also available separately are the Terminal (Honeyterm), and Viewdata (Honeyview) programs from Commstar at £19.95 each.

Please add carriage and V.A.T. to the above prices. P & P (U.K.): £0.75 with Nightingale £2.50.

Comprehensive fact sheets are available for these and other Pace products.

PACE

PACE Micro Technology
Juniper View, Allerton Road, Bradford, West Yorkshire.
Tel. 0274 488211 Telex No. 51338
Prestel Mailbox No. 274 729306
Telecom Gold Mailbox No. PCE 001
Int. Tel. No. +44 274 488211

ACCESS VISA

Rated best Modem and Software by **Amstrad Computer User**



AVAILABLE AT ALLDERS · BOOTS · CURRYS · DIXONS · GREENS · JOHN LEWIS · LASKYS · TANDY · W.H. SMITH · COMMERCIAL OFFICE EQUIPMENT · FARNELLS ·

The electric typewriter's days are numbered.

Because now there's a machine that puts real wordprocessing power within everyone's reach.

The Amstrad PCW 8256 is a complete word-processor and a powerful computer in one unit.

And its unbelievably low price includes a screen with built-in disc drive, keyboard, printer and word-processing software.

It's a complete wordprocessor

The PCW 8256 is totally equipped for word-processing. It has a high resolution screen with 90 columns and 32 lines of text.

That's 40% more usable display area than most PC's.

There's a high speed RAM disc that allows you to store and retrieve information instantaneously, as you're creating a document.

There's also an optional combined serial and parallel interface that gives you access to modem, additional printers and other peripherals. And you can even add an extra 1 M byte drive.

Training


The PCW 8256 comes with a comprehensive user guide that tells you, in simple language, how to master its wordprocessing and computer capabilities.

But if you want to get to grips with it even quicker, there are now a great number of training courses available throughout the country.

On-site maintenance

Amstrad computers are exceptionally reliable.

But many business users find it reassuring to know that nationwide on-site service and maintenance contracts can be arranged.



The 82 key keyboard is specifically designed for wordprocessing. Its special function keys allow you to refer to 'pull down' menus as you work, so you don't have to memorise complicated codes.

And the PCW 8256 has an integrated printer with compatible software that gives you a choice of letter quality and high speed drafting capabilities.

Finally, there's an automatic paper load system, as well as tractor feed for continuous stationery.

It's a powerful computer

The PCW 8256 is also a purpose built computer with an enormous 256k memory.

For computer buffs, the Mallard basic, Dr Logo and GSX Graphics system extensions will mean you can write your own programs.

All of which puts the ordinary office typewriter firmly in its place.

The place featured on the opposite page.

Please send me some more information about the PCW 8256
Home user ☐ Office user ☐ (Please tick)

Name_____

Address_____

_____

_____

Tel:_____

Company_____

Amstrad PCW 8256

Amstrad, P.O. Box 462, Brentwood, Essex CM14 4EE.
Tel: (0277) 230222. ACU 4/86

METYCLEAN · OFFICE INTERNATIONAL · RONALD MARTIN · RYMANS · SANDHURST · THOMAS HILL · WILDINGS AND GOOD INDEPENDENT COMPUTER STORES.

your needs, so you adapt to using them rather than be bothered to find out how to amend them so they exactly suit your needs.

One of the templates, for instance, has a great number of tab settings, so you find it esier to press the Tab key several times to move you across the page of a document rather than try to edit the original template to delete some of the unwanted tab settings.

Because there are several different types of tab settings, you may feel it's going to be too confusing to learn how to set them and to learn what each one does, but if you think like that then you may as well go back to using a typewriter as you won't get the full benefit of your word processor.

The indent tab, for instance, is extremely useful, allowing you to indent a whole block of text to a particular point across the page while retaining the automatic word-wrap facility. Anyone interested in writing scripts would find this invaluable, and there will be lots of occasions where you'll want to prepare a document which has a section indented like that, and an indent tab is easily brought into effect by pressing ALT+TAB instead of TAB alone.

Headers and footers

One aspect of LocoScript that can be confusing, partly because it seems to operate differently from the way described in the early manuals, is the question of header and footer zone positions. If using single sheet paper the Amstrad allows for a maximum possible 70 lines of text on one A4 sheet.

Of this, the default settings that are in operation when you load LocoScript are for a header zone of nine lines and a footer zone of seven lines. This means that on any page the first nine lines will be blank, or with have whatever you choose to put as a header on each page, and the last seven lines will also be blank, or will contain whatever you choose to have at the foot of every page. The text of your document will appear on the 54 lines in-between.

These header and footer zones are very generous, and do give you a well spaced page with healthy margins all round, but if you want to squeeze more information on each page then don't be afraid to alter them to suit yourself – they're only suggested settings after all.

What you must be careful of, though, are the two settings marked position on the Page size menu, selectable from the options available when you're editing the header.

Although you have a zone of nine lines set aside for the header on each page, you're unlikely to want the header text to appear on the first line of that zone, right at the top of the page, so you select a position setting of perhaps 4 or 5 to indicate on which line of the page the first line of your header text will appear. If you have just one line of text, say a title and page number, this gives you a reasonable margin above and below it.

There is a problem with the footer zone position setting, however. This works in a similar way, and you use it to indicate where you wish the first line of your footer zone text to appear. Obviously you don't want it immediately after the last line of the document proper as it will look more like a continuation of it, so you'll probably want to leave at least a couple of blank lines before the footer is printed.

According to the manual the footer position is counted up from the bottom of the screen, so if you enter a setting of 3 the first line of your footer text will appear three lines up from the bottom of the page.

Unfortunately this doesn't seem to work in practice, and with a setting like that LocoScript will try to print the first line of footer text on the third line of the page, counting from the top. As this is occupied by text, it waits and prints the footer text as soon as possible after the body of the document.

If the text fills the page this doesn't matter too much, as the footer gets printed at the foot anyway, but if your text ends half way up the page then you'll get your footer printed just under it. The footer zone position must be set instead at the line number on the page where you want the first line of footer text to appear, that is, something like 66 or 67 if you want a small gap above and below.

You must also remember not to put more lines into the footer zone text than can actually be fitted on to the page. If your first line of text is to appear on line 67, and you then enter four lines of footer text, the final one won't fit on the page and will be carried over to be printed on the top of the next page.

If you are printing out a single sheet of paper this could cause the program to appear to lock up, and you won't be able to do anything with it, whereas all that's happening is that the document hasn't finished printing its final line of text and the machine is simply "Waiting for paper".

Stop!

In dealing with LocoScript in practice, I've been concentrating on items that the manual doesn't explain perhaps as well as it could, or on slightly confusing areas, and there's one important key that doesn't even appear in the index, which is the Stop key.

You should know by now that the Can key (for Cancel) allows you to take back any command or menu that you've decided that you don't want after all, and in effect it's the opposite to the Enter key which confirms that you want to go ahead with the action that you've chosen.

The Stop key works as an extra safeguard and allows you to halt certain actions if you change your mind. It won't work on every type of action, but if, for instance, you've pressed the wrong key and started to send the cursor to the end of the document instead of to the beginning, you can press Stop to prevent you having to sit there and watch while the cursor slowly but inexorably makes its way to the wrong place.

Pressing Stop at once calls a temporary halt to things, and you can either stop permanently by pressing Stop a second time, or carry on by pressing Enter.

If you think you've made a mistake, it's always worth pressing Stop to see if you can get out of it again. It doesn't cancel the action, but merely halts it at the place it's reached and allows you to send the cursor back the other way or whatever it is you wish to do.


I hope this series of articles has served to explain Joyce a little more thoroughly to both those who've bought her and those who are thinking of buying the machine.

I said at the start that having spent my hard-earned money on the PCW, I felt justified in criticising where necessary, but in truth there have only been a few slight moans and I honestly feel it's the best buy I have ever made. It seems to have almost doubled my writing output, and you can hardly ask for much more than that.

ABC



BRITAIN'S BEST VALUE COMPUTER HARDWARE




So far so good. If you've bought an Amstrad PCW 8256 you've got the best value hardware on the market. But what now? Keep on saving with the best selling, Sage 'Popular' range of business software.

Take your pick from the biggest and best range of professional software for the AMSTRAD. Accounts, Payroll, Invoicing, Data Base Management and Communications programs, all simple to use but highly effective and yours from as little as £69.99 incl. VAT. For the cost-conscious small business, there's no better bet than Sage. What's more, you don't need to be a computer buff to put our programs to work. We give you 90 days direct after sales support absolutely free, and for a modest annual payment we'll provide ongoing support, including free program updates. (Try asking some suppliers of higher priced software how much support they offer!)

What Amstrad did for hardware prices, Sage, one of Britain's top software companies, have done for software prices. Talk to your local dealer today, or send for more information.

DESERVES BRITAIN'S BEST VALUE SOFTWARE



● **ACCOUNTS** The original SAGE accounting system to automate your bookkeeping. **£99.99** incl. VAT

● **INVOICING** Automatic invoice production linked to a stock recording system **£69.99** incl. VAT

● **ACCOUNTS PLUS** SAGE accounts combined with Invoicing and linked directly to your ledgers. **£149.99** incl. VAT

● **PAYROLL** An effective, easy-to-use system to automate wage calculations, payslip printing etc **£69.99** incl. VAT

● **COMBO PACK** The SAGE Accounts and Payroll programs in a money-saving package **£149.99** incl. VAT

● **SUPER COMBO** Accounts, Invoicing and Payroll at a saving of £39.98. **£199.99** incl. VAT

● **SAGE DATABASE** The electronic filing system to organise your records and produce reports and mail shots **£69.99** incl. VAT

● **CHIT-CHAT, E-MAIL** A special version of this top-selling program to connect to electronic mail systems like Telecom Gold, One-to-One, etc. Includes free One-to-One mail box worth £50. **£69.99** incl. VAT

● **CHIT-CHAT, VIEWDATA** This version of Chit-Chat gives you access to Prestel and other information systems **£69.99** incl. VAT

● **CHIT-CHAT COMBO** Save £39.99 with this combination of our E-Mail and Viewdata programs. **£99.99** incl. VAT

FOR MORE INFORMATION

Fill in the details below and post to: Sagesoft plc, NEI House, Regent Centre, Gosforth, Newcastle upon Tyne NE3 3DS.

NAME _____

COMPANY _____

POSITION _____

ADDRESS _____

_____

_____

POST CODE _____

TEL. NO _____

☎ ORDER BY PHONE

SAGE

Holders of Access and Barclaycard can order by 'phoning Tyneside (091) 284 7077. Please allow 28 days for delivery.

BETTER SAGE THAN SORRY

ACU4/86

Total Package



Total Price....
£247.50

Totally amazed? Read on . . . P.C.Soft offers a completely integrated accounts software package at a realistic price. No other package on the market today offers so much at such a low price.

INDIVIDUAL MODULES OR COMPLETE SYSTEM

Purchase individual P.C.Soft modules at only £99.50 each OR buy the complete suite of five for only £247.50.

THE TOTAL PACKAGE

Module P.C.S. 1	
INVOICING	£99.50
Module P.C.S. 2	
SALES LEDGER	£99.50
Module P.C.S. 3	
STOCK LEDGER	£99.50
Module P.C.S. 4	
PURCHASE LEDGER	£99.50
Module P.C.S. 5	
NOMINAL LEDGER	£99.50
BUT TOTAL PRICE ONLY	£247.50

WELL ESTABLISHED SYSTEM

The P.C.Soft software packages are not new. Over 3,000 modules have been fully operational in the U.K. since 1981.

IS P.C.SOFT COMPATIBLE?

YES! Our system operates on all micro's operating under CPM, MS-DOS, or PC-DOS on IBM, Olivetti, Zenith, Apricot, ICL, Sanyo, Canon, Compact, Ericcson and many more even the incredible **AMSTRAD**.

We even produce a fantastic MULTI USER SYSTEM for use with CCP M and Conc. DOS.

TRAINING, SUPPORT, BACK UP


We strongly believe in giving full support on our systems to all end users. As a result, a network of regional centres is already fully operational to offer complete hands on training. Further, we operate a HOT LINE direct to our H.Q. to give rapid answers to your queries.

HOW TO SAVE ON YOUR SOFTWARE

For complete details of the full P.C.Soft £247.50 package, and other modules including **PAYROLL** and **JOB COSTING** fill in the coupon now or Telephone: 0222 705030 705039.

YOUR GUARANTEE

If any P.C.Soft module does not measure up to your expectations we will refund your money immediately.



To: Datasoftware International Ltd., 1 Windsor Chambers, Windsor Arcade, Penarth, South Glamorgan, CF6 1JA. Please send full details on the Complete P.C.Soft Accounting Package at £247.50 and individual modules at £99.50

Name _____ Company _____

Address _____

_____

_____ Tel. No. _____

ABC
SURVEY

Business computing:

What did you want?

The survey in issue 1 of Amstrad Business Computing produced a stunning response. William Poel studied the forms.

The first ABC supplement carried a brief questionnaire designed to get readers to work out what it was they needed from their first encounter with computing in their businesses.

The resulting forms have been read – but not analysed by computer (shame!) – since the size of the sample and the wide ranging nature of the questionnaire made this very difficult. However, the trends were quite apparent, and prove the marketing philosophy of Amstrad is dead right . . .

Who?

The source of submissions would have brought a lump to the throat of politicians who specialise in empty rhetoric extolling the virtues of why every business in Britain should embrace the "new technology" and computerise in the National Interest.

Everything from fish and chip shops to accountants, via small manufacturing businesses and a goodly (Godly?) dose of the clergy sent in their outlines for consideration.


In other words, the heartland of Mrs Thatcher's enterprising community that steadfastly avoided the products of those other computer companies that featured heavily with the political PR, but who failed to address the needs of the small business.

What?

The number one subject (besides word-processing, taken for granted with a PCW 8256) was accounts. This is not surprising, but it is an area where a single disc PCW 8256 is at a disadvantage.

The main problem being that account data files need to be pre-set: and changing the size of accounts data files is a notoriously delicate task, if it is possible at all. So you must try and get it right first time. It isn't easy guessing how many customers you will have in 12 months time, how many stock lines, how many transactions.

Playing with only 173k of data leaves little or no room for guesswork, and makes the totally integrated approach of invoicing, stock control and sales ledger nearly impossible. Far better to start with the second drive fitted if accounts



are going to feature in your requirements.

Around 80 per cent of the submissions confessed to have no prior knowledge of computers or computing, and were bravely setting out on the great quest for knowledge on their own. Not too many owners regard their encounter with the PCW 8256 as a "learning" experience – but I suspect that view will become modified after the first piece of software is purchased.

Spreadsheets and databases come joint second (no surprises here), and a few people added comments, declaring the high cost of Prestel and BT Gold to be a severe disincentive. Mind you, £1 a week is nothing when compared to the cost of the phone bill but most people seem to regard that quarterly event with a fatalistic indifference.

In any case, how many letters can you send for £1? And how many of those turn up next day? The "recorded delivery" E-Mail has been with us for years (telex), and it is a mystery why no one is trying harder to put together a low cost telex line interface for the PCW 8256. Hang all these modem mania, what the businessman needs is a real telex facility.

No messing about

A concise and clear cut attitude that computers are for computerising is fine: as long as the user is prepared to take a clinical view on the costs of acquiring knowledge, and actually add up the cost of their own and their staff's time spent in getting acquainted.

Anyone who does not count the cost is participating in a learning experience, whether or not they wish to call it that. This is why it is so important to make the right choices at the outset, and why the cheapest solution is not automatically the best solution. It may well only be the cheapest in the short term, turning out to be very much more expensive than other options in the medium or long term.

It was interesting to see that well over half the submissions claimed no prior knowledge of home computing either. Some (admittedly dubious) statistics seem to indicate that every man, woman and water vole in Great Britain owns a Spectrum (let alone anything else). I can only conclude that the experience has been so chastening that the owners have written off the idea of ever taking computing seriously where their livelihoods are at stake.

The cost

Following on from this point, when asked if the hardware, software or time spent learning was the most expensive element of the purchase, came a touching expectation that the highest price to be paid was for the hardware. Oh dear.

Virtually 100 per cent of users decided that they would make their minds up about the next stage in their development of computerisation based on their initial experiences. This is hardly surprising – and it will be interesting to re-ask the question in 12 months time.

The business outlook

Over 70 per cent of users claimed to have a passable or better knowledge of accountancy. It's inevitable for a small business to have to understand most aspects of accountancy these days, as the time spent in unpaid work on behalf of the government is probably the major driving force in the business computer industry. It seems likely that the most conscientious book keepers are likely to be those who perceive the most benefits from computerisation.

Almost everyone offered credit account facilities for their sales. next to the VAT return, the biggest moan in the small business is the chasing of unpaid debts, and the benefits of computerisation are very obvious on this score.

Stock control featured in 15 per cent of the forms. This is not a bad thing, since the rigours and discipline of stock management are rarely observed properly in small businesses, making a computerised record about as much use as a raffle.

Three people actually took any advice on the selection of their system, and one of those was a salesman from a multiple electrical retail chain. This says much for the power of Amstrad's message and promotional philosophy that "price is all".

Naturally enough, the three who took the advice rated it as "good". I only know of one or two of the thousands who bought a PCW 8256 to be disappointed – and that was almost entirely due to their fundamental meanness at refusing to buy a big enough system to match their immediate needs.

Conclusions

Those of you who sent in a form with an SAE may wonder why you have not received a direct response. I have dark and terrible confession to make. The forms and SAE's were detached, and since the form does not contain a name and address, and I'm not into handwriting analysis, I regret the only solution was to stuff as much general information into the envelopes as would fit, and return them.

The fundamental advice to all is to choose and use your accounting software in conjunction with your accountant (he may find it as much fun as you do), and under no circumstances stop keeping manual records until you are 100 per cent confident that you have a system that can recover from accidents such as power cuts.

There are now so many different software products available for the PCW 8256 owner that the prime considerations should be:

1. Is the author available to support the product? You'll either pay in the basic cost or with a paid support scheme. Expect to pay for this service. There ain't no such thing as a free lunch, and software publishers who don't charge enough go bust: then where do you stand? Arriving just as the Official Receiver is towing the sleek black Porsche away is not going to rescue your payroll system when the NI rates have changed (yet again).

2. Does the software have any upgrade path – in other words, if your business grows and you upgrade your hardware, will you be able to transport your knowledge and your data with you? Avoid cul-de-sac products where your knowledge is locked in to the PCW8256.

There's plenty around where counterparts exist on IBM PC, CP/M 86 etc that you have no excuse to remain shackled to machine-specific software.

The future for small business computing

The Sage Rent scheme is a good idea – as well as being a very shrewd piece of marketing in its own right by one of the most wily and experienced firms in the business. Dealers wishing to take a grip on their localities could do much worse than instigate similar ideas of their own, and users could do far worse than take up such ideas – especially where a dealer is able to offer a broad choice from the entire gamut of software available.


One drawback in such a scheme is the uncertainty of software warranties, and the scope for the awkward customer to wreak havoc with unreasonable demands for assistance. So far, PCW 8256 owners have shown themselves to be model customers *(that means they can go through the door we've fitted to the Joyce on the cover – Ed)*, being small business people who understand the reality of business better than the hobbyist consumer who is happy to spend hours on the phone to a software house trying to work out how to get past level 99 on Space Invaders.

As long as we all learn from the gradual decline of the plush carpeted, expensively equipped computer shops selling systems costing upwards of £5,000, and approach small business computing with a cautious realism on all fronts, then Amstrad will have done the economy a great service.

Too bad the government isn't interested in creating a climate where it would be viable for Amstrad to make the PCW 8256 in the UK. But on the other hand, just look what happened to those manufacturers who tried.

ABC

What puts the **Plus** in the **ScratchPad** spreadsheet?



ScratchPad Plus is an electronic spreadsheet available for the Amstrad PCW 8256 and CPC 6128 computers. But it's the **Plus** that makes **ScratchPad** the only choice for all professional electronic spreadsheet users.

It's the **Plus** that gives what others give...

Plus

CAPACITY....

ScratchPad Plus is the ONLY spreadsheet that does not have an "OUT OF MEMORY" message – It doesn't need one! Because **ScratchPad Plus** is the ONLY spreadsheet that carries on giving you working space when other spreadsheets completely run out of steam.

The power of Virtual Memory!

ScratchPad Plus utilizes "Virtual" memory. Just like any other spreadsheet, it begins by building your model in memory. But unlike any other spreadsheet, **ScratchPad Plus** does not stop when you have used all the memory space available – It then pretends your disk drive is extra memory, and uses the space available to carry on calculating for you.

Anyone doing any serious spreadsheet work will tell you just how frustrating it can be when there just isn't any room left to complete your calculations!

Now that **ScratchPad Plus** is available, a spreadsheet just isn't worth considering unless it uses Virtual Memory!

Plus

FEATURES...

Multiple windows

Most spreadsheet programs allow you to view two parts of your spreadsheet at the same time. **ScratchPad Plus** is the only spreadsheet which gives you almost unlimited screen splitting capabilities.

Simultaneously view as many parts of your spreadsheet as will fit on the screen at the same time – Ask "what if" questions and see ALL the answers you need presented before you!

Design the spreadsheet around your application – Not the other way round!

With other spreadsheets, the theoretical number of rows and columns you can have is FIXED. If you need less columns, but more rows – NO CAN DO! With **ScratchPad Plus,** you decide how many actual rows and columns you require.

Display Pounds (£££££) not Dollars ($$$$$)

Let's face it – We are not part of the United States of America. Our currency is English Pounds (£), not US Dollars ($$$$$). **ScratchPad Plus** allows you to display the good old "£" sign – SOME OTHER SPREADSHEETS DON'T.

Plus

HELP...

Instant help

ScratchPad Plus has a comprehensive, easy to follow, user guide and tutorial which takes you step by step through all the features of the product. And there is a comprehensive set of help screens available to you all the time you are working with a spreadsheet.

Help just a phone call away

Every user of any Caxton product is backed by a skilled telephone support team who use the products themselves every day. If you have a question about **ScratchPad Plus** that the manual does not answer for you, it doesn't matter where you purchased our program from – just dial (01) 379 6502. The people who publish the product will help.

Help in the form of Training

Soon we will be beginning our series of **ScratchPad Plus** training courses at our training centre in Covent Garden. Pick up the phone and ask for details of prices and dates.

Plus SMARTKEY II! (WORTH £49.99)

For a limited period only, we are supplying FREE with each copy of **ScratchPad Plus** one copy of SmartKey II – the very clever keyboard enhancer and macro facility which works with most CP/M software. Combined with **ScratchPad Plus,** SmartKey II will allow you to display windows, recalculate models, save files and print by just pressing ONE KEY!

And combine SmartKey II with other programs to take the tedium out of any regular keyboard work you have to do.


The price of **ScratchPad** (and all the "**Pluses**") is just £69.99 inc of VAT. Available from all good dealers, or call

(01) 379 6502 NOW

Caxton Software Ltd.
10-14 Bedford St.,
London,
WC2E 9HE.
01-379 6502.

ScratchPad Plus is copyright SuperSoft. SmartKey II is copyright FBN Software.

POWER BEHIND



Light Pen

A sophisticated Graphics Package which includes a Colour Palette, Nudge Control for one pixel accuracy, Brush Choice, Text Handling and User Defined Characters.

It can Magnify, Shrink, create Circles, Rectangles, Lines, Curves and Colour Fill.

There is Picture Storage and Retrieval, a Pen Callibration utillity and Printer Dump.

There is casette driven or ROM software for the 464 and ROM software for the 6128.

Casette **£19.95.**
ROM **£29.95.**

Speech Synthesiser

A speech synthesiser and powerful stereo amplifier which greatly improves the quality of the internal speaker.

Extremely easy to use with an almost infinite vocabulary.

Supplied with text to speech convertor for ease of output creation.

Includes two high quality four inch speakers designed to compliment the Amstrad.

There is casette driven or ROM software for the 464 and ROM software for the 6128.

Casette **£29.95.**
ROM **£39.95.**

DK Tronics products are available in all good computer stores. If you have any local problems obtaining them contact us directly.

You can order by phone quoting your Barclaycard or Access number, orders are normally despatched in 24 hours.

YOUR AMSTRAD



64K Memory Expansion

Converts the 464 into a 6128 (except for the ROMS) and gives 128K of memory.

The 64K gives the same amount and configuration of RAM as the 6128.

It is supplied with bank switching software in the form of RSXs to use the second 64K RAM as storage for screens, windows, arrays and variables.

It allows the use of CPM plus as supplied with the 6128.

It requires no additional power supply.

£49.95.

256K Memory Expansion

Converts the 464 into a 6128 (except for the ROMS) and gives a total memory of 320K.

Gives the same memory configuration as the 6128 but there are four extra banks of 64K.

It is supplied with bank switching software in the form of RSXs to use the memory as storage for screens, windows, arrays and variables. The 250K can store 16 full 16K screens.

It allows the use of CPM plus as supplied with the 6128.

It requires no added power supply.

£99.95.

256K Silicon Disc

256K of RAM disc accessible many times faster than the conventional drive and with a greater disc capacity.

It can be logged on as drive B or in a two drive system as drive C.

It will accept all normal Amstrad disc commands i.e. load, save, cat, etc.


Data can be transferred onto the silicon disc from a normal disc or from RAM, application programmes can then work on the data at vastly increased speed.

£99.95.

dk'tronics

MANUFACTURERS OF POWERFUL PERIPHERALS

DK Tronics Limited
Englands Lane, Gorleston-on-Sea, Great Yarmouth, Norfolk NR31 6BE
Phone 0493 602926 (24 Hours), Telex 975408.



Thinking of buying a PCW 8256?

VISIT OUR SHOP AT 92 VICTORIA STREET LONDON SW1

- *COMPREHENSIVE DEMONSTRATIONS*
- *WIDE RANGE OF SOFTWARE AND SUPPLIES*
- *MAIL ORDER WELCOME*

BARCLAY CARD • ACCESS • AMERICAN EXPRESS DINERS • SAME DAY DESPATCH ON CREDIT CARD ORDERS

METYCLEAN
BUSINESS SYSTEMS

Metyclean House, 38/48 Monkton St.
London SE11 4TP
Tel: 01-582 5555

AUTHORISED IBM AND OLIVETTI DEALERS

Disappointed with your PCW 8256?

THEN PERHAPS YOU NEED TO BE TRAINED PROPERLY?

BOOK A TRAINING COURSE WITH METYCLEAN
RING 01-582 5555 NOW
OR
FILL IN AND RETURN THE COUPON BELOW

* Please send me details on Metyclean Training.

* Please telephone me to make a booking.

*(*Please delete as required)*

Name _____


Company _____

Address _____

_____

Postcode _____ Telephone _____

ABC SPECIAL



Add character to your Joyce

Cliff Lawson, the man from Amstrad technical, returns to present part 13 in his awe inspiring series of articles on the socio-economic effect of pink jelly on a settlement of lesser spotted wood voles. In fact it's really something to do with redefining the Joyce character set (on screen, not printer, sorry!), but that doesn't sound half as interesting.

Before we go any further, I think I had better make it clear that the rest of this article is unlikely to take any prisoners. Some of the sentences are of a highly technical nature and should be avoided by anyone scared of the-word PEEK.

Much to the protestations of the Editor, I think it has to be said that any normal thinking human being will prefer Sans-serif text to that used for setting this magazine. (Sans-serif means that the ends of the lines of letters don't have ostentatious twiddly bits).


The eagle eyed among you may have noticed that your Joyce also has serifs on some of its characters and, as I don't like them, I figured that something needed to be done. The fruit of my labours is presented here, a simple (???) way to redefine the entire Joyce character set (or just selected characters).

When we sell you a Joyce, there probably aren't many people who realise that we also throw in several hundred pounds worth of software. Locoscript itself must be worth several hundred and in addition to this you get Mallard Basic (£100), GSX (£200ish), Dr Logo (£3.37), and Digital Research Programming tools (SID, ASM, MAC, RMAC, LINK) (another £200ish). So it seems like a good idea to make the most of this. The one drawback of the multiplicity of assemblers that we supply is that they are all Intel 8080, rather than Zilog Z80 assemblers, but this isn't really a major problem if your head is screwed on the right way (your nose should point in the same direction as you walk).

Mission possible

Your task, should you choose to accept it, is to type in the two assembler listings shown here. They must be entered into a couple of files on disc and by far the easiest way of doing this is to use RPED. If you have set your CP/M disc s that it has a PROFILE.SUB as described on page 15 of the CP/M section in Book 1, then just type the word RPED. Once the editor has loaded, hit f3 to create a new file. When asked for a name, type in either REDEFINE.ASM or DOIT.ASM, depending on whether you are typing in listing 1 or 2. The spacing in assembler programs is not exactly critical, but it does ease readability if there is a good sized space between each field of an instruction.

When you have typed in the file name, before hitting Return it would be a good



```
A)type text.txt
To be or not to be, that is the question
Whether 'tis nobler in the mind
To suffer the slings and arrows of outrageous fortune
Or to take arms against a sea of trouble and by opposing end them.
To die, to sleep no more and by a sleep to say we end the heartaches
And the thousand natural shocks that flesh is heir to.
'Tis a consummation. Devoutly to be wished.
To die, to sleep, to sleep, perchance to dream.
Ay, there's the rub. For in that sleep of death
What dreams may come when we have shuffled off this mortal coil
Must give us pause,
There's the respect that makes calamity of such long life.
```

```
A)type text.txt
To be or not to be, that is the question
Whether 'tis nobler in the mind
To suffer the slings and arrows of outrageous fortune
Or to take arms against a sea of trouble and by opposing end them.
To die, to sleep no more and by a sleep to say we end the heartaches
And the thousand natural shocks that flesh is heir to.
'Tis a consummation. Devoutly to be wished.
To die, to sleep, to sleep, perchance to dream.
Ay, there's the rub. For in that sleep of death
What dreams may come when we have shuffled off this mortal coil
Must give us pause,
There's the respect that makes calamity of such long life.
```

Top: With serifs. Bottom: Sans-serif

idea to remove your system disc and insert a formatted blank that has a bit more space on it.

Putting it all together

Having entered these two files, the fun really starts. They both have to be assembled then linked and finally combined. To do this, you will need to get your (back up of) side 3/4 disc out of his box. Remove the disc onto which you have just saved DOIT and REDEFINE and insert side 3 to the left. Then type:

RMAC B:DOIT

After a short pause, you will be prompted to insert the disc for drive B:. Remove side 3 and insert the disc with the two files on it. Once this operation has been successfully completed, you should be met by the following:

CP/M RMAC ASSEM 1.1
0251
000H USE FACTOR
END OF ASSEMBLY

If anything else appears, then this almost certainly means that you have made a typing error, so go back to RPED, to correct the file (DOIT.ASM).

Once the file has been successfully assembled, remove the disc and insert side 3 again. This time, type:

LINK B:DOIT

You will be asked to insert the disc for drive A:, just hit a key. You will then be asked to insert the disc for drive B:. Insert the disc with the assembler files and then hit a key. This should produce the following:

ABSOLUTE	0000
CODE SIZE	0251 (0100-0350)
DATA SIZE	0000
COMMON SIZE	0000
USE FACTOR	00

So far, so good, now you'll have to repeat the whole process for REDEFINE.ASM. Insert side 3 and type:

RMAC B:REDEFINE

Helpful hint: RMAC is on the disc for drive A: (side 3) and REDEFINE is on the disc for drive B: (disc with assembler files). Then type:

LINK B:REDEFINE [OP]

This will produce a file called REDEFINE.PRL, which is a page relocatable file containing a CP/M RSX. This must be renamed:

REN REDEFINE.RSX=REDEFINE.PRL

This must be added on to DOIT.COM using:


GENCOM B:DOIT B:REDEFINE

(GENCOM is on side 3).

If you understood all of that, you should now have a disc containing a file called DOIT.COM. With this disc in the drive, type:

DOIT

All being well, the character set will now



6128/8256 OWNERS! PAY LESS FOR THE BEST PROFESSIONAL PROGRAMS.

SUPERCALC 2

"It can't be faulted . . . probably one of the top five best-known names in the business software world, used by companies worldwide. It makes the 8256 even more viable as a low-cost business system". (Popular Computing Weekly 12/85)

"A classic spreadsheet . . . one major advantage over most other 'Calc' programs is a HELP function . . . very easy to use, easy to learn . . a must for anyone who has hopes of running a business!" (Personal Computer World 02/86)

Clear, helpful manual with 12 lessons and sample spreadsheets already on disc. On-screen HELP. Advanced guide, too. 6128/8256. (Amsoft/Sorcim/IUS)

Save £5.00 on recommended price. Only £44.95.

CARDBOX

"Cardbox is a powerful database, it scores in being easy to use and understand". (Amstrad User 01/86)

Claimed to be the best electronic card-indexing system available. Now on the Amstrad for about £50 less than its usual price! Up to 65,000 cards in a file (depending on disk capacity.) Up to 26 fields and 1404 characters on each card. No limit to the number of indexed words you can search for on a card or file. Design cards as you wish. We've found Cardbox simple to use and the manual clear and helpful. 6128/8256. (Caxton)

Save £5.00 on recommended price. Only £94.99.

POPULAR ACCOUNTS

"The Sage package has the edge . . . the manual runs to 80 pages, is full of illustrations and is friendly, while still being concise". (Amstrad Action 02/86)

"Aimed at small businesses, but slightly larger than those who use Cash Trader . . . Sage maintains a User Hotline, which is extremely useful. This program is very powerful . . . it really does have all the power of more sophisticated accounts packages running on machines like the IBM PC, at a fraction of the cost". (What Micro? 02/86)

Detailed information/combination packages in our catalogue. 6128/8256. (Sage)

Save £5.00 on recommended price. Only £94.99.

AUDIO TUTOR

What the manual never taught you! Two double-sided audio cassettes take you through 4 forty-five minute, step-by-step lessons. Follow the instructions at your keyboard and learn to get the most out of your Amstrad soonest.

8256 only. (New Star Software) Two sound cassettes **£9.95.**

KEYBOARD TUTOR

This "Touch 'n' Go" keyboard tutor really works. By the end of the course, you should reach 40 words a minute with an alphabetic accuracy of 95% and a numeric accuracy of 100%. If you concentrate, you can do it in 24 hours!

6128/8256. (Caxton) **Only £24.99.**

"Quite simply, you're the best". *(G. Murrow, Edinburgh)*

DR GRAPH

Data can be entered either manually or from a spreadsheet like Supercalc. You can produce line, bar, scatter and stick graphs as well as pie charts and text-only charts. Works with both Amstrad and Epson-compatible printers.

Bar charts can be stacked, clustered or arranged in steps or sticks. Pie charts can include exploded slices. Combine line and bar charts in one if you wish. Choose from 3 different type-styles for your text (plus the Amstrad face). It's amazing the difference this program makes to the way you present your information. 6128/8256. (Digital Research)

Save £5.00 on recommended price. Only £44.95.

CASH TRADER

"One of the most-friendly pieces of software on a CP/M micro. The manual was hardly necessary at all . . . If, like many small firms, you do your own accounts, it will not impose on you . . . If your paperwork tends to be somewhat haphazard, Cash Trader is brilliant at creating order from chaos . . . it is flexible and capable of working in almost any small business environment . . . a powerful program, excellent value for any small business". (What Micro? 02/86)

Details in our catalogue. 6128/8256. (Quest)

Save £10.00 on recommended price. Only £104.95 or £139.45 with Analyzer too.

DISKS £37.50 for 10

Double-sided 3" blank discs. Each disc in a hinged clear plastic box. Buy discs singly if you wish for **£4.00** each. Or save on ten, just **£37.50.**

BUSINESS CATALOGUE

Send £1 for our catalogue of business software, refunded with your first order.

6128 GAMES CATALOGUE

Send £1 for our catalogue of 6128 games programs, refunded with your first order. 20,000 words, illustrated with screen shots, quotes all the reviews.

6128 G.A.C.

"The Graphic Adventure Creator combines greater power with much greater ease of use. Both graphics designer and text organiser are in memory at the same time . . . it's a beautifully designed package". (Popular Computing Weekly 10/85)

"The most astounding program I've ever encountered on an eight-bit machine . . . Those who want to write adventures will find there is no better value-for-money product on the market. The neat simplicity and power of the commands, coupled with the tiny 17K the program takes up, puts it far ahead". (Amtix 12/85)

6128 only. The Graphic Adventure Creator by Incentive. **Only £24.95.**

"By far the best service of any other mail order company".
(C. Green, Dorset)

TASWORD 6128

"For £24.95, you get a powerful and easy-to-use word processor and a superb data merge program . . . Tasword has truly grown up". (Amtix 12/85)

Text files up to 60,000 characters; on-screen HELP; all the expected features plus four on-screen notepads. 6128 only. (Tasman) **Only £24.95.**

TAS-SPELL 6128

"A very worthwhile system that meets, with ease, the requirements of all but the most prolific writers . . . very useful". (Amtix 12/85)

Dictionary disk with about 20,000 words on. Add your own words as you wish and check all your documents. 6128 only. (Tasman) **Only £16.50.**

TAPE/DISK TRANSFER

"A really good program with a professional sheen to the whole thing . . . very user-friendly and still works on very long programs, the only program to offer the option of sending output to printer". (Amstrad Action 02/86)

"A disk utility which gives 11 commands which make the task of tape-to-disk transfer literally child's play . . . I found the program invaluable. It performs extremely well . . . an invaluable aid for those with newly-acquired disk drives". (Popular Computing Weekly 11/85)

6128 only. TRANSMAT by Pride Utilities. **Only £11.95.**

MINI OFFICE 2

If you're just getting used to your 6128, this amazing suite of programs on one disk could be the best introduction you could buy to the powerful serious uses of your computer.

There's a WORD PROCESSOR with a 40 or 80 column display: a DATABASE which will pass records to the wordpro: a powerful SPREADSHEET and a GRAPH program: a COMMUNICATIONS program to access Microlink or Telecom Gold and even a LABEL PRINTER.

All modules will use the AMX Mouse if you've got one. If you haven't send for our catalogue and save money! 6128 only. (Database) **Only £19.95.**

LASER BASIC

"Of tremendous value to anyone wanting to become involved in graphics programming . . . as good as you're likely to get". (Amstrad Action 02/86)

"Brilliant new games-writing aid . . . the manual is thankfully comprehensive and easy to follow . . . more than just a games designer, it's a major shot in the arm for your computer, driving it to new heights of performance. It's in a completely different league to any sprites or games designer package you may have seen before". (Popular Computing Weekly)

Laser Basic adds 200 new commands to your BASIC and lets you create arcade games with music, sound and action. 6128 only. (Ocean/Oasis) **Only £19.95.**

HOW TO ORDER

ALL ORDERS NORMALLY DESPATCHED WITHIN 24 HOURS

1. PHONE **01-846 9353** at any time, 24 hours a day. Tell us your computer type, name, address, order, credit card type and number and expiry date, plus your own phone number. During office hours, you'll get a person, not our Ansaphone. Order from anywhere in the world; satisfied customers in 64 countries!

2. WRITE to us at **SPEEDYSOFT, 37 Church Road, London SW13 9HQ, England,** enclosing a sterling cheque, postal order or bank draft or give your credit card details as above.

ACCESS/VISA/EUROCARD/MASTERCARD honoured.

3. EITHER WAY, please add the appropriate charge for p&p to your order. UK addresses £1 per program, Europe £1.50 per program, elsewhere £2 per program. UK prices include VAT, export prices are the same because of the extra work.

TERMS OF BUSINESS

1. All orders must be pre-paid in sterling or charged to your credit card. The banks have agreed not to sell software as long as we don't give credit.
2. In the unlikely event that you receive a faulty disk, we will replace it at once. But, please, just return the disk, not the manual as well.
3. Most programs require you to copy them to make a working disk. We are therefore unable to exchange disks for any other program or to issue refunds
4. Our liability is limited to the replacement of program discs shown to be faulty. We cannot be held liable for any loss arising out of the use of these programs.

ACCESS VISA **SPEEDYSOFT 01-846 9353** **EUROCARD MASTERCARD**

have been changed (for the better?).

If you cast your eye over the file called DOIT.ASM, you will see that the majority of lines in it take the form:

```
db      '?',nn,nn,nn,nn,nn,nn,nn,nn
```

Where the '?' is the character to be defined (this can also be given as a numeric character number 0..255). This is then followed by 8 bytes of bit significant data that define the 8 successive lines of dots that make up a character. Anyone who has ever met user defined symbols of any sort (such as on other Amstrads, Sinclairs and Acorns) will no doubt see the exact method of use for this. Basically, if you draw the character to be defined on an 8 by 8 grid, then convert each line in turn into a binary number, these can then be used in such a definition.

If DOIT.ASM is changed, then it will have to be assembled and linked again (you don't need to do REDEFINE.ASM again). Then the RSX has to be added using GENCOM just as before. Once this is done, the command DOIT will once again redefine the selected characters.

The more enterprising amongst you may be wondering just how this rabbit was pulled out of the hat. (If your not one of these then retire satisfied at this point because the going is about to get really tough).


These programs demonstrate several useful lessons for the would be assembler programmer. Firstly it makes use of a CP/M RSX and therefore demonstrates how they are used.

In CP/M+, any modifications to the operation of the system can very easily be made using RSXs. I'll assume you already know what a BDOS call is. An RSX allows one to patch location 5 (the BDOS entry point) so that your external code can have a first look at the call being made before control is passed onto the original BDOS entry point. The beauty of this system is that these operating system modifications are contained within a relocatable module that can easily be attached to a .COM file so that it is able to make use of new BDOS calls or modified versions of the existing ones that can be used within a number of different driving programs. RSXs attached to a .COM file are loaded on page boundaries from the top of the TPA downwards. This gives a secondary benefit if a piece of code must reside in the common memory of plus (from#C000 to#FFFF), it need not be moved from an address at the lower end of the TPA to a fixed address at the top. Instead, CP/M+ will move it for you to an address that best suits it and will do any relocating needed into the bargain.

You may wonder why a piece of code would want to be in the top of memory in preference to being lower down. Well, the essence of operation of CP/M+ is that one bank (64k chunk) of memory contains the TPA while the rest of the CP/M and screen memory and so on are kept hidden within some other 64k chunk.

To communicate between TPA and screen memory, for instance when a character is to be printed, there must be a smallish piece of the memory shared between all banks so that values can be passed back and forth.

The 64k banks are really made up of four 16k blocks, one of which is common to all banks. There are various possible combinations used for the operation of CP/M. The BDOS bank is made up of blocks 7, 3, 1, 0, the TPA is 7, 6, 5, 4, there



is an extra combination of 7, ?, 8, ? and the screen environment is blocks 7, 2, 1, 0. Block 7 (the top 16k of TPA) is common to all these environments. The blocks contain the following:

0 BIOS extended jumpblock
1 Screen memory
2 Matrix RAM, roller RAM and some screen memory
3 BIOS and BDOS
4 Bottom 16k of TPA
5 Next 16k chunk of TPA
6 Third 16k chunk of TPA
7 Common – top of TPA plus switching code
8 CCP, hash tables and data buffers


From within the TPA it is possible to call one of the extended BIOS routines in block 0 by calling the USERF entry in the BIOS. This is achieved by getting the address at location 1 (WBOOT) and adding an offset of 87. This gives the address of the USERF routine.

This value can then be stored following a 0C3h opcode (JMP instruction) to produce a simple routine that can be called (just like ENTERFIRMWARE in Amstrad CP/M 2.2). The call is followed by an inline address that is the address of the routine to call.

One particularly interesting routine is at address 000E9h, this is known as SCRRUNROUTINE and will allow the screen environment bank to be switched in, thus allowing access to the screen memory, the roller RAM and the character matrixes. The matrixes are held at 0B800h to 0BFFFh and the effect of the program is to update a particular group of eight bytes that constitute one particular character.

The actual position in this area is given by multiplying the characters value by 8 and adding this to the base address (0B800h). The area of memory from 0B600h to 0B7FFh holds what is known as the roller RAM, this contains 256 words each of which is the address of a pixel line on the screen. This can be used for rolling the screen.

If you didn't understand all that you'll be pleased to know that neither did I. A good look at the example program shown here will probably tell you a whole heap



Software the professionals use!

Now available for the Amstrad CPC-6128, PCW-8256 and CPC-464 (with CP/M)

Caxton

Call our order hot-line now!

01-379 6502



Imagine you have to prepare a report, plan a holiday, launch a new product, arrange a wedding or simply sort out your ideas on a new activity.

BrainStorm is a three dimensional scratch-pad designed to be the quickest and most efficient way of organising your thoughts on any subject. It allows you to think, write, edit and structure all at the same time.

First dump your random thoughts into BrainStorm. Identify major points; jot in other thoughts as they come to you; maybe develop an idea that particularly appeals.

Unobtrusively BrainStorm starts to develop a model of what's on your mind. You don't have to screw up balls of paper, use an eraser or write things out again. You can cut, paste and amend your ideas at will. Add in afterthoughts, change emphasis and resequence...all at the touch of a few keys.

Introductory Amstrad Offer
Usually £224.25 Now **£49.99** inc VAT

BrainStorm is the equal to a word processor on words, or a spreadsheet on numbers. With it you will develop the ideas in your mind...all in a fraction of the time it takes with a scratchpad and pencil.

If you think you must BrainStorm.




SmartKey has the power to dramatically improve the way your personal computer works for you, by customising and automating your keyboard and software.

It enables you to assign any long, repetitive, or difficult-to-remember set of keystrokes to any single key on your keyboard. Press this key once and SmartKey, the electronic assistant, will do the work for you. It can be used with, and is invisible to, your other programs.

With word processors you can type standard paragraphs, reformat text, find files and change margins instantly. With spreadsheets you can define keys to display windows, recalculate models, save files and print automatically. And with databases you can find records, enter data and produce reports with just one keystroke.

Introductory Amstrad Offer
Usually £113.85 Now **£49.99** inc VAT

With these and other software products the possibilities are endless! SmartKey will increase your productivity, improve your accuracy and reduce your frustration. Your Amstrad computer will be a lot easier and a lot more fun to use.



Are you frustrated by the keyboard barrier? Would 'error prone and slow' fairly describe your keyboard skills?

Touch 'N' Go will change all this. It is a carefully designed keyboard skills course developed over the last 20 years. Having been implemented on today's business micro-computers it has achieved success as the UK's most popular typing tutor. And now it's available for the Amstrad range of disk-based computers.

Introductory Amstrad Offer
Usually £63.25 Now **£24.99** inc VAT

The course develops your skill on the QWERTY keyboard and numeric keypad. With a little concentrated effort you can achieve mastery in just 24 hours.

It is actually so much fun to use that it becomes addictive. So don't start using Touch 'N' Go when you have something more important you should be getting on with!

Touch 'N' Go gives you the opportunity to banish keyboard frustration forever and increase productivity with the software products you use.



Cardbox is the most popular, the most flexible, the fastest and in fact THE BEST simple electronic card-indexing system on the market.

With Cardbox you can maintain instantly accessible records of customers, suppliers, staff, books, journal extracts, club memberships, widgets and just about anything you can think of. You design the card layouts yourself and index the information as you put it in. You can have any number of keywords in a file, display or print cards in any format and exchange information with other programs.

Introductory Amstrad Offer
Usually £143.75 Now **£99.99** inc VAT

You can have up to 65,000 cards in any one file (depending on disk capacity). Each card can have up to 1404 characters on it. There can be up to 26 fields on each card. The largest field you can have is 1404 characters (the size of the card). And there is absolutely NO LIMIT to the number of indexed words you can have on a card or in a file.

Offers last for a limited period only.

Please add £3 P&P per product.

© Cardbox – Business Simulations; SmartKey – FBN Software; Touch 'N' Go – Harcourt Systems; BrainStorm – BrainStorm Software.

Caxton

Caxton Software Ltd.,
Lading House, 10-14 Bedford St.,
London WC2E 9HE.

Our Software w
to end your pape

If you run a small business you'll know, only too well, how much unproductive time you spend on that necessary evil, paperwork.

Quest Business Software for the AMSTRAD, IBM and COMPATIBLES and most CP/M micros will, quite simply, relieve you of the paperwork millstone and can PAY FOR ITSELF in as little as ONE MONTH by dramatically increasing your efficiency and profitability.

Since our award winning CASH TRADER was published last year we've considerably expanded our range of Business Software to save you time on accounting, searching through files, typing letters and producing reports.

As many of our packages are available for evaluation prior to outright purchase, you've everything to gain by ordering today. Just because our software costs less it doesn't mean that we've cut corners or skimped on detail – thousands of users, world wide, will testify to that!

All Quest Business Software is very easy to use and we've paid particular attention to provide detailed documentation, and, should you need it, Ongoing support.

You could say that we haven't slept . . .
. . . So you can.

AMSTRAD BUSINESS CONTROL SYSTEM+
QUEST BUSINESS CONTROL SYSTEM*

THE LOW-COST FULLY INTEGRATED ACCOUNTING SYSTEM WITH OVER 30,000 USERS WORLDWIDE!

"Behaves like much more expensive software, and is well structured" 'What Micro' Feb. '86.

These accounting systems designed for the Amstrad, IBM (and compatibles) and most CP/M micros put the power of fully integrated accounting within even the smallest budget. The three modules, of which the system comprises, are Sales Ledger/Invoicing/Stock Control : Purchase Ledger : Nominal Ledger. Modules may be purchased independently if required and full software support is available.

All packages are fully documented and an evaluation suite for ALL THREE modules is available.

EVALUATION COPY ONLY £19.95! (14 day Money Back Guarantee)

CASH TRADER*+

"If your paperwork tends to be somewhat haphazard, Cash Trader is brilliant at creating order out of chaos" – 'What Micro' Feb. '86.

Cash Trader has sold over 5,500 copies since its launch last year and has been universally acclaimed. Designed for business people – not accountants – Cash Trader is as easy to use as a Cashbook with the added advantages of automatic totalling and cross costing, the ability to produce printed reports for VAT and Auditors' requirements and the tremendous benefit of accepting ANY TYPE OF ENTRY in ANY ORDER – eliminating tedious manual paperwork sorting.

Additional reports from CASH TRADER may be simply produced with ANALYSER – a low cost add-on module.

Cash Trader and Analyser are supplied with full documentation and software support, if required.

. . . "an outstanding and original contribution to business profitability and efficiency" The Standard Micro Business Awards. Sept. 1985.

EVALUATION COPY ONLY £19.95! (14 day Money Back Guarantee)

+ For Amstrad WPC 8256, CPC 6128, 664 and 464 (Twin Drive)
* IBM, Compatibles and most MSDOS or CP/M micros. Cash Trader can run on a single drive.



orks like a dream
rwork nightmares.

THE AMSTRAD POCKET SERIES

WORD PROCESSING : SPREADSHEET : DATABASE : REPORT GENERATOR 'Office Automation at a price to suit your pocket'.

Sold in 42 countries, these four essential business tools originate from MicroPro – the authors of WORDSTAR – the best known software package ever produced.

POCKET WORDSTAR WITH MAILMERGE – Professional WORDPROCESSING with a host of features and incorporating MAILMERGE. to allow personalised letters and address labels, etc., to be extracted from MAILMERGE.

POCKET SPELLSTAR – will check the spelling in your correspondence automatically, from a 'dictionary' stored in your computer.

POCKET CALCSTAR – Enjoy the benefits of accurate forecasting and planning with this spreadsheet.

POCKET DATASTAR – Your electronic filing cabinet in which valuable information is held safely and is accessed and sorted at the touch of a button.

POCKET REPORTSTAR – Designs and generates the reports you need – in the form that you require them. Invaluable when used with DataStar

WORDLINK – Links ABC accounting with POCKET WORDSTAR to enable details from your ledgers to be utilised for WORDPROCESSING. Wordlink, for example, will enable you to send personalised letters to all accounts more than 30 days overdue – Automatically.

TYPING TUTORS

KEYBOARD COACH – Absolute beginners will soon increase their speed and accuracy with this easy-to-use tutor. **MASTERTYPE** – for "two fingered typists" to help bring other fingers into play WITHOUT starting from scratch.

Amstrad and most CP/M machines. Twin drives advisable.

MATCHBOX

The stand-alone Electronic Card Index you can't afford to be without!

Only £29.95

MATCHBOX is one of the easiest to use software packages ever designed. It allows you both to store information (e.g. customer records, product specifications etc.) and then to sort it in a variety of forms that may then be used, if requried, to print out lists or labels.

Features include:

- Up to 32000 Records per File
- Up to 30 Alpha or Numeric fields per record
- Sorts on any selected field.

MATCHBOX is equally valuable for business or private use!

Amstrad 8256, 6128. Can run on a single drive.

WAGES AND SSP*+

How much time do you spend calculating Wages, Tax, and N.I. or maintaining SSP records? Too much?

Our WAGES and SSP package takes all the hassle away by automatically calculating salaries, wages and overtime.

Income Tax and N.I. contributions are also calculated and payslips produced together with comprehensive payday reports. The system also creates Year End Forms P14/P60 and P35 (CS).

Full SSP records are maintained, sick pay due calculated and reports printed.

Annual updates for TAX and N.I. changes are available together with full software support, if required.

EVALUATION COPY ONLY £19.95
(14 day Money Back Guarantee)

* Runs on AMSTRAD WPC 8256m CPC 6128, 664 and 464
+ IBM and Compatibles, Apricot.

SOFTWARE FOR ACCOUNTANTS*+

SHOEBOX. A powerful Incomplete Records Program produces Trial Balance, Profit & Loss A/C and Balance Sheet, simple to use, rapid entry routine, automatic VAT extraction. Links to Wordstar for tailored reporting, comprehensive audit trial, up to 300 Nominal Accounts with 99 sub analysis codes in each.

POCKET WORDSTAR accepts Final Accounts reports from Shoebox, offers comprehensive editing and printing options.

TIME RECORDER records Time and Disbursements, Caters for up to 200 clients with 150* charge rates, produces comprehensive WIP reports.

* Volumes for Amstrad, IBM and compatibles accommodate more
** Amstrad WPC 8256, CPC 6128, 664 and 464 with Twin Drives and most dot matrix or daily wheel printers.

quest

AMSTRAD BUSINESS CONTROL SYSTEM AND QUEST BUSINESS CONTROL SYSTEMS

Please send me **Sales Ledger, Invoicing and Stock Control**	£99.00 inc VAT ☐
Please send me **Purchase Ledger**	£33.00 inc VAT ☐
Please send me **Nominal ledger**	£33.00 inc VAT ☐
Please send me **Evaluation/Demonstration Suite** (all 3 modules)	£19.95 inc VAT ☐

CASH TRADER WITH ANALYSER

Please send me **Evaluation** copy	£19.95 inc VAT ☐
Please send me **Cash Trader** – full working copy	£99.95 inc VAT ☐
Please send me **Cash Trader with Analyser**	£149.95 inc VAT ☐

SOFTWARE FOR ACCOUNTANTS

Please send me **Shoebox**	£149.95 inc VAT ☐
Please send me **Pocket Wordstar**	£99.95 inc VAT ☐
Please send me **Time Recorder**	£69.95 inc VAT ☐

AMSTRAD POCKET SERIES

Please send me **Pocket Wordstar with MailMerge**	£99.96 inc VAT ☐
Please send me **Pocket Spellstar** (Spelling Checker)	£39.95 inc VAT ☐
Please send me **Pocket Calcstar** (Spreadsheet)	£49.95 inc VAT ☐
Please send me **Pocket Datastar** (Database)	£69.95 inc VAT ☐
Please send me **Pocket Reportstar** (Report Generator)	£49.95 inc VAT ☐
Please send me **Wages** and **Statutory** Sick Pay	£69.95 inc VAT ☐
Please send me **MATCHBOX**	£29.95 inc VAT ☐
Please send me further details	☐

Total: _____

Evaluation Copies

Evaluation copies are usable but a restriction on the number of entries exists.

On payment of the balance you will be given a password to remove the restriction and enable full use to be made.

If, for any reason you find the product unsuitable for your purposes, send the evaluation copy back within 14 days for a full refund.

I enclose my cheque made payable to Quest International Computers for

Total: _____ Please debit my Access/Visa/American Express Card No:

☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐

Microcomputer Used _____ Name: _____

Address: _____

_____

Tel: _____ Type of Business: _____

ACU 4/86

Quest International Computers Ltd., School Lane, Chandlers Ford, Eastleigh, Hants. SO5 3YY Tel: (04215) 66488

```
***REDEFINE.ASM****

wboot           equ     1
charmat         equ     0b800h
scrrunroutine   equ     000e9h
        cseg
        db      0,0,0,0,0,0
        jmp     start
next:   db      0c3h
        dw      0
prev:   dw      0
remov:  db      0ffh
nbank:  db      0
        db      'NCHARSET'
loader: db      0
        db      0,0
start:
        mov     a,c
        cpi     73
        jz      begin
        jmp     next
begin:
        lxi     d,buffer
        lxi     b,9
        db      0edh,0b0h ;move parms to high mem before switch
        lhld    wboot
        lxi     d,87
        dad     d
        shld    cjfirm
        lxi     h,buffer
        lxi     b,code
        call    entfw
        dw      scrrunroutine
        ret
entfw:          db      0c3h
cjfirm:         dw      0
code:
        mov     a,m             ;get char number
        inx     h
        push    h
        mov     l,a
        mvi     h,0
        dad     h
        dad     h
        dad     h
        lxi     d,charmat
        dad     d
        push    h
        pop     d
        pop     h
        lxi     b,8
        db      0edh,0b0h       ; ldir
        ret
buffer:
        ds      10
        end
        lxi     h,table
        mvi     b,64
fred:
        mvi     c,73
        push    h
        push    b
        call    5
        pop     b
        pop     h
        lxi     d,9
        dad     d
        dcr     b
        jnz     fred
        rst     0
table:
        db      '0',038h,06Ch,0C6h,0C6h,0C6h,06Ch,038h,00
        db      '1',018h,038h,018h,018h,018h,018h,018h,00
        db      '2',03Ch,066h,06h,03Ch,060h,060h,07Eh,00
        db      '3',03Ch,066h,06h,01Ch,06h,066h,03Ch,00
        db      '4',01Ch,03Ch,06Ch,0CCh,0FEh,0Ch,0Ch,00
        db      '5',07Eh,060h,060h,07Ch,06h,066h,03Ch,00
        db      '6',03Ch,066h,060h,07Ch,066h,066h,03Ch,00
        db      '7',07Eh,06h,06h,0Ch,018h,018h,018h,00
        db      '8',03Ch,066h,066h,03Ch,066h,066h,03Ch,00
        db      '9',03Ch,066h,066h,03Eh,06h,066h,03Ch,00
        db      'A',03Ch,066h,066h,07Eh,066h,066h,066h,00
        db      'B',07Ch,066h,066h,07Ch,066h,066h,07Ch,00
        db      'C',03Ch,066h,0C0h,0C0h,0C0h,066h,03Ch,00
        db      'D',078h,06Ch,066h,066h,066h,06Ch,078h,00
        db      'E',07Eh,060h,060h,078h,060h,060h,07Eh,00
        db      'F',07Eh,060h,060h,078h,060h,060h,060h,00
        db      'G',03Ch,066h,0C0h,0C0h,0CEh,066h,03Ch,00
        db      'H',066h,066h,066h,07Eh,066h,066h,066h,00
        db      'I',07Eh,018h,018h,018h,018h,018h,07Eh,00
        db      'J',0Ch,0Ch,0Ch,0Ch,0CCh,0CCh,078h,00
        db      'K',066h,066h,06Ch,078h,06Ch,066h,066h,00
        db      'L',060h,060h,060h,060h,060h,060h,07Eh,00
        db      'M',06Ch,0FEh,0FEh,0D6h,0D6h,0C6h,0C6h,00
        db      'N',0C6h,0E6h,0F6h,0DEh,0CEh,0C6h,0C6h,00
        db      'O',07Ch,0C6h,0C6h,0C6h,0C6h,0C6h,07Ch,00
        db      'P',07Ch,066h,066h,07Ch,060h,060h,060h,00
        db      'Q',07Ch,0C6h,0C6h,0C6h,0DAh,0CCh,076h,00
        db      'R',07Ch,066h,066h,07Ch,06Ch,066h,066h,00
        db      'S',03Ch,066h,060h,03Ch,06h,066h,03Ch,00
        db      'T',07Eh,018h,018h,018h,018h,018h,018h,00
        db      'U',066h,066h,066h,066h,066h,066h,03Ch,00
        db      'V',066h,066h,066h,066h,066h,03Ch,018h,00
        db      'W',0C6h,0C6h,0C6h,0D6h,0FEh,0FEh,06Ch,00
        db      'X',0C6h,06Ch,038h,038h,06Ch,0C6h,0C6h,00
        db      'Y',066h,066h,066h,03Ch,018h,018h,018h,00
        db      'Z',0FEh,06h,0Ch,018h,030h,060h,0FEh,00
        db      'a',00h,00h,078h,0CCh,0CCh,0CCh,076h,00
        db      'b',060h,060h,07Ch,066h,066h,066h,07Ch,00
        db      'c',00h,00h,03Ch,066h,060h,066h,03Ch,00
        db      'd',0Ch,0Ch,07Ch,0CCh,0CCh,0CCh,074h,00
        db      'e',00h,00h,03Ch,066h,07Eh,060h,03Ch,00
        db      'f',03Ch,066h,060h,078h,060h,060h,060h,00
        db      'g',00h,00h,03Ch,066h,066h,03Eh,06h,03Ch
        db      'h',060h,060h,07ch,066h,066h,066h,066h,00
        db      'i',018h,00h,018h,018h,018h,018h,018h,00
        db      'j',06h,00h,06h,06h,06h,066h,066h,03Ch
        db      'k',060h,060h,066h,06Ch,078h,06Ch,066h,00
        db      'l',030h,030h,030h,030h,030h,036h,01Ch,00
        db      'm',00h,00h,06Ch,0FEh,0D6h,0D6h,0C6h,00
        db      'n',00h,00h,05Ch,066h,066h,066h,066h,00
        db      'o',00h,00h,03Ch,066h,066h,066h,03Ch,00
        db      'p',00h,00h,07Ch,066h,066h,07Ch,060h,060h
        db      'q',00h,00h,07Ch,0CCh,0CCh,07Ch,0Ch,0Eh
        db      'r',00h,00h,07Ch,066h,060h,060h,060h,00
        db      's',00h,00h,03Ch,060h,03Ch,06h,07Ch,00
        db      't',030h,030h,03Ch,030h,030h,036h,01Ch,00
        db      'u',00h,00h,066h,066h,066h,066h,03Ch,00
        db      'v',00h,00h,066h,066h,066h,03Ch,018h,00
        db      'w',00h,00h,0C6h,0D6h,0D6h,0FEh,06Ch,00
        db      'x',00h,00h,0C6h,06Ch,038h,06Ch,0C6h,00
        db      'y',00h,00h,066h,066h,066h,03Eh,06h,03Ch
        db      'z',00h,00h,07Eh,0Ch,018h,030h,07Eh,00
        db      '#',03ch,066h,060h,0f8h,060h,060h,07eh,00h
efw:    db      0c3h
hidihi: dw      0
```

Listing 1: Redefine.ASM

more than a multitude of fatuous waffle.

REDEFINE.ASM contains the code to implement my RSX. This adds a new BDOS call (73, well why not?). The header information contained within the first 27 bytes at the top of this file will always be pretty similar whenever you want to implement a new RSX.

The first six bytes are always 0 and are filled when the RSX is loaded. The next three contain a jump instruction to the start of your interception routine. The following couple will be followed by the address of the previous module. This is the address to call if a BDOS function is required within the RSX.

This is followed by a single byte that should be OFFh if the RSX should be removed from memory next time the RSX is loaded and 000h if it should remain. An eight byte name will follow this. The loader flag indicates whether or not this is the last RSX in the chain. Finally there are a couple of bytes that are reserved.

```
cseg                    mvic,73
                        pushh
lhld1                   pushb
lxid,87                 call5
dadd                    popb
shldhidihi              poph
callefw                 lxid,9
dw0c2h                  dadd
                        dcrb
lxih,table              jnzfred
mvib,64                 rst0
fred:
```

Listing 2: Do it.ASM

The first thing the RSX code should do is check the value in register C. If this contains the value of the BDOS call to be intercepted the routine is entered, otherwise control is passed to the next: routine.

In this example the RSX intercepts BDOS call 73. If this is called the nine bytes pointed to by HL are moved into a buffer in common memory. The address of USERF is calculated and stored then used to access the SCRRUNROUTINE.

This calls a small section of program entitled code: which picks up the character number which is multiplied by 8 and added to the base address of the matrixes. Finally the new definition is moved into place with an LDIR operation accessed by a db in 8080 code.

Well, my good God, that was interesting wasn't it. I am sure we can all sleep a little sounder in our beds tonight, happy in this new found knowledge. Seriously though if that's possible, the above has shown how values can be moved from CP/Ms TPA into the bank containing the screen memory and so on so there is no longer any excuse for people not to produce some amazing graphic effects on the machine. Yeah, I know you were all just about to do it in GSX anyway.

ABC

Amstrad–PCW 8256

Standard 5¼" Add On Disk Drives

100% CP/M Software and LocoScript Compatibility using Low Cost Floppies

DRIVE 1	DRIVE 2
DOUBLE SIDED	DOUBLE SIDED
40 TRACK 360K	80 TRACK 720K
£177.50	**£207.25**

PC/MS DOS ↔ CPM Transfer Utility
Allows 360K Drive to Read and Write
IBM FILES, Read Only with 720K
£23.50

Enquire for other Transfer Formats
or other Disk sizes (3", 3.5", 8").
PRICES INCLUDE INSTALLATION SOFTWARE, P&P & VAT.

BOX LTD.
22 Hendred Street, Oxon OX4 2ED.
Tel: (0865) 717968

PCW 8256
WORD PROCESSOR
LOCOSCRIPT
INSTRUCTION

London and Provinces
Full Day Course – £55
For Brochure
0651-6446

Tel.
Or write
GRAYFIELD LTD.
FREEPOST
AB5 8QL
(No stamp required)

COMPACT
WORDSTAR, SUPERCALC
NEWWORD CRACKER



COMPACT
ACCOUNTING SOFTWARE
for the **AMSTRAD PCW 8256** from **£49.45**

***Award Winning Compact Software** with over 12,000 packages already in use in businesses large and small has been tested and recommended by leading British accountants. The incredible value and success of Amstrads PCW 8256 Business Computer has enabled Compact to offer its proven packages at a fraction of the normal cost • **DAYBOOK £49.45** our entry level system for the retailer or small trader includes everything necessary to imitate manually kept books. ie. Sales Daybook, Purchase Daybook, Cash Book, Nominal Ledger • **COMPACT ACCOUNTS £199.99** is our easy to use Complete Accounting System including Sales Ledger, Invoicing, Purchase and Nominal Ledger. It produces Invoices, Statements also Debitors and Creditors Analysis, provides Credit Control Functions, Budgeting, VAT Analysis and Reporting. Full Audit Trails Product Profitability Analysis and Comprehensive Management Reporting to Trial Balance • **COMPACT PAYROLL £99.99** Deals with weekly, fornightly, 4 weekly and monthly payrolls and conforms to all the latest N.I. and S.S.P. requirements. If you only require a single ledger ie. Sales ledger or Nominal Ledger each can be purchased separately at **£69.99** inc. VAT. All Compact packages can transfer data to **SUPERCALC, NEWWORD MULTIPLAN CRACKER, WORDSTAR.** So you can prepare cashflow charts with Supercalc or write to your customers using Newword without re-entering data already created in your accounting system. So don't delay **order today and let Compact start helping your business now!**

What the Papers say:- "COMPACT is a very well written system, extremely good value for money and very powerful". PC USER January 1985 — "COMPACT ledgers offer some excellent features for the small company". MICRO DECISION December 1985.

*In 1984COMPACT SOFTWARE won the "RITA" award which is to the information technology world what the "Oscar" is to the film industry.

COMPACT DAYBOOK inc. VAT + p&p = **£52.90** ☐
COMPACT ACCOUNTS inc. VAT + p&p **£203.00** ☐
COMPACT PAYROLL inc. VAT + p&p = **£103.00** ☐
SINGLE LEDGERS inc. VAT + p&p = **£73.00** ☐
(state which Ledger) _____

I enclose cheque payable to COMPACT SOFTWARE LTD. for ☐

Return to COMPACT SOFTWARE LTD.
1 Ensbury Park Road, Bournemouth, Dorset BH9 2SQ

NAME _____ ACU4

COMPANY _____

ADDRESS _____

_____

TEL. NO. _____ *Please allow 28 days for delivery.*

"Quite the best and most flexible personal accounts system I've seen – doubles as an inexpensive business system"
Computing with the Amstrad review, September 1985.

Unrivalled features

MONEY MANAGER

Unbeatable value

AMSTRAD CPC464 CPC664 CPC6128 PCW8256 PCW 8512

Financial management software for personal and/or small business use.

OVER 1000 SATISFIED USERS

Record all your financial transactions, and analyse them to see where you stand. Make the most of your money, monitor your cash flow, check your bank or credit card statements, pacify the bank manager, convince the tax man, avoid nasty surprises!

12 months of entries are kept in a file stored on your disc or tape. At any time, you may load a file into the computer memory, add to or edit the entries, analyse them, print statements and then save the updated file for later use. Entries may be historic (for record keeping) or forecast (for budgeting). You may have any number of separate files, and make copies of files for archive purposes. You may advance the period covered by a file month by month.

Up to 100 separate transactions may be entered per month.
Each entry consists of:

- The day of the month, e.g. 23rd of June.
- An account number, one of up to 9 defined by you to suit your circumstances e.g. 1=Barclays, 2=Visa, 3=Halifax etc.
- Reference, e.g. ABC123 for a cheque number or invoice reference.
- A class code, one of up to 50 defined by you to suit your circumstances e.g. h0=Household expenses, h1=Mortgage, h2=Rates or p0=Production, p1=Raw materials, p2=Assembly, p3=Packing etc.
- A description so that you can see what each transaction was for, e.g. "New gearbox" or "Box of 10 discs".
- The amount of the transaction, which may be plus or minus.
- An optional single character mark which you may include for further classification e.g. b=business, p=private, v=VAT, etc.

You may select categories according to account, class and mark (e.g. all motoring expenses for business using a credit card) and produce reports as follows:

- Full detailed statements, showing each transaction for any month or for the whole year.
- Tables showing the totals in each class for each month of the year.
- Tables showing the totals in each class for each account.
- Tables showing monthly maximum, minimum, average balances, turnover, cashflow etc, (disc versions only).
- Bar graphs of any category month by month.
- Pie charts of annual totals for various categories (CPC versions only).

Comprehensive manual and full set of practice data included. Full telephone support.

CPC cassette £14.95 CPC disc £17.95 PCW disc £23.95 (incl. VAT, p&p)

Send cheque or credit card number or phone for immediate delivery.

Connect Systems

VISA

3 Flanchford Road, London W12 9ND
01-743-9792 8am-10pm 7 days a week

Access

TURN YOUR *PCW8256* INTO A COMPLETE BUSINESS WORKSTATION WITH SIAS the Simplified Integrated Accounting System

- FULLY INTEGRATED COMPLETE BOOKKEEPING/ACCOUNTS SYSTEM

Each transaction need only to be entered once, all relevant ledger postings happen automatically at the time of posting.

- SPECIALLY WRITTEN FOR PCW8256

Utilizes the RAM Disk to eliminate the need for changing disks during the day.

- PERSONALIZED INVOICES/STATEMENTS/REMITTANCES

- Produces Professional Documents with Full Business Details on inexpensive blank paper thus improving your companies image.
- Desinged to fit standard window envelopes.

- LARGE FILE CAPACITY

Sufficient Sales, Purchase, and Nominal Ledger Records may be kept for most businesses on 1 data disk.

- EASY TO USE - Designed for Inexperienced Users.

Full instructions for use appear on the screen. The comprehensive manual need only be used for reference.

- FULL CUSTOMER TELEPHONE SUPPORT

Sales Ledger
- Invoice Posting
- Cash Receipts
- Debtors List
- Statements
- View Account

Purchase Ledger
- Bill Posting
- Cash Payments
- Creditors List
- Remittances
- View Account

Name & Address Labels

Nominal Ledger
- Lists of Accounts
- Reports
- Periodic Transactions
- N.L. History

Cashbook
- Bank Statement Entry
- Full Reconcilliation
- Periodic Transaction
- View (gives TRUE cash status)

VAT Returns

Invoicing/Credit Notes

Management Reports
1) Stock Report
   - Value of Stock
   - Cost of Sales
2) Assets
   - Including Depreciation
3) Prepayments & Postpayments
4) Expenses
5) Profit & Loss
6) Balance Sheets

All reports are available in the following time frames
- to Date
- Estimated Year
- Last Year
- Budget
- % Change on Budget
- % Change on Last Year

- Contact us NOW for more information
Dealer enquiries welcome

ONLY £149 +VAT

WREXHAM COMPUTER CENTRE

24 ABBOT STREET, WREXHAM, CLWYD. LL11 1TA
TELEPHONE (0978) 358832

The great Caxton give-away



The Amstrad PCW 8256 is much more than just a word processor. There are now many programs available which enable you to use it as a spreadsheet computer, database computer, ideas processor and so on.

Caxton software has become one of the leading suppliers of software for the PCW8256. This month they have donated one of each of their top selling programs to be used as a prize in our competition. The first correct entry will win a copy of Cardbox, Scratchpad plus, Brainstorm, Touch 'n' Go and SmartKey. This is a prize worth nearly £350. The five runners up will each win a copy of Touch 'n' Go.

All you have to do to enter this competition is answer the seven questions which appear below. To answer question seven simply telephone Caxton on 01-379 6502 and ask the name of the person on the end of the line. (The other end – Ed). The closing date for the competition is Tuesday, April 29. Good Luck.

The Questions

1. Caxton was the first English printer. What was his first name?
2. Caxton software use 'The Thinker' as a logo for the 'Brainstorm' ideas processor. Who sculpted 'The Thinker'?
3. Touch 'n' Go makes using any kind of typewriter keyboard easier. Who invented the typewriter?
4. All the Caxton software for Amstrad computers runs under CP/M. What does CP/M stand for?
5. What is the theoretical maximum number of records that can be stored using Cardbox?
6. What is special about the way Scratchpad uses its memory?
7. Name someone who works for Caxton.

Rules

1. Only one entry per person. You may photocopy the form, but anyone submitting more than one form will have all entries disqualified.
2. The judges' decision is final.
3. No employees of Amstrad, Amstrad User, nor their relatives or friends may enter.
4. Entries should be sent to: *Caxton Competition, Amstrad User, 169 Kings Road, Brentwood, Essex CM14 4EF.*

Answers

1. _____
2. _____
3. _____
4. _____
5. _____
6. _____
7. _____

Name _____

Address _____

_____

_____

_____

_____

_____

IF YOU REALLY WANT TO KNOW THAT THE PROGRAM YOU BUY WILL MATCH YOUR REQUIREMENTS AND YOUR WALLET

Then come to:

Software City

THE UK'S NO. 1 SOFTWARE DEALER Limited

AND TAKE A LOOK AT THIS SELECTION FOR THE PCW 8256

FREE.....
90 Day 'Hotline' support provided with all Sagesoft Programs.

FREE.....
'ONE TO ONE' Mailbox worth £50 with every 'Chit Chat' package.

Sage 'Chit Chat'... The ability to send a TELEX for under £500.

Sage 'Popular' Accounts	**£99.95**
Sage 'Popular' Payroll	**£69.95**
Sage 'Popular' Invoicing and Stock Control	**£69.95**
Sage 'Popular' Combo ('Popular' Accounts/Payroll)	**£149.95**
Sage 'Popular' Accounts Plus ('Popular' Accounts/Invoicing and Stock Control)	**£149.95**
Sage Super Combo ('Popular' Accounts/Invoicing and Stock Control/Payroll)	**£199.95**
Sage Accounts Statement Paper per 1000 sheets	**£40.00**
Sage Payroll Payslips per 250	**£12.50**
Sage Retrieve Database	**£69.95**
Sage 'Chit Chat' Viewdata (ie. Prestel)	**£69.95**
Sage 'Chit Chat' E Mail	**£69.95**
Sage 'Chit Chat' Combo (Viewdata and E Mail)	**£99.95**
Sage Modem with Viewdata or E Mail (requires RS232)	**£199.95**
Sage Modem with Viewdata and E Mail (requires RS232)	**£239.95**

RS232 Interface
Printer Cables
Printer Ribbons
3" Disks
Tractor Feed Paper
Labels
CP/M PLUS Books
3" Disk Boxes (holds 30)
Dust Covers

DR CBasic Compiler	**£49.95**
DR Graph	**£49.95**
DR Pascal/MT+	**£49.95**
DR Draw	**£49.95**
Caxton Cardbox	**£99.95**
Caxton Touch 'N' Go	**£24.95**
Caxton Scratchpad	**£69.95**
Caxton Smart Key II	**£49.95**
Caxton Brainstorm	**£49.95**
The Cracker	**£49.00**
Saxon Flexi-File	**£49.95**
Compsoft Delta	**£99.95**
Supercalc II	**£49.95**
Locoscript Tutorial	**£9.95**
AT LAST	**£49.95**

AT LAST is a fully relational database including up-to-date sorting on pre-defined keys.

For the Service you've always wanted but couldn't find!

Demonstrations available. Installations carried out if necessary.


382 Kings Road
Chelsea
London
SW3 5UZ
Tel: 01-352 9220

14 Thames Street
Kingston Upon Thames
Surrey
KT1 1PE
Tel: 01-541 4911

47 Cheap Street
Newbury
Berkshire
RG14 5BX
Tel: 0635 31696

Mail Order Welcome
***ACCESS and VISA or cheques to* 'Software City'**
Trade and Export enquiries welcomed.

the CAMSOFT professional range of business software for the Amstrad PCW 8256



cambase database
stock control
invoicing
sales ledger
purchase ledger
nominal ledger
payroll

NEW FOR 1986

- ★ full use of all 8256 features
- ★ set up file sizes
- ★ any disc drives
- ★ single key commands
- ★ export data
- ★ large screen displays
- ★ cursor controlled editing


Send for data sheet to:
Cambrian Software Works Ltd, Unit 2, Maenofferen,
Blaenau Ffestiniog, Gwynedd, Wales, UK.

AMSTRAD AUTHORISED DEALER

HARROW

AMSTRAD AUTHORISED REPAIR CENTRE

AMSTRAD PCW8256 512



PCW 8256 with 512k **£399**

PCW 8256 with 256k **£385**

PCW Second Disk Drive **£138**

PCW Modem/Printer Interface **£59**

RAD SYSTEMS
Tel: 01-863 2559

DELIVERY: £8. ADD 15% VAT.
RAD SYSTEMS
Business Technology Centre
111 High Street
Wealdstone
HARROW HA3 5DL

MICROWAY
Computer Centre

PCW8256 + CPC6128
PROFESSIONAL CP/M + SOFTWARE

DATABASE SYSTEMS
Cardbox £99.99
Delta 1.25 ..... £114.95
Sage £69.99
Cambase £49.95
Flexifile £49.95

SPREADSHEET + MODELLING
Supercalc 2 ..... £49.95
Multiplan £182.85
Scratchpad + ... £69.99
Cracker £49.00

COMMUNICATIONS
Chit-Chat 'E-mail' .. £69.99
Chit-Chat 'Viewdata' . £69.99

ACCOUNTING
Sage Popular Accounts £99.99
Stock + Invoicing ... £69.99
Accounts Plus £149.99
Payroll £69.99
(Sagesoft Hotline support)

UTILITIES/ LANGUAGES
Dr Draw/Graph .... £49/£49
Dr CBasic/Pascal ..£49/£49
Hisoft Pascal 80/"C" ..... £39/£39
Hisoft Devpac 80/Knife ..... £39/£13

WORD PROCESSING
Pocket Wordstar .. £119.00
New Word £69.00

(RS232, MODEM, 2nd DRIVE, DMP2000 – Please call)

FREE – blank data disc or software over £50

EXTRA READING
CP/M Plus Handbook £9.95
CP/M Software Bus .. £8.95
Supercalc Supermodels £15.95
CP/M Bible £15.95
Soul of CP/M £14.95
Delta, Data, & You ... £9.95
8256 dust cover set £14.95

We also stock a large range of CPC464/6128 software, ROMs hardware, books + accessories – including Arnor, Program Power, Beebugsoft and Tasman products – Please call.
UK prices inclusive of VAT + postage.

MICROWAY COMPUTERS
39 High Street, Rainham, Kent.
Tel: 0634 376702

AMSTRAD
IN MANCHESTER

NOW IN STOCK

CPC 6128
CPC 464
THE NEW PCW 8256!!

PLUS..PLUS..PLUS..PLUS..PLUS..PLUS..PLUS..PLUS..

- JOYSTICKS ● SPEECH SYNTHESISERS
- MP2 COLOUR MODULATORS
- "SUPER POWER" EXPANSION KITS
- ARNOR-MAXAM, UTOPIA AND PROTEXT

— AVAILABLE ON DISK AND CASSETTE —

PLUS..PLUS..PLUS..PLUS..PLUS..PLUS..PLUS..PLUS..

A WIDE RANGE OF SOFTWARE FROM WORD PROCESSORS TO GAMES
ALL GAMES AT BUDGET PRICES:
AT LEAST 50% OFF!!

NOW IS THE TIME TO CALL IN AT:



BUDGET SOFTWARE CENTRE
51 FENNEL STREET
MANCHESTER M4 3DY

OR TEL: 061-834 2808


ACU ADVERTISERS' BUSINESS INDEX

Amstrad ..... (VIII/IX)
Box ..... (XXVII)
Camsoft ..... (XXXI)
Caxton ..... (XV) (XXIII)
Celcom ..... (XXXII)
Compact ..... (XXVII)
Connect ..... (XXVIII)
Data Soft ..... (XII)
DK Tronics ..... (XVI/XVII)
Greyfield ..... (XXVII)
Metyclean ..... (XVIII)
Micro-Way ..... (XXXII)
Newstar ..... (IV)
Northern Comp ..... (II)
Pace ..... (VII)
Quest ..... (XXIV/XXV)
Rad Systems ..... (XXXII)
Sage Soft ..... (XI)
Software City ..... (XXX)
Speedysoft ..... (XXI)
Wrexham ..... (XXVIII)

Amsoft's £2000 Software Competition

Competition time again. Lots of entries this month and of the usual high standard. There were some outstanding programs this time and of course they have scooped the prizes.





Galaxians Revenge, by K.N. Khalique of Batley, West Yorkshire, stood out as an excellent game suitable for publishing. It is a Space Invader type shoot-em-up. Nothing special about that you say. Okay, so it's not the most original idea, but an old idea presented well is still a playable and interesting game. All the ingredients were there, good colourful graphics, good sound effects, good response to the player.

The idea of the game, for those who have never seen Galaxians, is that alien invaders from another planet (the same one you've been on if you've ever seen Galaxians) are swooping down, dropping bombs on your laser cannon. You have the ability to move the laser cannon left and right to dodge the bombs and of course, fire back. When you have destroyed all the alien ships you get to meet the second wave, and so on.

Mr Khalique's game uses Basic, to do all the tricky stuff like taking one away from your lives, and then machine code to generate the sprites on the screen. The whole lot goes together in a neat little package that is just right.

Racer, by K. Murfitt, is a formula one motor racing simulator. Written entirely in Basic, it really shows what can be done without resorting to machine code. There are four circuits to choose from, some trickier with more bends, than others. The main part of the game shows you the rear of the car and the track ahead.

As you progress around the course you must overtake the opposition cars and avoid crashing into them. Corners must be taken at a safe speed or you will damage the car. Too much damage has the same effect as an outright crash, losing the game. Mr Murfitt uses ink switching to get the speeding track effect.

The third contender for our prize is Space Mania, written by Neil Kolban of Glasgow. Neil's game is a Jet Set Willy type of game, where the main charcter has to find his way around several screens of obstacles by running and jumping, left and right. We particularly like the catchy tune that continually plays through the game.

The final verdict of the judges is to award Neil Kolban £800, and K.N. Khalique and K. Murfitt £600 each.

Those people that didn't win needn't feel down-hearted. I often feel it's a real achievement to even finish a program. There is always the temptation to add a bit more and gild the lily. This is something that usually leads to poorly written and very long programs.

This can be avoided by doing 90 per cent of the work on paper. Planning your program and deciding exactly how it is going to look when it's finished is a worthwhile thing to do. Writing a program is a bit like making a model from a kit. If you start off by gluing bits together piecemeal you will end with a mess. If you sort out which bits go with which other bits and put them together in small assemblies. Then put all the small assemblies together, you will end with a much tidier result.

So get out those pencils and paper and let's see some really good entries this time.

GRAFIX NEWS

Amstrad musicians take up the baton ...

Having produced the best graphics software with light pen control, which has yet been seen on the Amstrad, the Electric Studio have commissioned the first light pen controlled Music Package, which also looks set to become the market leader.

The MUSIC BOX is available on cassette or disc and boasts an impressive list of features, which include:

464, 664 and 6128 compatible.
3 channel polyphonic sound.
Tone and volume Envelope Designer.*
Internal storage of approximately 8000 notes.
Print out of musical score.
Save score and envelopes to tape or disc.
Use envelopes in own program.
Any key or time signature.
Automatic bar line insertion.
Easy to use Icons with light pen control option.
Cursor music editor.
Share memory of channels in any combination.
Playback: Tempo: Key transposition: Octave.
Demonstration music included.

* The Envelope Designer uses the light pen to draw the graph of the envelopes — no numbers to enter. Sounds can be played while envelopes are edited.

The package can be controlled by either the ESP or DKtronics light pen; by joystick; or by cursor keys which will help all users get the full benefit from the various functions of the program.

THE PROGRAM WILL WORK WITHOUT A LIGHT PEN AND CAN BE PURCHASED SEPARATELY FOR USE WITH JOYSTICK OR KEYBOARD.

The MUSIC BOX is priced at £9.95 for the cassette program or £16.95 for the disc version and for a limited period the MUSIC BOX plus an ESP Light Pen will be available for the price of £19.95 with cassette software or £29.95 with disc based software.

Don't worry Joyce — you're not forgotten!

Final development work which will allow the ESP Light Pen to interface with the Amstrad 8256 "Joyce" machine, is now nearing completion at ESP's research and development facility. If you thought that people just go to sleep in Beds, then you'll be surprised at the activity taking place in Luton!

A simple to use graphics program, based on the successful format of the ESP range for Amstrad home computers, will soon be available which will transform your simple word processor into a graphically illuminating experience.

Many 8256 owners will need a graphics capability and should find the new Light Pen program an extremely useful work tool for their business or leisure use.

World First for British Company!

At a Press Conference held earlier this week, The Electric Studio announced the launch of the first ever, pixel accurate light pen for the Amstrad, for under £20.

This major breakthrough has been achieved through extensive development of their product since its introduction in September 1985, and is the culmination of months of work by the technical department.

The Technical Director of the company was quoted as saying "Up to now pixel accurate pens for freehand drawing were priced around the £40 mark. We can now produce a light pen capable of total accuracy, for a price that no other light pen manufacturer gets near."

The company confirmed that the ESP "PIXEL" Light Pen was available for £19.95 complete with the cassette software package that has proven to be the market leader.

They stressed that the accuracy would be available on both mono and colour monitors and the CPC 6128 machine specific program with freehand draw ability, will now retail at £29.95 with software on disc.

All future products, commencing with the "PIXEL" pen will be released with French, German and Spanish versions of both program and manual, as The Electric Studio recognises the importance of the European involvement with the Amstrad/Schneider range of computers.

Continued support for existing ESP users

Because of the launch of the new freehand drawing "PIXEL" pen, the Electric Studio will offer a special upgrade facility for existing users of the ESP character accurate Light Pen.

The Upgrade will provide modified pen and software which will transform the unit to a freehand drawing instrument, while the full graphics capabilities of the program remain the same.

Any owner of an ESP character accurate pen, whether in the UK or elsewhere can benefit from this offer by observing the following conditions:

All returns to The Electric Studio, PO Box 96, Luton LU3 2JP.

Cassette Software: Return the Light Pen only.

Disc Software: Return the Light Pen plus a disc and state type of computer.

Any user who has upgraded to a CPC 6128 computer since purchasing a Light Pen will be supplied with a 6128 program provided a blank disc accompanies the returned Light Pen.

Terms and Conditions of Upgrade:

a) The pen must be in working order.
b) Returned units should be mailed in protective packaging. i.e. Jiffy Bag or similar.
c) State clearly name, address and model of computer.
d) Enclose a cheque or P.O. for £5.00 for delivery within the U.K. or £7.00 for overseas delivery.

Electric Studio to support US Giant

6128 owners who have purchased or are considering the purchase of the Digital Research program DR Draw will be delighted by the news of the availability of an ESP Enhancement Pack.

This comprises a pixel accurate light pen with GSX driver on disc, which will allow total control of DR Draw using the light pen instead of cursor key controls.

The cursor is controlled by the light pen which gives almost instant access to all parts of the screen, making menu selection a much speedier process and thus giving additional flexibility to the overall package which is an invaluable time saver for the program user.

8256 users can look forward to a similar enhancement kit being available shortly.

Advertisement

Please send the items indicated: ACU 4

"PIXEL" light pen (464 cassette)	£19.95 ☐
"PIXEL" light pen (464/664 disc)	£29.95 ☐
"PIXEL" light pen (CPC 6128 disc)	£29.95 ☐
ESP Enhancement Kit for DR Draw	£29.95 ☐
MUSIC BOX Program on cassette	£9.95 ☐
MUSIC BOX Program on disc	£16.95 ☐
ES Pen + MUSIC BOX (cassette)	£19.95 ☐
ES Pen + MUSIC BOX (disc)	£29.95 ☐

UPGRADE SERVICE for "PIXEL" pen (MUST INCLUDE RETURNED UNIT)
U.K. £5.00 ☐ Overseas £7.00 ☐


Name .....
Address .....
.....
.....
Cheque/P.O. for £ ..... is enclosed
Debit my Access/Visa
Card No .....



24 HOUR CREDIT CARD HOT-LINE

THE ELECTRIC STUDIO
P.O. BOX 96, LUTON LU3 2JP TEL: 0582 595222

Shutting the windows



Richard Sargent concludes his series on pull down windows.

Last month we looked at routines which read a character square (CALL &9000) and saved the information found there in user defined graphic number 255. There was also, on a larger scale, a routine which read a rectangular portion of the screen (CALL &90C0) and saved the information found there in RAM. The screen manipulation techniques in these routines require only a small amount of tweaking to enable them to be used as the basis for some interesting programs. This month we round off the series on windows by looking at a program which brings 'pull down menus' to the Amstrad.

Pull down menus

A pull down menu (PDM) is a panel of text, usually in the form of a list of options which can be called to the screen instantly. When you've finished with the menu the screen reverts to its original state. The pull down menu is generally recognised to be a good thing, and since it's part of the 16 bit micro revolution, no manufacturer of a new computer would want to be without some. However, memory restrictions, and, to a lesser extent, the lower screen resolution of the 8 bit micros has tended to exclude the pull down menu from the home micro scene, and unless you're lucky enough to own a mouse and some icon driven software to go with it, the chances are you won't have seen menus rolling down from the top of the Amstrad screen.

Using the software presented here, you can now incorporate pull down menus into your own program. Two extensions to the screen save routine are needed, but last month's code at &90C0-&9135 is substantially unchanged. Also, the area referred to as general RAM, in which parts of the screen are stored, is retained at &6D00-&8F20.

How then will the pull down menu system work? The menu must not destroy what's on the screen. A routine must therefore save that part of the screen where the menu is going to appear, and restore everything to normal afterwards. A pull down menu on the Amstrad CPC computers won't be as fast as those on the 16 and 32 bit machines, but there's no way around this problem other than to keep the menu reasonably small.

Sometimes it is useful if the pull down menu is available at all times, regardless of what task the computer is currently doing. If you want this feature, (it is optional) then the pull down menu code must be tied into the computer's interrupt system. This is done by a special piece of code called the interrupt service routine. Assuming you go for this fully fledged system of interrupt control, the sequence of events for the whole pull down menu program looks something like this:

1. The interrupt service routine is called every fiftieth of a second. It checks keys f1, f2, f3 and f4 to see if a menu needs to be "pulled down".
2. A screen segment is saved to general RAM at &6D00.
3. The menu is moved to VDU RAM.
4. The foreground program is now effectively frozen, and will do nothing. If the foreground program were allowed to continue (which is technically possible by altering the interrupt service routine program slightly) it might print data over the menu and destroy it!
5. The interrupt service routine now looks for key press f0, which will remove the menu.
6. The original screen segment is restored to VDU RAM.
7. The interrupt service routine is now finished, and the foreground program continues.

Some users might like to dispense with the interrupt arrangements. It is perfectly acceptable to use the same machine code routines to produce a pull down menu in response to a standard INPUT or INKEY$ command and such an application will be explained before the more complicated interrupt version is considered. When this more straightforward module is debugged and working satisfactorily the system can be transferred to interrupt control; but first, let's look at the pull down

```
100 REM M20.BAS PULL-DOWN-MENU DESIGNER
110 REM MEMORY &6CFF:LOAD "M20.BIN"
120 KEY DEF 15,0,32:KEY DEF 13,0,32:KEY
    DEF 14,0,32
130 KEY DEF 5,0,32:KEY DEF 20,0,32
140 WIPE=&91DB:CREATE=&9206:PPBASE=&9137
150 CLS:INPUT "MODE 1 OR 2";M:IF M<1 OR
    M>2 THEN GOTO 150
160 INPUT "DEPTH OF MENU 1 - 7 ";D
170 IF D<1 OR D>7 THEN GOTO 160
180 YB=(398-((D+2)*16))/2:E=D+1
190 MODE M:BORDER 9
200 IF M=2 THEN GOSUB 590
210 IF M=1 THEN GOSUB 630
220 LOCATE 1,D+3
230 PRINT " MENU 1               ";
240 PRINT " MENU 2               ";
250 IF M=1 THEN PRINT:GOTO 290
260 PRINT " MENU 3               ";
270 PRINT " MENU 4"
280 PRINT
290 WINDOW #2,1,80,D+5,24
300 WINDOW 1,80,22,24
310 PRINT #2,"TYPE 1,2,3 OR 4 TO SELECT
    THE MENU-BOX  YOU WISH TO WORK ON."
320 PRINT #2,"YOU MAY TYPE INSIDE THE BO
    X AND USE THE <DEL> KEY,"
330 PRINT #2,"THE <ENTER> KEY TAKES YOU
    OUT OF THE BOX"
340 PRINT #2,"TYPE 10,20,30 OR 40 TO MOV
    E  A  BOX  TO THE MACHINE CODE PROGR
    AM"
350 PRINT #2,"TYPE 99 TO RETURN TO BASIC
    "
360 PRINT #2,"TYPE 88 TO SAVE TO TAPE OR
     DISC";
370 LOCATE 1,2
380 INPUT A
390 IF A=99 THEN MODE M:STOP
400 IF M=1 AND (A=3 OR A=4) THEN GOTO 38
    0
410 IF M=1 AND (A=30 OR A=40) THEN GOTO
    380
420 IF A=1 THEN WINDOW #1,2,19,2,E:GOTO
    580
430 IF A=2 THEN WINDOW #1,22,39,2,E:GOTO
     580
440 IF A=3 THEN WINDOW #1,42,59,2,E:GOTO
    580
450 IF A=4 THEN WINDOW #1,62,79,2,E:GOTO
     580
460 IF A=10 AND M=1 THEN ST=PPBASE+40:N=
    PPBASE+42:GOTO 540
470 IF A=10 AND M=2 THEN ST=PPBASE:N=PPB
    ASE+2:GOTO 540
480 IF A=20 AND M=1 THEN ST=PPBASE+50:N=
    PPBASE+52:GOTO 540
490 IF A=20 AND M=2 THEN ST=PPBASE+10:N=
    PPBASE+12:GOTO 540
500 IF A=30 AND M=2 THEN ST=PPBASE+20:N=
    PPBASE+22:GOTO 540
510 IF A=40 AND M=2 THEN ST=PPBASE+30:N=
    PPBASE+32:GOTO 540
520 REM IF A=88 THEN SAVE "MTEXT.BIN",B,
    &78A0,5760
530 GOTO 380
540 POKE N,YB-(INT(YB/256)*256)
550 POKE N+1,INT(YB/256)
560 CALL CREATE,ST:GOTO 380
570 :
580 CLS #1:LINE INPUT #1,;"",A$:GOTO 380
590 FOR X=3 TO 656 STEP 160
600 PLOT X,392:GOSUB 620:NEXT
610 RETURN
620 DRAWR 152,0:DRAWR 0,-16*e:DRAWR -152
    ,0:DRAWR 0,16*e:RETURN
630 PLOT 3,392:GOSUB 640:PLOT 322,392:GO
    SUB 640:RETURN
640 DRAWR 315,0:DRAWR 0,-16*e:DRAWR -315
    ,0:DRAWR 0,16*e:RETURN
```

Listing 1

menu designer, which is a straightforward Basic program.

Type in Listing 1(M20.BAS), complete with the REM statements. When the Basic has been loaded, type RUN and in answer to the prompt "MODE 1 OR 2?" type 2, and to the prompt "Depth of menu 1-7?" type 7. The menu designer will appear on the screen, and by following the instructions given, one or more menus can be written.

You should experiment with various depths of menu in both modes 1 and 2 to get the feel of the designer. The editing facilities are somewhat limited and you need to remember to avoid the natural reflex of pressing the Enter key to go down a line while in the process of typing the menu contents. Once you have taken the cursor outside the menu box (which is achieved by pressing Enter) you can't get back in. You may use the arrow keys to move the cursor around inside the menu box.

The largest pull down menu which can be designed is 18 characters wide and 7 lines deep. There is always a border around the text, so in fact the total area of the pull down menu is 20 columns by 9 rows. The border is drawn by the subroutine at lines 590-640, using a value of E computed in line 180. E is simply the depth of the menu (D) plus one. Either line 200 or line 210 calls the relevant border drawing routine, depending on which screen mode has been selected. A more important task of line 180 is to inform the machine code routine which pixel line represents the bottom of the menu:

YB=(398–((D+2)*16))/2

Lines 220-370 are general prompt messages, while lines 380-530 deal with the options of design, create, and save menu. Lines 540-560 pass critical information about the size and number of the menu to the pull down menu machine code. CALL CREATE, ST creates a pull down menu. This code should be protected by a REM until the machine code is loaded, otherwise the computer will crash. Line 580 is the entire pull down menu editor and is essentially a LINE INPUT command acting on a specified window.

Pull down menu machine code

The pull down menu system works independently of the Basic designer, and occupies &1F6 bytes of code. Unfortunately, the storage area required for the four menus brings the total number of bytes required up to &25B5, but there's not much you can do about this factor unless you have a 6128 or a memory extension pack and are also happy about paging in the extra banks of RAM at machine code level. The source listing (Listing 2) of the pull down menu code is given in full so that hardy programmers can convert the code to handle menus which are stored in the alternate 64k RAM. At this stage the protective REM at line 560 should be removed from the designer program, and the loader program (listing 3) used to load the machine code bytes. The designer can then be RUN again and an experimental menu 1 and menu 2 created (the screen mode you use doesn't matter). Then the machine code can be put to work.

The first place to start investigating the code is at &9206, the create routine. This routine receives the variable ST from the Basic menu designer and immediately transfers the value into the HL register. HL now points to one of six tables. Let's assume for the sake of argument that the value of ST was such as to point HL at the table M2B1A at &9137. M2B1 simply stands for Mode 2, menu block 1. It's a data table of five numbers and it specifies the size and position of Menu 1 on a Mode 2 screen. M2B1A holds the address where pull down Menu I will be stored when it's created.

The pull down Menu 1 coordinates then follow – M2B1YB holds the bottom pixel coordinate of the Y axis, M2B1YT holds the top of the Y axis, M2B1XL holds X axis left, and M2B1XR holds X axis right.

The create routine moves these 10 bytes of M2B1 information into a special holding area labelled PP.

We are now almost ready to move the newly created menu from the screen into general RAM. A quick call to ROM establishes the screen mode, and this is placed in the B register. The direction of transfer of information is from VDU RAM to general RAM, so register C is set to 0. With PP, reg B and reg C now all valid, the general purpose routine MV_IT can be used to move the necessary bytes and so create the menu.

A quick look at MV_IT at &90D5 now revals what is happening . MV_IT is simply part of last month's code, where it was used in support of the Basic command CALL &90C0,D,XR,XL,YT,YB,ADDR. Now at this point I would normally say that those readers following

```
        LIST
;M2B.ASM PULL DOWN MENUS ON COMMAND
        ORG &90C0
SIZE    EQU 1440
M5      EQU &6000
PDMP    EQU M5+2880
PP      EQU PDMP+84
M1      EQU PP+12
M3      EQU M1+1440
M2      EQU M3+1440
M4      EQU M2+1440
FAREA   EQU M4+1440
;CODE FOR CALL &90C0,D,XR,XL,YT,YB,ADDR
;0=0 screen to RAM
;0=1 RAM to screen
SCRMV   LD C,(IX+10)
XCREAT  LD B,12
        LD HL,PP
XCL     LD A,(IX+0)
        LD (HL),A
        INC IX
        INC HL
        DJNZ XCL
        CALL &BC11;SCR GET MODE
        LD B,A
;and fall thru to MV_IT
;CODE FOR SCREEN/VDU RAM TRANSFER
MV_IT   LD A,(PP)
        LD L,A
        LD A,(PP+1)
        LD H,A
        PUSH HL
        POP IX
        LD A,(PP+8)
        LD E,A
        LD A,(PP+9)
        LD D,A
MV1     LD A,(PP+7)
        SUB D
        RET C
        JR NZ,MV6
        LD A,(PP+6)
        SUB E
        RET C
MV6     LD A,(PP+4)
        LD L,A
        LD A,(PP+5)
        LD H,A
MV2     PUSH HL
        PUSH BC
        PUSH DE
        CALL &BC1D;SCR DOT POS
        POP DE
        POP BC
        BIT 0,C
        JR Z,MV4
        LD A,(IX+0)
        LD (HL),A
        JR MV5
MV4     LD A,(HL)
        LD (IX+0),A
MV5     INC IX
        POP HL
        DEC HL
        LD A,(PP+3)
        CP H
        JR NZ,MV2
        LD A,(PP+2)
        CP L
        JR NZ,MV2
        LD A,0
        INC DE
        CP 0
        JR Z,MV1
        INC DE
        INC DE
        CP 1
        JR Z,MV1
        INC DE
        INC DE
        INC DE
        INC DE
        JR MV1
        NOP
        NOP
;NOW THE CODE TO DEAL WITH HANDLING
;THE SCREEN MATERIAL UNDER THE
;PROPOSED MENU
;DATA AREA
M2B1A   DW M1
M2B1YB  DW 128
M2B1YT  DW 199
M2B1XL  DW 159
M2B1XR  DW 0
M2B2A   DW M2
M2B2YB  DW 128
M2B2YT  DW 199
M2B2XL  DW 319
M2B2XR  DW 160
M2B3A   DW M3
M2B3YB  DW 128
M2B3YT  DW 199
M2B3XL  DW 479
M2B3XR  DW 320
M2B4A   DW M4
M2B4YB  DW 128
M2B4YT  DW 199
M2B4XL  DW 639
M2B4XR  DW 480
M1B1A   DW M1
M1B1YB  DW 128
M1B1YT  DW 199
M1B1XL  DW 159
M1B1XR  DW 0
M1B2A   DW M2
M1B2YB  DW 128
M1B2YT  DW 199
M1B2XL  DW 319
M1B2XR  DW 160
STATUS  DW 0
;ENTRY POINTS ARE B1,B2,B3,B4
B1      CALL &BC11
        DEC A
        JR Z,M1B1
M2B1    LD HL,M2B1A
        JR PDM
M1B1    LD HL,M1B1A
        JR PDM
B2      CALL &BC11
        DEC A
        JR Z,M1B2
M2B2    LD HL,M2B2A
        JR PDM
M1B2    LD HL,M1B2A
        JR PDM
B3      LD HL,M2B3A
        JR PDM
B4      LD HL,M2B4A
;P (parameter storage area) is now
;overwritten using data from table
;pointed to by HL
PDM     LD DE,PP
        LD BC,(STATUS)
        XOR A
        OR B
        OR C
        RET NZ;PDM ALREADY ON SCREEN!
        LD (STATUS),HL
        PUSH DE
        POP IX
        LD BC,10
        LDIR
;PULL DOWN THE MENU
        CALL &BC11
        LD B,A
;SAVE WHICHEVER BLOCK (1-4) NEEDS SAVING
        LD L,(IX+0)
        LD H,(IX+1)
        PUSH HL
;RELOAD P+0,P+1 WITH M5
        LD HL,M5
        LD (IX+0),L
        LD (IX+1),H
;AND SO SAVE TO M5
        LD C,0
        CALL MV_IT
;RECOVER HL RELOAD TO P+0,P+1
        POP HL
        LD A,L
        LD (PP),A
        LD A,H
        LD (PP+1),A
        LD C,1
        CALL MV_IT
        RET
;ERASE A PDM FROM THE SCREEN AND
;RESTORE ORIGINAL SCREEN
WIPE    LD DE,PP
        PUSH DE
        POP IX
        LD HL,(STATUS)
        XOR A
        OR L
        OR H
        RET Z;NO PDM PRESENT!
        LD BC,10
        LDIR
;PULL IT UP
        CALL &BC11
        LD B,A
;LOAD P+0,P+1 WITH M5
        LD HL,M5
        LD (IX+0),L
        LD (IX+1),H
;RECALL SCREEN FROM M5
        LD C,1
        CALL MV_IT
        LD HL,0
        LD (STATUS),HL
        RET
CREATE  EX DE,HL
        LD DE,PP
        LD BC,10
        LDIR
        CALL &BC11
        LD B,A
        LD C,0
        CALL MV_IT
        RET
K1      EQU 13 ;KEYPAD 1
K2      EQU 14 ;       2
K3      EQU 5  ;       3
K4      EQU 20 ;       4
K0      EQU 15 ;       0
KEYS    DI
        PUSH AF
        PUSH HL
        PUSH DE
        PUSH BC
        PUSH IX
        LD HL,KFIN;RET ADDR ONTO STACK
        PUSH HL
        LD A,K1
        CALL &BB1E
        JP NZ,B1
        LD A,K2
        CALL &BB1E
        JP NZ,B2
        LD A,K3
        CALL &BB1E
        JP NZ,B3
        LD A,K4
        CALL &BB1E
        JP NZ,B4
        POP HL
        JR KCONT
KFIN    NOP
        NOP
        NOP
        LD A,K0
        CALL &BB1E
        JR Z,KFIN
        CALL WIPE
KCONT   POP IX
        POP BC
        POP DE
        POP HL
        POP AF
        EI
        RET
ISROFF  LD HL,TICK_BLOCK
        CALL &BCDD ;KL DEL FRAME FLY
        RET
ISRON   LD HL,TICK_BLOCK
        LD B,&81
        LD C,0
        LD DE,KEYS
        CALL &BCD7 ;KL NEW FRAME FLY
        RET
TICK_BLOCK DS 9
;ALTERNATE ISR ROUTINE
NOWAIT  DI
        PUSH AF
        PUSH HL
        PUSH DE
        PUSH BC
        PUSH IX
        LD HL,KEYFIN;RET ADDR ONTO STACK
        PUSH HL
        LD A,K1
        CALL &BB1E
        JP NZ,B1
        LD A,K2
        CALL &BB1E
        JP NZ,B2
        LD A,K3
        CALL &BB1E
        JP NZ,B3
        LD A,K4
        CALL &BB1E
        JP NZ,B4
        LD A,K0
        CALL &BB1E
        JP NZ,WIPE
        POP HL
KEYFIN  POP IX
        POP BC
        POP DE
        POP HL
        POP AF
        EI
        RET
        LIST
TFIN    EQU $
TSIZE   EQU TFIN-SCRMV
        END
```

Listing 2

the series should already have the code from &90C0 to &9135 in their computer, or tucked away on tape or disc. This was the intention, but a slight imperfection in the original code around &90ED has meant that two extra bytes have had to be squeezed into the program at this point, lengthening the routine and upsetting the values of the seven relative jumps which occur later.

In practical terms the original code saved portions of the screen quite happily until it enountered screen locations in a certain range, whereupon it refused to do the save. The routines used to test CALL &90C0 didn't use the critical screen locations and in consequence the bug didn't show up. The missing bytes are 20 05, a Jump Relative If Non-Zero instruction.

This month there are six entry points to the machine code. We have already met the first, CALL &9206,ST, which in conjunction with the menu designer creates the menu. Four separate calls invoke the menu of your choice. CALL &9175 pulls down menu block number 1, CALL &9185 pulls down block 2, CALL &9195 pulls down block 3 and CALL &919A pulls down block 4. Try CALL &9175 – menu 1 should come down. CALL &9185, Menu II, will now not work, since you can only have one menu on screen at any given time. Use CALL &91DB to wipe the menu from the screen. The original screen contents should be restored and if you type CALL &9185, menu II should drop down.

Once you have finished working with the Basic designer, it can be erased by command NEW. Your Basic programs can now use CALL &9185 (or any of menu calls) to pull down a menu and CALL &91BD to push it back up. Listing 4 shows a possible program segment which will handle a tranditional list of options menu. In the example of listing 4, option number one lists the program to the printer, and option seven simply pushes up the menu. Options 2-6 are not implemented.

May I interrupt?

Locomotive Basic runs amidst a constant flow of interruptions, most of which take place privately within the computer and are transparent to the user. If you've used the EVERY or AFTER commands you have already added your own Basic interrupt routines to those implemented by the ROM operating system and it's almost as simple to add machine code interrupt routines to the system. There is one important difference, if the routine fails to work first time and the result of that failure is a program crash, then the debugging procedure is horrendously complicated.

The main task of converting the menus to interrupt control falls to the Keys routine at &921F. It is this routine which scans the keyboard looking for the keypresses which signify "I want a menu now". The routine must deliver the correct menu, and also tidy up the screen afterwards.

The first thing you'll notice in Keys is that all the

registers are saved, an essential operation for an interrupt routine, and failure to do this will certainly lead to frequent and fatal program crashes. Next, four CALLs to &BB1E establish whether the function keys f1, f2, f3 and f4 have been pressed. If they haven't, an immediate exit from the interrupt routine is made via label KCONT, and the foreground program is allowed to continue. If one of the keys is found pressed, the relevant pull down menu routine is called, though you won't see any CALL code in the routine. In case this puzzles you, consider the test for key number 13, the f1 key. The code is:

```
LD HL,KFIN:KFIN is the address where the program flow must go to after
PUSH HL      :(and if) the jump to &9175 is made.
             :The PUSH puts the address on the stack.
LD A,13          :A call to &BB1E with the A register correctly loaded
CALL &BB1E       :tests the f1 key
JP NZ,&9175      :If f1 pressed, jump to the pull down menu1 routine;
                 :at the end of the pull down menu1 routine, the RET
                 ;instruction will cause a return to label KFIN
```

If any pull down menu routine is called, then the program sits in the KFIN loop, waiting for the f0 key to be pressed, whereupon the menu will be removed with a CALL to &91DB.

The next step is to tell the computer that the Keys routine exists, and this is handled by a piece of code which asks the computer to add keys to the list of routines which are called regularly on interrupt. This is accomplished from Basic with a call to &9263 ISROM (Interrupt Service Routine ON). A call to ISROFF at &925C will remove Keys from the list, thus switching the pull down menus off. An alternate interrupt service routine is provided, which doesn't hold up the foreground program to any great extent. It's called NOWAIT and can be patched into the interrupt service routine, thus replacing the Keys routine, by the direct Basic command POKE &926B,&7A. Now if you press function key f1 menu one drops down, but the main program is not halted. f0 pushes up the menu as usual.

Active menus

In normal use the interrupt driven menu is probably best used for prompts, providing, for example, two Help menus if you're in Mode 1. Help menus are passive affairs, you look at them for information and that is all. Seasoned machine coders will have already worked out that it is possible to make the menus active rather than passive. To do this, the Keys routine, rather than the Nowait one is used, and a JUMP instruction is inserted at &9247, the address of label KFIN, replacing the three no-operation instructions which are there.

After a function key press has been detected and a menu displayed, the program flow goes to KFIN and then makes the jump to a new piece of code (which must of course be written). This code should scan the keyboard looking for a user's response to whatever instruction or options were contained in the pull down menu and take appropriate action if certain keys were pressed. This will all happen with the foreground program suspended. All the extra code is technically a gigantic interrupt service routine.

If it becomes too lengthy the computer may begin to wonder if its every going to be allowed to service other interrupts or get on with the main program. However this is something of a diversion. The pull down menu system doesn't have to run under interrupt, and in Listing 4 where the menu is simply called by a line of Basic, the menu is nevertheless fully active. It offers options to which a keypress response is expected. How you use the pull down menus in your programs, is, as ever, entirely up to you.

```
100 MEMORY &6CFF
110 RESTORE 150
120 FOR a=&90C0 TO &92B5
130 READ A$:POKE A,VAL("&"+A$):NEXT
140 SAVE "M20.BIN",B,&90C0,&1F6:STOP
150 DATA DD,4E,0A,06,0C,21,94,78,DD,7E,0
    0,77,DD,23,23,10,F7,CD,11,BC,47,3A,94
160 DATA 78,6F,3A,95,78,67,E5,DD,E1,3A,9C
170 DATA 78,5F,3A,9D,78,57,3A,9B,78,92,D
    8,20,05
180 DATA 3A,9A,78,93,D8,3A,98,78,6F,3A,9
    9,78,67,E5,C5,D5,CD,1D,BC,D1,C1,CB,41
190 DATA 28,06,DD,7E,00,77,18,04,7E,DD,7
    7,00,DD,23,E1,2B,3A,97,78,BC,20,E0,3A
200 DATA 96,78,BD,20,DA,78,13,FE,00,28,C
    0,13,13,13,FE,01,28,B9,13,13,13,13,18
210 DATA B3,00,00,A0,78,80,00,C7,00,9F,0
    0,00,00,E0,83,80,00,C7,00,3F,01,A0,00
220 DATA 40,7E,80,00,C7,00,DF,01,40,01,8
    0,89,80,00,C7,00,7F,02,E0,01,A0,78,80
230 DATA 00,C7,00,9F,00,00,00,E0,83,80,0
    0,C7,00,3F,01,A0,00,00,00,CD,11,BC,3D
240 DATA 28,05,21,37,91,18,1D,21,5F,91,1
    8,18,CD,11,BC,3D,28,05,21,41,91,18,0D
250 DATA 21,69,91,18,08,21,4B,91,18,03,2
    1,55,91,11,94,78,ED,4B,73,91,AF,B0,B1
260 DATA C0,22,73,91,D5,DD,E1,01,0A,00,E
    D,B0,CD,11,BC,47,DD,6E,00,DD,66,01,E5
270 DATA 21,00,6D,DD,75,00,DD,74,01,0E,0
    0,CD,D5,90,E1,7D,32,94,78,7C,32,95,78
280 DATA 0E,01,CD,D5,90,C9,11,94,78,D5,D
    D,E1,2A,73,91,AF,B5,B4,C8,01,0A,00,ED
290 DATA B0,CD,11,BC,47,21,00,6D,DD,75,0
    0,DD,74,01,0E,01,CD,D5,90,21,00,00,22
300 DATA 73,91,C9,EB,11,94,78,01,0A,00,E
    D,B0,CD,11,BC,47,0E,00,CD,D5,90,C9,F3
310 DATA F5,E5,D5,C5,DD,E5,21,47,92,E5,3
    E,0D,CD,1E,BB,C2,75,91,3E,0E,CD,1E,BB
320 DATA C2,85,91,3E,05,CD,1E,BB,C2,95,9
    1,3E,14,CD,1E,BB,C2,9A,91,E1,18,0D,00
330 DATA 00,00,3E,0F,CD,1E,BB,28,F6,CD,D
    B,91,DD,E1,C1,D1,E1,F1,FB,C9,21,71,92
340 DATA CD,DD,BC,C9,21,71,92,06,81,0E,0
    0,11,19,92,CD,D7,BC,C9,00,00,00,00,00
350 DATA 00,00,00,00,F3,F5,E5,D5,C5,DD,E
    5,21,AE,92,E5,3E,0D,CD,1E,BB,C2,75,91
360 DATA 3E,0E,CD,1E,BB,C2,85,91,3E,05,C
    D,1E,BB,C2,95,91,3E,14,CD,1E,BB,C2,9A
370 DATA 91,3E,0F,CD,1E,BB,C2,DB,91,E1,D
    D,E1,C1,D1,E1,F1,FB,C9
```

Listing 3

```
50 REM KEYPRESS "1" PULLS DOWN PDM 1
100 A$=INKEY$:IF A$ <> "1" THEN GOTO 100
110 CALL &9175:REM PULL MENU DOWN
120 A$=INKEY$:IF A$="" THEN GOTO 120
130 A=INSTR("1234567",A$)
135 REM 6 OPTIONS WITHIN THE MENU
140 ON A GOTO 1000,2000,3000,4000,5000,6
    000,7000
1000 CALL &91DB:LIST #8:STOP
6950 REM OPTION 7 CANCELS THE MENU
7000 CALL &91DB:REM PUSH MENU UP
```

Listing 4

ACU

HISOFT

180 High Street North, Dunstable, Beds LU6 1AT. Tel (0582) 696421

NEW Catalog £14.95

The ideal utility for owners of all Amstrad computers with discs. Record directories of all your discs, print them, erase and rename files. Then you can find the file that you know is on one of them somewhere!

Devpac80 £39.95

A Zilog-standard macro assembler, a powerful, screen-based debugger, and an easy-to-use screen editor. We use it to write our products, debug C, patch files, write manuals, fantastic value!

To order: use cheque, PO, Access, or Visa

C £39.95

The fastest C compiler around, with integrated full-screen editor. Gives just about all K&R features (except floats). Comes with library of most Unix functions: i/o redirection, heap, random files. Allows inline Z80 code

Pascal80 £39.95

The fastest Pascal compiler around. It produces pure machine code for fast, small object programs. Now comes with random file access and a disassembler written in Pascal. Includes our full screen editor.

Please ring for any other information

Font64 £12.95

Define your own character sets, for use on-screen and printer, dump screens to Epson or DMP printers. Works on 464 (cassette £7.95), 664, 6128, not 8256.

coming soon on a screen near you:


TurboBASIC £15.95

A fast integer BASIC compiler for 464, 664, and 6128 users.

Art in Pascal £14.95

An art program for the 464, 664, and 6128. Supplied with source code in HiSoft Pascal!

6-8-4-5 Who do we appreciate?



Graphics handling on the CPC machines is impressive as it stands, but with a little inside information you can get the display exactly as you want it. Chris Laing spills the beans

The screen display modes and format are determined by a combination of the firmware, the infamous ULA and the 6845 cathode ray tube controller.

It is possible to generate differing displays by altering the standard configuration using either the 6845 or the ULA. Unfortunately as soon as you start to wander away from the standard formats the firmware becomes practically useless when addressing the screen. In fact it can be positively annoying because there is no way of letting the screen know that you are going to try something slightly different for a change, so it assumes that everything is tickety-boo, just as it was before.

Unsuspecting Arnold

The moral of this is that the techniques discussed here are not for the faint hearted, because once you start playing around with the screen you're on your own, even Soft 158, cannot cope with the things we are about to do to your unsuspecting Arnold.

Having finished the public health warning, it has to be said that there are great rewards in terms of screen access time that can be gained from this approach.

There are 16 registers in the 6845 controller that are used to configure its operation, and they are detailed in Table 1. Although there is provision for a 6845 controlled cursor, this is not implemented in the Amstrad's hardware and so is of little use to the programmer.

To access the internal registers the number of the required register must be output to location &BC00 and the data to be sent to the register is output at location &BD00. As an example, suppose that we wish to set the value of R13 to 5. The following program sequence would then be required.

```
;
LD BC,&BC0D     ; set the register number
                        first
OUT (C),C
LD BC,&BD05     ; followed by the value
OUT (C),C
;
```

Note the technique of setting the value required into the C register. This is possible because only the high byte is significant in the I/O address for this chip.


The first two registers that we shall examine determine the positioning of the display on the screen. The horizontal sync position register (R2) allows the display to be moved left or right. Increasing it moves the screen to the left, and decreasing it moves the screen to the right. Similarly, the vertical sync position register (R7) allows the display to be moved up or down. Increasing it moves the screen up and decreasing it moves the screen down.

Several effects can be created by altering the values of these.

Listing 1 is a program that bounces the display around the screen. This feature is sometimes used while a picture is being drawn on the screen and stopped when the drawing is complete, giving the impression of a lot of activity whilst the picture is being composed. By varying the values in the data table, different effects can be created for example if the horizontal position is maintained constant, the screen can be made to shudder.

This is often used in conjunction with an explosion. It is worth mentioning that altering only these registers does not have an effect on the firmware which can therefore still be used for writing to the screen.

Before we move on to examining how we can really change the screen display format, let's consider how the screen memory addressing works. Each character cell is made up from an eight by eight matrix, and although the width of each character varies according to the mode,




the height is always the same. Each of the rows that make up the character is termed a raster, so there are normally eight rasters for each character, numbered 0-7 (see Figure 1).

```
. . . O O . . .  - Raster 0
. . O O O O . .  - Raster 1
. O O . . O O .  - Raster 2
. O O . . O O .  - Raster 3
. O O O O O O .  - Raster 4
. O O . . O O .  - Raster 5
. O O . . O O .  - Raster 6
. . . . . . . .  - Raster 7
```

Figure 1

16k of RAM is allocated for the screen



memory, which is divided into eight 2k blocks. These each contain the information for one raster for the entire screen, so block zero contains the information for the top pixel row in all characters and block seven contains the information for the bottom pixel row in all characters.

When the information is displayed it is read out of a raster block in consecutive bytes up to the end of one line; the next byte then wraps round to the start of the next line. If the end of a 2k block is reached before the bottom of the screen it wraps round back to the beginning of the block. The important feature is that the memory map is independent of the number of characters displayed on a line.

This is where things can really start to be fun. Having discovered that we are not restricted to the standard number of characters per line, let's see how we set about changing it. The registers concerned with the horizontal parameters are the horizontal total register (R0) and the horizontal displayed register (R1).

R0 is concerned with timing considerations to ensure that the start of one line is displayed correctly in relation to the end of the previous one, and should not normally be altered (although it can produce some interesting effects). R1 is the register that actually determines how many characters are displayed across the screen. The value it contains corresponds to the number of characters in mode one. This is doubled to obtain the number displayed in mode two, and halved for mode zero. Care should be taken to use an even number if working in mode zero, or half characters will appear at the end of lines.

"Why?", you may well ask, "would I want to change the number of characters in a line?" There are several possible answers to this question. If the number of characters per line is reduced, some memory is freed at the end of each 2k block of the screen RAM. Note, however, that this memory is not contiguous. A particular application such as word processing, may require more characters to be displayed on a line than the standard 80 that are available in mode 2. A game that involves a lot of animation is easier to write if the action is contained within a smaller playing area.

The final reason for altering the screen area is perhaps the most important, and again we resort to the screen memory map for its explanation. When directly addressing the screen, the calculation of the memory address is non-trivial, as anyone who's tried it will confirm.

Basically, moving horizontally from one pixel to another is simply a matter of incrementing the address by one, two or four depending on the screen mode, and moving vertically within a character cell requires the addition of 2k to move into the next raster block.

Calculating the changes

The difficulty arises when moving between character blocks vertically. The offset required for this transition is dependent upon the number of characters displayed in a line because of the wrap-round feature described earlier. The default value for this is 80 to move from one raster row to the corresponding raster row in the character cell below it (there are 80 characters by default in mode 2). The hex value for this offset is &50.


To calculate the offset for a line 10 characters below the current one therefore requires multiplying &50 by 10. Although this is not beyond the realms of human comprehension, it would be much nicer to be multiplying by &40 when working in machine code, as all self-respecting games programmers do. This is comparable to multiplying by either 10 or 13 in decimal – even I can manage to stick a zero on the end of a number.

The saving is only a couple of bytes of code for one operation, but when you're constantly accessing the screen the difference really becomes noticeable – ever tried playing Starion?

OK, so we've decided that we'd rather be multiplying by &40, but what does this mean? Well &40 is 64 in the real world and this is the number of characters that we want to display in

```
Listing 1.
;
; This program bounces the display around
; the screen.  A data table contains.
; a series of values for the Horizontal
; and Vertical sync positions with a null
; signifying the end of the table.
;
; The speed of the 'bouncing' is
  determined by the value of the counter
; variable.
;
          ORG     &4000
;
waitfly   EQU     &BD19       ; MC_WAIT_FLYBACK
counter   EQU     &4000       ; delay counter
;
          LD      BC, &BC00
restore   LD      HL, DATA    ; point to the data table
;
readin    LD      D, (HL)     ; read horizontal sync data
          INC     HL
          LD      A, D        ; test for end of data
          OR      A
          JR      Z, restore ; if so go back to start
;
          LD      E, (HL)     ; read the vertical sync
          INC     HL
;
          CALL      waitfly   ; synchronise with
;                               frame flyback
;
          LD      C, 2
          OUT     (C), C ; set horizontal sync
          INC     B      ; go to the data port
          OUT     (C), D
          DEC     B      ; back to address port
;
          LD      C, 7
          OUT     (C), C ; set the vertical sync
          INC     B
          OUT     (C), E
          DEC     B
;
          CALL  delay  ; wait a while
          JR    readin ; and go round again
;
delay     LD      DE, counter
;
dloop     LD      A, D  ; end of delay?
          OR      E
          RET     Z     ; yes, then stop
          PUSH    HL    ; else waste some time
          POP     HL
          DEC     DE
          JR      dloop ; until its done
;
DATA      DEFB  47,31,48,32,47,31,46,
                30,47,29,48,28,47,29,46,30
          DEFB  45,29,44,28,45,29,46,30,45,
                31,44,32,45,31,46,30
          DEFB  0,0
;
```

Listing 1



Register function		Default value
R0	Horizontal Total	63
R1	Horizontal Displayed	40
R2	Horizontal Sync Position	46
R3	Hsync, Vsync Pulse Widths	&8E
R4	Vertical Total	38
R5	Vertical Total Adjust	0
R6	Vertical Displayed	25
R7	Vertical Sync Position	30
R8	Interlace and Skew	0
R9	Maximum Raster Address	7
R10	Cursor Start Raster	—
R11	Cursor End Raster	—
R12	Start Address (High)	—
R13	Start Address (Low)	—
R14	Cursor Address (High)	—
R15	Cursor Address (Low)	—

Table 1: The 6845 integal registers

mode 2, which is twice the value that should be programmed into R1. With a dextrous piece of mental arithmetic we deduce that we need to set R1 to 32. Now having reset the number of characters displayed on the line it has become shorter, and so to restore a sense of symmetry the display can be centred by altering R2 to 42.

A similar piece of jiggery-pokery can be performed on the number of rows displayed, although in this case it is relevant only for reduced playing area and to release some memory. The registers concerned are vertical total (R4), vertical total adjust (R5), and vertical displayed (R6). R4 and R5 are again used for timing and R6 is the one that actually determines how high the screen is. The value it contains corresponds directly to the number of character rows on the screen. Here again the display can be centred by altering the value in R7.

There is a second way that the vertical display can be altered. If you recall each character cell is made up of eight rows with the rows corresponding to rasters and the information for the rasters is stored in a 2k block. The number of rasters displayed on each line is controlled by the maximum raster address register (R9). The default value is seven, hence the eight rows (0-7). This value can be varied; setting it to four will cause only the top half of each line to be displayed, whereas setting it to 16 will cause each line to be displayed twice.

A bonus of using this method to reduce the display is that for each raster removed, 2k of memory is liberated for program use. There is, however, a drawback to this approach in that it affects the overall timing of a frame, and so when R9 is adjusted, R4 and R5 must be reprogrammed accordingly. As ever, there is a magic formula which determines what these should be:

R4 = INT(312/(R9+1))

R5 = 312–(R9+1)*R4

These are simply calculated once the number of rasters required has been decided. Note that if the number of rasters is increased, then multiple images of the same line are created.


The start address registers (R12 and R13) can be used to scroll the screen either vertically or horizontally. Vertical scrolling is achieved by altering the value of the lower 12 bits by the length of a line in bytes. The line length is twice the value stored in R1. Altering the lower 12 bits by anything other than a line length will cause horizontal scrolling.

A combination of horizontal and vertical scrolling can be achieved by changing the offset by a value greater than a line length. Bits four and five of R12 are used to set the screen base to be either &0000, &4000, &8000 or &C000. Register R3 is used to set the pulse widths given out by the 6845 at the end of every line and the end of every frame. These are used by the internal hardware and should not be altered from their default values.

The final register (R8) is used to determine the type of scan that the monitor uses. The Amstrad monitors all use a non-interlace type and so this need not normally be set. As a final effect, however, try setting this register value to 1 – you are advised to hold onto your lunch!

ACU

SUPERPOWER



NEW Bigger, Better ROM-CARD

NEW 'Lightning' Assembler Package

NEW Staggering Price Reductions

NEW Disc-based programs

NEW 6128 and 664 versions

NEW SUPERPOWER ROM-CARD

Eight sockets, addressable 0 to 7, 8 to 15, 16 to 23 etc.; cased unit plugging neatly to expansion port; through connector.

ASSEMBLER, DISASSEMBLER & MACHINE-CODE MONITOR

Over 30 commands in both Assembler and Monitor. Tokenised source code accelerates development time. Assembly at 24000 lines per minute (as many as 8 times faster than competition); large source and object files can be held in memory. Disassembled files can be edited and re-assembled. Comprehensive Monitor with Single-step, conditional breakpoints etc. Rom version held in two 16K chips.

PROGRAMMER'S TOOLBOX & BASIC EXTENSIONS

DIRECT COMMANDS — Character; Compact; Editor; Find; Kill; Medit; Picture; Soundlab; Tidylist; Xref.
PRINTER COMMANDS — Cdump; Dump; Echo.on; Echo.off; Ltron; Ltroff.
GRAPHICS COMMANDS — Circle, Turtle.
(CPC 464 Additional. Fill. Graphics Paper/Graphics Pen. Frame. Mask.)
SCREEN COMMANDS — Double Height; Underline; Normal; Page.on; Page.off; Screen; VDU.
FILE COMMANDS — Baud; Info; Unprotect.
GENERAL COMMANDS — Assemble (simple assembler within Basic); Keyboard; Roms; Tune.

SUPERPOWER DISK USER'S UTILITIES

Program allows detailed inspection and modification of information held on disk and is of particular use for recovering data from corrupted disks. Individual sectors can be read from and written to. All data can be output to the screen and/or printer. Program also contains a number of functions of use to assembly language programmers.

TABULATE DIRECTORY: Displays directory and enters EDIT mode. READ DISK SECTOR: Read sector and enter EDIT mode. LOAD DISK FILE: Load first sector into buffer and remainder to memory for fast access. Enter EDIT mode.

LOAD ROM: Catalogues resident roms, prompts for rom selection and enters EDIT mode. EDIT MEMORY: Displays current buffer. Data displayed is Buffer Address, Hex and ASCII. Comprehensive editing facilities. 'COPY' key gives Intelligent Data Copy. 'TAB' key gives printer output. WRITE: Write sector to disk. DISASSEMBLE: Disassembles code from specified address, giving address, object code, mnemonics and ASCII. Screen and/or Printer output. SEARCH MEMORY: Search sector or a complete file for ASCII string or series of Hex codes. UTILITIES: Includes Format, Hex/Decimal conversions, jump calculations etc. SCREEN UTILITIES. Select from four display modes; choose background and foreground colours.

MAILING LIST AND CLUB MEMBERSHIP PROGRAMME

Program handles thousands of name and address records (label and non-label fields). Twenty classification indicators make possible sophisticated selective examination, counting and printing of records. Alphabetical order is dealt with on data entry, allowing user to select 'key' word. Works with single and double disks as w ll as cassette.

Main Comm ds . . . ENTER: Data entry(*). GET: Load new file. COUNT: Sele ve Count. FIND: Find 'Name' or any String(*). LIST: List current . e on screen(*). PRINT: Print label data or whole records selectively. MERGE: Merge and Sort files. SAVE. Write a file to disk or cassette. RESET: Reset colours, label sizes, class definitions, string constants etc. (*Editing facilities available).

NEW SUPERPOWER ROM-CARD	ONLY **£34.95**
Original Rom-Card (464 only)	**£25.00**

SUPERPOWER SOFTWARE	ROM	DISC
Assembler, Disassembler, Monitor (ADM)	**£29.95**	**£29.95**
Programmer's Toolbox & Basic Extensions	**£19.95**	**£19.95**
Disc Users Utilities	**£19.95**	**£19.95**
Mailing List & Club Membership	**£19.95**	**£19.95**

HOW TO ORDER: Phone or Write to:

Micro Power Ltd.,
Northwood House, North Street,
Leeds LS7 2AA
Tel: (0532) 434006/458800

Also available from Dealers. Ring for latest catalogue and nearest stockist.

WHEN ORDERING PLEASE NOTE: There are different versions of the Roms and Discs for each machine. State, therefore 6128, 664 or 464! Please add 0.75p per order Post & Packing.

SUPER POWER
SERIOUS SOFTWARE FROM THE MICROPOWER ORGANISATION

THIS IS NOT JUST A MODEM, BUT A COMPLETE SYSTEM, NOTHING ELSE TO BUY


'COMMUNICATOR'

£153

PROHIBITED from direct or indirect connection to public telecommunications systems. Action may be taken against anyone so connecting this apparatus.

Why pay extra for the features that the COMMUNICATOR offers as standard?
NOT A BITS and PIECES SYSTEM..... THIS IS A DEDICATED MODEM Compatiable with the 464.664 and 6128
******* NOW WITH THE LATEST SOFTWARE *******

Software contol of all options via the inbuilt SERIAL and PARALLEL interfaces Features include:



AUTO DIAL and AUTO ANSWER.
SOFTWARE included on SIDEWAYS ROM
Through connector for further expansion.
Contact BULLETIN BOARDS, PRESTEL, MICRONET 800 and BT GOLD ETC...
Prestel software includes the FULL 8 COLOUR DISPLAY,
DYNAMIC Frame handling and TELESOFTWARE DOWNLOADING.
Options accessable from BASIC using the Amstrad Bar Commands.
NO LESS than 50 Bar commands are available to the BASIC programmer.
Also selectable from the NUMERIC KEYPAD while ON LINE.
Twin seven segment LED to display digit being dialed and mode selected.
RX and TX indication within the LED display.
SOFTWARE SELECTABLE BAUD RATES.. 300/300 (ans or orig), 1200/75,75/1200 full duplex. 600 and 1200 half duplex. BELL and EUROPEAN rates.
SPOOL ALL incoming data to... Tape, Disc or Printer.
X-ON and X-OFF selectable when SPOOLING to tape or Disc.
DOWNLOAD or UPLOAD files using the XMODEM protocol.
Wordprocessor FILES or PROGRAMMES can be Read from tape or disc and sent directly DOWN LINE.
RECIEVE or SEND complete blocks of code to/from anywhere in the computers memory.
RE-DIRECT ALL print — 8 listings to the modem and reset to CENTRONICS.
Selectable size BUFFER to store data using the TEXT EDIT facility, recieved data or LOADED from tape to disc.
Buffer contents can be SAVED to tape or disc, directed to PRINTER or TRANSFERED down line.
SEND, PRINT or SAVE SCREENS. (ASCII characters).
AUTO CHANGE OVER from TX and RX selectable when in HALF DUPLEX.
Single bytes can be received or sent using the GET and PUT commands.
Selectable LINE FEED code can be sent to.. SCREEN, PRINTER or DOWN LINE.
Local and Recieved data ECHO Facilities.
Unit dimensions (in inches)... 1.5 High - 6.5 Wide - 9.5 Deep A 90 day unconditional warranty is included (subject to misuse).

*** In terms of value for money it's EXCELLENT * Amstrad User Magazine.**
AMSTRAD SET THE STANDARD FOR ALL IN ONE SYSTEMS
K.D.S. CONTINUE THAT WITH THE COMMUNICATOR
DON'T DELAY ... ORDER TODAY.
FREE Subscription to Microlink with every modem.

KDS ELECTRONICS

PARALLEL PORT £22
Twin 8 bit input/output ports, operates from Basic or M/C, TTL outputs, (uses Z80APIO).

RS232 SERIAL PORT £34
For connection to modems, printers, and other computers. Split baud rates, standard 25 way "D".

SIDEWAYS ROM BOARD £26
Holds 4 ROMs. Each 2, 4, 8 or 16k in size. Free utility ROM with each unit.

8 BIT PRINTER PORT £17
Send all character codes (i.e. 0 to 255) to your printer, uses standard print £8 etc. Unique design, no power input needed.

PRINTER "T" SWITCH £22 ** NEW **
Connect 2 printers to your Amstrad, software controllable changeover between printers i.e. invoices on one labels on the other with manual over-ride.

POWER CONTROLLER £40 ** NEW **
Featuring 8 switching relays handling a massive 5 amps AC or DC upto 240 volts AC. Control lights, fans, robots, etc etc. Plugs into the centronics port, uses BASIC OUT command.

******* NEW FOR THE PCW8256 *******
A version of our DEDICATED modem 104 now available for the PCW8256, see opposite.

RS232 AND CENTRONICS INTERFACE £53
SERIAL and CENTRONICS ports for the PCW8256. Connect to other printers, modems, computers.

15 HILL STREET, HUNSTANTON, NORFOLK PE36 5BS. TEL:(04853)2076 Please add VAT to all prices.

WIN THE POOLS?

NEW! AMSTRA-DRAW 2 – THE LATEST DISC BASED VERSION OF THE ORIGINAL AND BEST POOLS PREDICTION PROGRAM FOR THE AMSTRAD CPC464 (WITH DISC DRIVE) AND CPC664 COMPUTERS!!

'THE COMPUTER CAME UP WITH ONE FIRST DIVIDEND PLUS MINOR DIVIDENDS MAKING A TOTAL OF £6000!'
– J. R. Beckett, Sheffield.



- Supplied with Database containing data on over 12,000 matches since 1980!
- You update the Database each week – but no tedious typing, as team and division names already in program!
- Errors easily corrected – the program even checks your entries!
- Comprehensive instruction manual and menu driven program easy to use, even for a newcomer to computing!
- Will forecast the least likely draws for those who prefer to bet on fixed odds!
- Built in perm generator – complete your coupon direct from the screen!
- Compatible with the DK'tronics speech synthesiser – the only pools prediction program to read you its predictions!
- Each copy is individually updated with all results up to the date of dispatch – no typing in enormous lists of previous matches before using the program!
- Full after sales service, including Database updates and end of season upgrades!

AMSTRA-DRAW 2 (ON DISK ONLY) £12·95
ORIGINAL AMSTRA-DRAW ON TAPE (NO SPEECH) £9·95
(Cheques/P.O.s payable to B. S. McALLEY)
AMSTRA-DRAW (Dept CA), 1 Cowleaze, Chinnor, Oxford OX9 4TD
(Tel: 0844-52426)

Tel: (0664) 63617

Squirrel's Byte

7 Coniston Road, Melton Mowbray, Leicestershire LE13 0NE

COMPUTERS (a)

CPC 6128 (with colour monitor) + FREE joystick	399.95
PCW 8256 + FREE paper and disks	458.85

PRINTERS (b)

Shinwa CPA80+ (NLQ)	199.50	Daisy Junior	211.50
Kaga KP810	248.95	Juki 6100	345.00
Epson LX80	240.00	Brother HR15	382.95
Seikosha SP1000	229.00	Amstrad DMP2000	152.00

RIBBONS – others available, please ring.

Shinwa	3.95	Epson 80 series	3.45
Kaga KP810	4.99	Epson 100 series	5.85
Juki 6100 s/s	1.65	Amstrad 8256	6.50
Seikosha	3.68	Amstrad DMP2000	5.98
CABLES 1 metre	9.95	1.5 metre	10.95

MODEMS (c)

Pace Nightingale package for Amstrad (inc. Interface, lead & software) 161.00 (state machine type)

DISK DRIVES (c)

Amstrad	DD1	(inc. interface)	159.00	
Amstrad	FD1	(ex. interface)	99.00	
Amstrad	FD2	(for PCW8256)	159.00	– includes fitting
Cumana	CS001	3" drive	95.00	
Cumana	CS002	5.25" second drive	126.00	

Please state machine type when ordering.

3" DISKETTES FOR AMSTRAD – POST FREE!

Price per box of 10 CF2 disks	38.75
5 CF2 disks	20.95

5.25" disks also available – ring for latest discount prices

MISC. PERIPHERALS – POST FREE!

AMX Mouse	68.50	Serial Interface	49.95
Joystick	14.95	Speech Synth	29.95
Light Pen	19.95		

Carriage rates: (a) £10.00, (b) £7.00, (c) £6.00; ribbons etc. £1.15 (any quantity)
Please telephone if you do not see the item you require.

SIREN SOFTWARE

SIREN SOFTWARE

DISCOVERY

TRANSFER YOUR TAPE BASED SOFTWARE TO DISC NOW
HANDLES SOME TURBOLOADERS ALTERS BASIC LOADERS to get programs running without alteration,. Relocates programs plus all the normal features.
When comparing DISCOVERY WITH A Similair Program AMTIX said 'I found DISCOVERY just a bit easy to use'.

464/664 and 6128
TAPE £7.99 DISC £11.99
ROM £19.99

SIREN SOFTWARE
FOR SPEEDY DELIVERY SEND CHEQUES/P.O.S. TO:
SIREN SOFTWARE, 76 BRIDGE ST, MANCHESTER M3 2RJ
Tel: 061-796 6874
PLEASE ADD £1.50 FOR OVERSEAS ORDERS
ALSO AVAILABLE FROM
SHEKHANA COMPUTER SERVICES

NEW! Masterdisc –
The complete suite of disc utilities on one disc.

Disc Duplicator, Double speed formattor.

Sector/Directory/Memory Editor, Basic protection remover + many, many more.

£12.99 on disc, 464, 664 and 6128 compatible.

TAPE UTILITY

Back your software with ease. Now handles some Turboloaders. Manages Headerless and Normal Programs. Choice of 10 Save Speeds
'Simply the BEST'.
'The tape to tape Back-up copier to beat all tape to tape back up copies' Amsclub XTRA2

464 ONLY TAPE £6.99

SIREN SOFTWARE

DISC DRIVE OWNERS.... **DISKON**


464, 664 and 6128 Disc £13.99


Put those 'Impossible' headerless programs onto disc.


Diskon give you the power to put headerless programs on disk and get them running.
Part 1 Enables you to transfer them to disc Part 2 Retrieves and runs them
This program is not an automatic program like Discovery and is not recommended for the novice user.

SIREN SOFTWARE

DRAUGHTSMAN & GRAFMAN







Explore the true graphic potential of your AMSTRAD CPC 464/664/6128.
Using cursor control keys, joystick, lightpen or graphics tablet you can work in all 3 modes using selected colours. Draw in solid, dash or dot/dash lines, circles, arcs, ellipses, polygons, etc. Recall regular shapes from memory. Draw in one or two point perspective. 3 cursor speeds. 3 types of erasers. Constant readout of X,Y coordinates, drawing and cursor status, distance measure, fix position, on-screen prompts. Hatching and fill facilities. Design sets of symbols (sprites) for use in your drawings/diagrams eg. electronic circuits. Print characters at any pixel position. Save/load symbols. Save/load screens. User screen dump option.

Written by a qualified designer this program is very versatile and user friendly. Your AMSTRAD has excellent graphic facilities. Why not put them to work?
"... an extremely good graphics aid".
"... the program is easy to use, the manual is easy to follow, and the presentation is professional". – Computing with the Amstrad. Nov. '85.
"... it is nice to see E.G. Computer Graphics adopt a different approach to the problem of creating a user friendly graphics package".
"... a strong favourite when compared to the fashionable icon system".
"... provides a very fast and efficient way of accessing a multitude of functions and drawing routines ..." – Amtix! Jan. '86.

GRAFMAN is a powerful and versatile function plotter. Developed by a qualified physicist this program is capable of drawing any DEFinable function. User access to an extensive range of 'built-in' functions: generalized polynomials, trigonometric, exponential/logarithmic, irrational and inverse. Choice of X-Y scale is wide ranging and specific ranges can be defined to display any portion of a curve. Areas of high curvature can be 'magnified' allowing the user to 'home-in' on real roots to a high degree of accuracy. Save/load screen. User screen dump option. Despite the complexity of the program it is very user friendly. On-screen instructions carefully explain each step making this a truly valuable and educational utility.

For further information send S.A.E. To order fill in the coupon.

COMPUTER GRAPHICS

Name .....
Address .....
.....
.....
.....

Please send me ..... copy(s) of:
☐ Draughtsman (disc) £24.95
☐ Draughtsman (tape) £19.95
☐ Grafman (disc) £13.95
☐ Grafman (tape) £9.95

Send P.O./Cheque to: **EG COMPUTER GRAPHICS, Orange House, Orange Street, Uppingham, Leics. LE15 9SQ.**

PCW8256 & CPC6128 SOFTWARE

FLEXIFILE — £39.95

Files of up to 65,000 records or all of one disk, uses B-tree fast file access, user defined screens, reports & selections. Redefine without losing data, IMPORT/EXPORT information. Records up to 1600 bytes long.

FLEXIWRITE — £29.95

Wordstar compatible with an easy to use MENU structure. Online HELP screens, will do MAILMERGE and produce ASCII files. Support for all popular printers. Can use FLEXIFILE data for mailmerge. Extra features include SORTING of lists, print to disk etc.

SPECIAL — £49.95

FLEXIFILE and FLEXIWRITE purchased together at a special price.

CASH BOOK ACCOUNTS — £29.95

Accounting for cash retail businesses to VAT Scheme D. Includes regular management reports. (PCW 8256 only).

DATABASES — £29.95

Ready built database templates for use with FlexiFile or AMSOFT's MicroFile. Applications for ESTATE AGENTS, DRIVING INSTRUCTORS, FARMERS, COLLECTORS, GARDENERS*, COMPANY DETAILS*, SALES PROSPECTING & more. (* includes data).

FLEXILABEL — £29.95

Flexible label handler producing multiple copies of mail list labels. Can read FlexiFile and Flexiwrite files or use direct input. Has both preset and user definable label sizes & formats.

PC-DOS MS-DOS versions also available

All prices include VAT and postage – NO EXTRAS
Send for our brochure for full program details

Access

VISA

Saxon Computing

3 St. Catherines Drive, Leconfield, BEVERLEY, Humberside HU17 7NT
Telephone for BROCHURE or ORDERS 0401-50697

pride utilities

Some programs are sold on the understanding that they must not be used to infringe copyright.

TRANSMAT

EASY TAPE TO DISC TRANSFER

This professionally used and respected utility has set the standard in tape to disc transfer that others attempt to mimmick. What the press think of Transmat:

* Voted No. 2 in the Serious Programs Top Ten Chart by Amstrad Action Readers. Jan 86
* Maximum review ratings in PCW Aug 85
* Highly recommended by AMSCLUB
* "Very easy to use utility" *PCT July 85*. Also selected for Best of the Bunch

Transmats many features include:

* Easy operation * Auto or non auto modes
* Relocator for programs which overwrite the disc area
* Erase * Catalog files * Rename
* Disc header reader * Select user area
* A or B drive working * Transmats itself

Cassette £7.95 inc. Disc £11.45 inc.
Now available on ROM, only £19.95 inc.

SPIRIT

The perfect advanced software complement to Transmat for those knowledgable in computing — Spirit offers all the tools you need in one economic package to transfer those genuine headerless programs onto disc.
This sophisticated package on a transmatable cassette for only £5.95 inc.

TAPE TO DISC TRANSFER SERVICE

We will put your ORIGINAL cassette software (even headerless and speedlock titles) on a quality 3" disc for just **£6.00** including the price of the disc. Just send your cassette, less any bulky packaging, with payment — we will send you the disc and keep the cassette, for legal reasons.

ODDJOB

THE DISC UTILITY PACKAGE YOU HAVE BEEN WAITING FOR

A complete disc utility with all the programs YOU have told us you wanted all together in one amazing package. A total of 39k of disc space used.

Just look at some of the features:

* A complete directory editor with which you can examine the disc directory and easily alter the contents
* Recover erased programs
* Hide programs from the directory
* A complete sector editor to examine and/or alter the contents of files in HEX or ASCII
* Map out your disc and locate where files are on the disc
* Prevent programs from accidentally being erased
* An intelligent disc copier that can copy those damaged/non-standard sectors on a single or twin drive system
* Format in half the time on either drive. Ideal for 5.25 inch second drives
* Transfer your little used programs/files from disc onto tape to reclaim expensive disc space
* Increase the speed of your disc drive by up to 20%
* Load and list protected BASIC programs
* All instructions are supplied on disc on a separate help menu
* Simple to use with single key selection
* Makes full use of the disc drive
* Compatible with all AMSTRAD CPC computers

All this for the incredible price of £12.95 on disc only

NEW SPECIAL OFFER
Buy two or more titles and receive completely free: a real time Digital Alarm Clock program or ZEDIS, our excellent Editor Disassembler on cassette — state choice please.

TAPE TO DISC TRANSFER SOLUTIONS
"The T.I.E. Book"
TRANSMAT OWNERS ONLY —
A bumper booklet is now available containing approx. 90 transfer solutions for those problem programs.
ONLY £3.95 inc. (TIE 1-5)
T.I.E. 5 sheets available on their own for £1.95 inc.

PRIDE UTILITIES LTD.
(Dept. CP4)
7 Chalton Heights
Chalton, Luton
Beds. LU4 9UF
England
Tel: 0582 411686

ALSO AVAILABLE FROM OUR EUROPEAN AGENTS
ZS-Soft Microtrading,
Postfach 2361-Buro:, Doktorberg 20,
8240 Berchtesgaden,
West Germany
ESAT SOFTWARE,
55 Rue Du Tondu, 3300 Bordeaux,
France
Contact above for details

ALL PRICES INCLUDE VAT AND P & P
For Europe add £1.00 per title
For Australasia add £1.75 per title
For Rest of World add £1.50 per title
INC. AIR MAIL

FOR ALL AMSTRAD CPC MODELS


(NOW DISC PRICES ARE EVEN LOWER)

Quality utilities from our fast, reliable and friendly mail order service. All enquiries with s.a.e. answered. Excellent discounts to the trade, fast export service, 48 hour UK turnaround all orders. In fact a complete professional guaranteed service.

SOFTWARE REVIEWS

GAME OF THE MONTH

TAU CETI



A program from CRL, that is best classed as "only pick me up if you have a whole weekend spare". As Elite, it is a genuine epic, no way are you going to blast your way through this in an evening.

It looks fairly innocuous in its little black box, all snuggled up with its instruction leaflet. But what a surprise you get when you load it (and it will load, no fancy funny loaders, and fully 664/6128 compatible). You have a bit of a graphic adventure, screens of the interior of your hangars, a bit of a text down the bottom, re-definable keys, a veritable arsenal that makes a Tornado jet look tame and a little story to set the scene.

As someone once said, "I'm gonna tell you a story". In 2050, it says here, four close stars were colonised, including (where have you seen this name before) Tau Ceti. Fifty cities were started up on the third planet and then a plague hit, followed by a meteor, followed by a robot take-over bid. Everybody got the message and legged it at warp factor 9 to laze in the sun on the beaches of Santraginus V, and get over it all with the aid of a few Pan-galactic Gargle Blasters.

One hundred years later . . . Some mug (you) decides to have a crack at re-colonising the planet, despite it having been taken over by robots who think they can do better without humans.

Gal-Corp. central (the same people who have written "No user serviceable parts – refer to qualified personel" on your airlock) have issued a few guidelines to you on how to use the jump pads, how to use an airlock, to look out for killer fleas and a stern warning not to blast up too many non-offensive buildings as they do really want to colonise the place when you've finished with it.

The rest of the leaflet has some piccys of what the graphics are supposed to look like for the buildings. Places that can restore and repair are shown but not all the buildings are listed, neither are the fleas (sand hoppers, they call them), mines or robot crawlers. You just have to find out from experience. Good job you can save the game isn't it?

Once you have rejigged the controls to work with a joystick you tell it to launch, and have a nose around at the outside world. Mostly tall buildings, with the odd dome and an occasional thingy shooting at you, a bit like London really.

The outside world is displayed in an area about one quarter the size of the screen in the top left corner. The way that the airlock door smoothly slides up and down in this area is beautiful to watch. There is a real-time clock in the top right corner, and outside a sun is shining. It don't shine for long though, the day is only one hour long and you'll soon use that up in this game. As you get closer to sunset, the surroundings become more and more heavily shadowed, until they are only visible because of the chunks they take out of the horizon. This change is really gradual, not something that happens in a flash.

The whole 3Dness of the view is very well done. Shadows form on the right sides of the buildings, and as you fly round them while looking out of the side viewport the shadow shrinks and grows. Things get bigger and smaller as dictated by perspective and explosions seem less severe when you are a long way off.

To brighten the night up a little – so you can see who's shooting at you clearly – you can drop a flare. You only get eight of these and they don't last long, so you can use an infra-red night sight. This has a very persistent and blurred image as per your real night sight, everything leaves a bit of a trail.


Your lasers leap about a bit but the missiles (all eight of them) are great, they lock on to the target with no messing about and multiple launches are allowed. It gets fairly sneaky as both you and the enemy have missiles and anti-missile missiles. A double shot nearly always gets 'em though.

There is a comprehensive map of the jump pad network, allowing you to zoom in or out, scroll sideways, and to ask for information on any city on it. The info tells you how big the city is, what its defences are, and what jump pad links it has.


By now you will have cottoned on that this is a complex game. To help out with the complexities, there is a save game feature (tape or disc) and a notepad built in to the game for your notes. Very thoughtful of them is that.


The eventual aim of the game is to mix 'n' match the pieces of reactor cooling rods that you find in sub-stations (a puzzle in itself) so that you can do for the main reactor and shut down all the robots without Gal-Corp. having to wipe everything off the planet. Mind you, after I've finished blasting around out there it might have been a little tidier.

This game beats ordinary shoot-em-ups into a cocked hat. I can thoroughly recommend it to anyone fancying a bit of a challenge without having to learn about the life and times of J.R.R. Tolkein (which, as we all know, is hobbit forming). When you're finished with the tape Ed . . .



SKYFOX





This is a cockpit view shoot-em-up, featuring ground and air attacks which have very little to do with a flight simulator. The attacks are mostly directed at you and your base, and are spread over a huge map which has no rivers and some magical mountains that are always just on the horizon.

The first thing that struck me about the game was the time it took to load up, absolutely ages. Make cup of tea, read "The Hobbit", eat a four course meal and have your appendix out and it might just have finished loading.

At first I thought that this time dilation factor might just be my familiarity with disc drives, but a skim through the instructions (spoken in both Amstrad and Spectrum) revealed that you might have to flip the tape over during the game. It's a biggie!

While the loading was getting on with it, I tried to skim through the instructions for playing the thing. Although they are not that long, skimming through them is not easy. unless that is, you are one of those people who has the ability to read and digest Amstrad firmware manuals overnight. Putting it bluntly, this is one complicated game.

To illustrate how complicated it is, there are no less than 10 training levels – blasting tanks only, planes only, alternate waves, both together, mini-invasion, full-blooded invasion and then the heavy stuff with different opening moves; like in the better games of chess which I can't play very well either.

Right, helmet on, joystick ready, clear away remnants of four course meal and put jar containing appendix on top of the computer for a mascot. First select the easy level, pinpoint a hot-spot on the map, and launch at it. The auto pilot in this game can do quite a bit you know, and you can guide it by pointing at the map while in flight.

Now the tragic bit, the view out of your cockpit moves a chunk at a time. No flicker, but the view changes as infrequently and drastically as my tax code. I think this is because they are switching between two screens and altering the one you are not looking at.

The cockpit contains all the sort of information you would expect to find in an inter-galactic anti-tank/plane colony protection vessel. The number of missiles left, your current position and where the enemy are are all on display somewhere. A crib sheet supplied with the game helps you find the right dial if you get lost.

The tanks and planes look pretty much like moderately chunky tanks and planes, all done in what looks like mode 1, or at least with only three colours in it. Small mistook here, the distructions say that the shield power remaining is in red. Either I am red/blue colourblind or it's in blue. The sound effects are pretty much what you have come to expect by now, and you only notice them when some anti-noise pollution lobbyist in the family comes along and turns them off.

The gunsights are non-existent, and you just have to follow the shots to their vanishing point and put your target somewhere on that line. The radar scope does give a choice of top and side views with a range readout though, which almost makes up for the lack of decent sights.


The controls seem to be a bit sluggish and not very well de-bounced. This may just be an illusion caused by the slow screen update, but you frequently end up turning a missile off again just after arming it.

Only the one bug in the game spotted so far; you can blast down all the planes in a training level and sometimes the game won't end or give you any more planes to shoot at. No other bugs yet, but that might have something with me not lasting very well on the higher levels.

The best way of dealing with the tanks was to fly at them at high speed with the aid of the afterburners. ("Look at that go, Mummy Bird". "You'd shift that fast if your tail was on fire son".) When they start to look like tanks, you cut the engines completely and hover. The tanks are then at just the right distance for you to blow them to the scrapyard but for you to still be safely out of range. Buzzing them just wastes your ammo.

Planes are much harder and need much chasing about before you can blow them out of the sky. People shouting at you: "It won't go any faster if you bend the joystick", don't help much either.

The higher levels of play definitely require a bit of strategy to complement the joystick wiggling. If only the screen update had been smoother and you could really control the guided missiles, this would have been a super game.



THREE WEEKS IN PARADISE

This is the latest in the long and successful Wally series of games from Mikro-Gen. Three Weeks in Paradise continues where Everyones a Wally left off. Wally and the gang had to complete several tasks around town before going on a well earned holiday. However Wally's idea of a holiday is to get lost on the high seas in a pedal boat with Wilma, his wife and Herbert, his son. They end up marooned on a desert island. Wilma and Herbert wander off, only to be captured by the local natives, the Can Nibbles. Wally has to rescue them.

You take the part of Wally, resplendent in yellow loincloth and complete with knotted hanky on head. In the jungle around you there are bats flying about. Like most other moving obstacles they are easy to avoid but drain your energy on contact.

The screen is divided into two parts, the play taking place in the top of the screen, with the bottom quarter telling you how many lives you have left, and showing you which objects you are carrying. As you haven't any pockets in your loincloth you can only carry two objects. In the bottom right of the screen are two skeletons, one for Herbert and one for Wilma, they show what your family will look like if you don't look sharp.

At the bottom of the screen is an outline of an object that will become more clear as you complete the adventure. There is no energy meter but you have a limited amount of resistance to creatures such as the bats, wandering natives, fish, and sea-horses before you lose a life.

The Mikro-Gen graphics are as cartoon-like as ever with a black outline around them so they stand out from the background. What is new is that Wally walks behind some things, grass, signposts, chests, pillars and in front of others. Another difference is that you can pick up objects and put them down anywhere you like. You can Use objects, rubbing two sticks together to make a fire.

Wandering around the jungle you encounter Herbert in a huge cooking pot, guarded by two lions. A plaintive "DAD!" scrolls across the bottom of the screen. Clues and comments often scroll across the bottom two lines, depending on which location you are in, Such as "Finders Keepers", "Help! its me, Wilma!!" from Wally's wife who is being hung from a tree by her heels and guarded by a native, or just "Ribbit!!" from the giant frog sitting outside a hut.

It's not all jungle screens, there is an underwater scene where Wally does the doggy paddle down to Davy Jones' locker, a temple, an abandoned trading post which is now the home of a lion and other signs of the previous inhabitants that have been eaten by the Can Nibbles.

The objects and their uses are usually straightforward; needing flip-flops before you can walk across the sand, but what to do with the bowl of stuffing or the goldfish? And what use is a blunt axe? The scrolling messages will provide slight clues, but a warped sense of humour is a greater help.

In the jungle paths are conveniently signposted and you can go through the screen to a parallel pathway. Some locations are reached by odder means; try jumping into the seaside painting to get to the beach.

Mikro-Gen claims that the puzzles are a little easier than Everyones a Wally, but much harder than Dummy Run. Don't feel that you need to have played the other Wally games to enjoy Three Weeks. The variety of the locations and puzzles and the quality of the graphics make this a worthy buy. I particularly liked the way the giant frog's chest expanded when he croaked. Those of you who map games will be glad to know that it even connects up sensibly.






AUTHOR MIKRO-GEN
PRICE £9.95

GRAPHICS	18	FIRST IMPRESSION	16
SOUND	17	LASTING IMPRESSION	18
POLISH	18	VALUE	17

COMMENT Wally at his best

SWEEVOS WORLD



AUTHOR GARGOYLE GAMES
PRICE £7.95

GRAPHICS	18	FIRST IMPRESSION	14
SOUND	1	LASTING IMPRESSION	18
POLISH	17	VALUE	18

COMMENT An improvement on the 'Ultimate' style

It must be pretty fair to say that the two games that have made best use of the Amstrad machines up to now have been Knightlore and Alien 8 from Ultimate (and perhaps even Nightshade, their most recent release).

However, when they brought out the second of these two a lot of people moaned that the game format was too similar to the first. This is of course absolute rubbish. Once you're on to a winning idea why not make the most of it?

It was inevitable therefore that in the fullness of time the same type of game would appear from other software houses (in the same way that Manic Miner and Jet Set Willy spawned a whole new game type in days gone by). Unfortunately, successors to an original theme seem almost invariably to be quite inferior to the original but this definitely is not the case with Sweevos World from Gargoyle (the people who already have their own original game format used in Dun Darach and Marsport).

Once again, the basis of the game is a large map of rooms each one being depicted in reasonably convincing 3D view. Sweevos World has taken the idea a little further by spicing up the original monochrome idea so that each room is shown in four colours (three really because black is always used for the background). The speed of operation has also been noticeably improved upon. There is no longer a feeling that you're walking through a time warped world of limbo when you enter a room in which there happens to be a lot going on.

Things missing from this one that the Ultimate games did have are the ability to shuffle the scenery about and the ability to jump. This is never actually needed in the game but there are some puzzles that initially look impossible without the possibility of jumping.

The most important thing that seems to be missing however is any form of sound. The loader plays a very catchy little ditty but as soon as the game is entered a wall of silence falls. Not even so much as the pitter patter of footsteps is to be heard – a bit of a pity but it's probably better to have the prettier graphics and enhanced speed.

The actual aim in the game is to clear the map of various mutant creatures by dropping objects on them. There are tins to be picked up which can usually be used to aid in reaching a level that might otherwise be too high. These are used in conjunction with the lifts that are dotted about all over the place. Quite often two adjacent lifts will be found so that by switching from one to the other and dropping tins on the alternative lift it is then possible to rise to an otherwise unobtainable level.

It isn't easy to generalise about the nature of the problems that you are faced with though. Each object to be picked up or nasty to be avoided has its own foibles and pitfalls. This is where the game really scores against the opposition. In other games there was a standard technique for getting over walls (drop an object, jump on to it then pick it up again as you jump off it over the wall). The same just isn't true in Sweevos World. Each time you find something to pick up you'll have to put on your thinking cap to work out how it's to be done.

The world is on a number of levels and at various points there are "launching pads" that will bounce you up to the next level. There are also holes dotted about that can be dropped through to go down a level. (Be careful, there is one hole that allows you to drop out of the game.) Some of the objects to be picked up can only be got by dropping down to them from a room above so it's an absolute necessity that you should make a map unless you happen to be particularly good at memorising geography.

There is a pleasant level of humour in the game as well. For instance, you have to pick up BOOs and then go up behind a duck-like creature and make use of it, in other words you have to say BOO to a goose!. Another nice feature of the game is that an object dropped through a hole will still be there when you drop after it so that an otherwise deadly obstacle below a hole can be covered. There are various types of scenery to be found in the rooms – the best are the 1 TON weights that are held up by a semi-transparent beam.

Once the beam is touched the weight comes crashing down barring your pathway or worse still, flattening you. Re-entering a room will put them all back up a height though. There are also fingers which rise up out of the floor. It's usually just a matter of waiting for them to go down and learning how long any particular one takes before it re-appears again. There is also a body of gnome-like men that come up through the floor, but they never go back down again so you have to make a mad dash across them before they rise.

Various types of static object are also to be found. Bumping into them produces the message "Ouch!" and the smiling face that shows your status stops smiling. A few more touches and you can say your prayers. The more mobile types (the fingers and gnomes) are deadly at the first touch. Around the game area you may also find characters sitting looking like Cornish Pixies. These are Brownies and "Brownie Points" are to be gained by picking them up. Like so many of this type of game it is only possible to carry three objects at once. The system most games use for allowing you to pick them up and drop them is on a first in first out basis – not in Sweevos World though.

A highlighted block circulates around the three positions and the next time the fire button is pressed to pick up an object it is put into the current position or is dropped if an object already occupies the space. This is really annoying when you only have a split second to pick up an object and end up dropping something else instead, but I suppose it all helps to add to the difficulty of the game which for my money is one of the most entertaining that has appeared for the machine. It can be played with either keyboard or joystick and will work on all models of machine.

AMSTRAD IN EDUCATION - AMSTRAD NETWORK SYSTEM

* Latest Amstrad computer models.
* Substantial discount and education software.
* 1 year free education service contract.
* £200 education software primer pack supplied free with each disc system.
* Amstrad education software consortium details.
* Amstrad hard disc system.
* Amstrad local area network system (for Amstrad, BBC, Apricot, IBM micro computer systems).

Contact

THE U.K. AMSTRAD EDUCATION DISTRIBUTERS:

NORTHERN COMPUTERS LTD.
Churchfield Road, Frodsham, Cheshire WA6 6RD
Tel:(0928) 35700(10 lines).
Telel:265871(MONREF G) Quote:(UK)84:CXX123

UNLOCK YOUR
AMSTRAD 464/664/6128

***SNAPSHOT** ● Tape backup utility for normal and headerless tapes
Powerful tape utility that will back up your tape based software, so simple to use it's childs play!
On screen details of program length. Easy push-button selection for your choice of saving speed. The next best thing to a disc drive.
Tape £6.99

AMSHELP ● Transfer tape software to disc
Better than most, AMSHELP will even transfer ASCII files. Also automatically adds a relocator for those programs that overwrite the disc memory area.
FREE Disc deprotector, list protected programs etc.
Tape £6.99 Disc £10.99

LOCKSMITH+ ● Disc utility collection
The most user friendly utility of its type, this disc includes the functions that our customers have asked for, the options include, UNERASE, RENAME, MAKE INVISIBLE, MAKE VISIBLE, SET TO READ ONLY, SET TO READ & WRITE, CHANGE USER AREA, INFORMATION ON FILE LOCATION & LENGTH, PROGRAM DEPROTECTOR, DISC-COPY, DISC SPEED-UP, FAST AND EASY FORMAT, FULL DISC TRACK SECTOR EDITOR, etc. This utility will even show hidden programs and allow you to back up discs with bad or illegal sectors and tracks (unlike some imitations) all functions are easy to use, full on screen information.
Disc £10.99

SLOW-MOTION
Now for your Amstrad, the wonderful utility that actually allows you to slow down the speed of any game (play at any speed and zap the aliens back) instantly adjustable, from full speed to freeze frame.
£15.99

● Full Spec Eprom Blower, no additional power supply required, please send a S.A.E. for details.

Prices include packing and postage Overseas orders please add £1

INTERLOCK SERVICES LTD
123b Brent Street, London NW4 2DX
Tel: 01-202 8727
(Personal callers welcome)

VISA

Advantage

The Independent Computer User Group

"C" PACKAGE FOR ONLY £12.95

Suitable for CPC6128 or PCW computer owners who wish to learn what the "C" Language offers or who are experienced programmers. Occupies an entire 3 inch disc and includes the following software:-

* **A powerful compiler**
* **A full screen program editor**
* **21k of on-screen documentation**
* **Worked examples**
* **The complete source code for the compiler**
* **Utilities written in "C"**
* **Games written in "C"**

Price, including postage, £12.95 (UK) £13.95 (Overseas) £10.95 (Advantage Members)

CP/M GAMES COMPENDIUM FOR ONLY £8.95

Suitable for all CPC and PCW computers, this suite of games includes the famous Colossal Cave Adventure, Chess, Othello and a Golf Simulator. Also included are 5 amusing programs: Biorythm Calculator, Word-Search Puzzle Generator, Calendar Generator, Maze Designer and Banner Printers.
Price, including postage, £8.95 (UK) £9.95 (Overseas) £6.95 (Advantage Members)

TWO CP/M UTILITY COMPILATIONS £8.95 EACH

CP/M II contains DIRECTORY, 20 function FILE MANAGER including read-only, multiple rename or erase, and hide from directory, ERASED FILE RECOVERY, DISC SECTOR EDITOR, FULL SCREEN TEXT EDITOR, PRINTER FORMATTER, Easy FILE DISPLAY for listing text files 24 lines at a time, forwards or backwards, HEX and ASCII CODE DUMP, FAULTY SECTOR ELIMINATOR, STRING FINDER, COMPARE FILES, TYPEWRITER EMULATOR.
CP/M IV contains DIRECTORY, INVENTORY MANAGER for business or domestic applications, LIBRARY UTILITIES to aid the organising and keeping track of your files, SQUEEZE & UNSQUEEZE which can save up to 40% of your disc space thus saving money on discs, HELP utility, WORDCOUNT for text files USER-DEFINED KEYBOARD for allocating character strings to any key, enhanced PIP, SUB and CRCCHECK.
CPC and PCW compatible. Price each £8.95 (UK) £9.95 (Oversees) £6.95 (Advantage Members)

16 UTILITIES DISC £10.95 for CPC range

BACK-Up tape-tape & tape-disc, CHARACTER DESIGNER, 12 ready-to-run CHARACTER SETS, TWO KEYBOARD definers, MEMORY MONITOR & EDITOR, ASSEMBLER, DISASSEMBLER, DIRECTORY PRINTER, COLOUR CHARTS, PROGRAM TRACER, SCREEN DUMP, RSX COMMANDS, DISC SECTOR EDITOR, FILE MANAGER for one-key Erase, Rename, Cat, List, UTILITY MANAGER. All fully menu-driven with HELP screens and print-out option.
£10.95 (UK) £11.95 (O/S) £8.95 (Members) * 13 Utilities on TAPE for CPC464 * £8.95 (UK) £9.95 (O/S)

NATIONAL & INTERNATIONAL USER GROUP

Membership includes monthly Newsletter, user-support, opportunity to share views, programs and ideas plus access to software at special prices. Fee is £8.95 per year (UK) or £13.95 (Overseas)

Advantage (DEPT U5) 33 MALYNS CLOSE CHINNOR
OXFORDSHIRE OX9 4EW

CP/M packages contain some Public Domain Software which is supplied free of charge.

NEW

TAPE AND DISC CPC464/6128 UTILITIES

Yes LERM, famous for our SPECTRUM programs, now has vital utilities for AMSTRAD owners. We also offer on ALL our products:
* **A FULL MONEY BACK GUARANTEE.**
* AN UPDATE SERVICE to get the latest version at a reduced price.

TAPESPEED TWO (TS2)

ESSENTIAL FOR ALL 464 AND 6128 OWNERS
Convert your slow loading software from 1000 to a max. of 3600 baud. Stop and study programs. We believe TS2 to be the most comprehensive backup program of its type.
* AMAZING! — now converts many of the "CLICKY" leader programs, some will load into 6128 for the first time.
* Fully automatic. It loads in continuously up to 44k.
* Save at range of 9 speeds.
* Permanent display of HEADER plus STATUS information.
* Motor on/off. Insert PAUSE. Removes protection.
* Handles HEADERLESS files.
* Handles Amstrad programs with Spectrum loaders – convert to Amstrad for study and conversions. Speed (Baud rate) detector.
* VERY SIMPLE TO USE – FULL MANUAL.

DISC MANAGER ONE

Essential to help you manage your AMSTRAD drive. No risk – try it and see how useful it can be.
* Does a CAT which can then be used to do repeat ERASURES very easily. Gives disc type. Memory free/used.
* 2 Disc editors – edit or study sectors of a disc.
* Recover ERASED files.
* Simple and fast whole disc or sector BACKUP copier.
* Send outputs to printer (CAT, sector contents, etc).
* Unsecured for easy adaptation/drive transfer.
* Menu driven - FULL manual.

ALL INCLUSIVE PRICES:

Tapespeed two: £6.50 Disc Manager £5.99 State 464 or 6128

(Overseas: add £1 within Europe, £1.50 others)
SAE for more information.

LERM, DEPT AU, 10 BRUNSWICK GDNS, CORBY, NORTHANTS NN18 9ER

COMPLETE PRESTEL LINK

ONLY £35.99



FOR YOUR AMSTRAD

Enter the world of data communication with the Cirkit Prestel Link.

A complete package for the CPC464, 664 and 6128 computers consisting of Modem, Interface and Software for only **£35.99**

The software supports full Prestel features including dynamic frames and up to 16 colours.

Terminal mode allows access to BT Gold, bulletin boards etc.

Extensive documentation of the RSX software is supplied to enable the RS232 compatible interface to be used with your own programs.

The acousticly coupled Mode is very reliable with baud rates at 1200/75 and 1200/1200 half duplex and has full BT approval.

Printer Dump – Software upgrade to obtain hardcopy of non-screen text whilst in Prestel or Terminal Mode.

PRICES inc VAT and P&P
Prestel Link Pack
£35.99 (Software on Tape)
£43.99 (Software on Disc)
Printer Dump
£6.95 (On Tape)
£12.95 (On Disc)

- **Includes free subscription to MicroLink**
- **Telesoftware coming soon!**

Cirkit Distribution Ltd.
Park Lane, Broxbourne, Herts EN10 7NQ.
Telephone (0992) 444111 Telex 22478

OPUS WILL MAKE YOU A BETTER ORGANISER FOR ONLY £60



If your micro system is starting to get out of hand a smart organiser could be the solution to your problems.

At just £59.95 the Organiser desk from Opus Supplies will help to organise your system beautifully. It's purpose built to provide plenty of storage space and because it's produced alongside our range of executive computer desking it offers a level of quality you'll appreciate.

Shelving accommodates your monitor, printer computer, disc drive or cassette recorder and software, and the teak-finished unit is fitted with castors to make it fully mobile. The Organiser's assembled dimensions are: H. 31″, W. 40¼″ and D. 26″.

And our price includes VAT and FREE DELIVERY.

The Organiser desk is suitable for use with all leading home micros including the BBC, Amstrad, Commodore and Sinclair computers.

Getting organised couldn't be easier. Phone us on 0737 65080 or simply post the coupon below.

To: Opus Supplies Ltd,
55 Ormside Way, Holmethorpe Industrial Estate, Redhill, Surrey.

Please rush me the following:
(PRICES INCLUDE VAT AND CARRIAGE)

_____ Organiser Desk(s) at £59.95 each (inc. VAT)

I enclose a cheque for £_____ or please debit my credit card account with the amount of £_____

My Access ☐ Barclaycard ☐ (please tick) no. is:

_____

Name _____

Address _____

_____

Telephone _____

Opus.
Opus Supplies Ltd.

55 Ormside Way,
Holmethorpe Industrial
Estate, Redhill, Surrey.
TELEPHONE: 0737-65080

SIR FRED

This Mikro-Gen release was not written by the team responsible for the Wally series but by the programmers who wrote Roland on the Ropes for Amsoft. The result is a graphical adventure which is very different from the Wally series with the accent more on action than on brainpower.

Your quest as Sir Fred is to rescue the King's daughter from the wicked Sir Hugh D'unnyt, not an easy task. Each time you play the game the princess is put in one of seven locations. The starting positions of the objects changes from game to game so you must modify your actions as you find the objects.

A sword is essential to get past some of the guards. The bow and arrow is useful for dispatching some of the serfs, and you can choose from three angles of flight. The arrows are needed to flick some switches which you can't reach so don't waste them.

Sir Fred is a proper little action man, he runs, jumps, swings on ropes, swims through piranha-infested waters, indulges in sword fights and throws stones. He can carry up to four objects, some can be used only once, such as the food for energy, some can be used only a number of times such as the bow and arrows, and some can be used all the time, such as the sword.

You must be careful when picking up an object to move your selection pointer to an empty "pocket" or the object you pick up will destroy any you are carrying, something I found a little hard to cope with at first, trying to get some stones while being nibbled by a piranha, but it is easy enough to move the pointer before you enter a new location.

The emphasis is very much on action – running, jumping and swinging on ropes to get yourself catapulted over walls. The ropes are very difficult to master until you realise that Sir Fred must just flick himself to the outside of the rope on the upswing to get a little more height each swing, something that could be better explained in the insert.

Sir Fred has some degree of intelligence when you are controlling him. When you get to the top of a rope and press the down key he will turn and climb backwards a little way down the rope before you can continue. He will also conveniently climb out of the water when he gets to the edge.

You feel as if you are in control of a little person as he digs his heels in and skids as you try to stop him running. Sometimes the control is not as precise as you would want. If Sir Fred accelerates by you holding down a direction key too long, he can be slow to turn round, dug in heels and all, which can mean you can be catapulting him into danger.

The keys are definable, and apart from the direction keys you have one to select an object and one to use it. The graphics are fairly simple, with the only multicoloured things being the objects and characters. Nice touches are Sir Fred's eyes that blink. In the dark rooms a torch is essential, this casts a small pool of light around Sir Fred and leaves the rest of the room in darkness.

The objects you find are fairly straightforward to use and are only necessary to allow you to get to other parts of the game, rather than be used to solve a puzzle. Throw the meat in the river to distract the pirahna, tempt the drunken boatman with the bottle of beer to get across the other river.

With 58 different game plans it should keep you very occupied, and as it is possible to complete some of them without seeing all the locations, you will be back for "just one more go".





AUTHOR MIKRO-GEN
PRICE £9.95

GRAPHICS	14	FIRST IMPRESSION	16
SOUND	18	LASTING IMPRESSION	18
POLISH	18	VALUE	18

COMMENT Too difficult for me Ed!

SPINDIZZY

If you can afford to fritter away your change in the arcades you'll be familiar with Marble Madness. It involved rolling a ball across a gridded landscape, negotiating tight bends, narrow ledges and sheer cliffs. Like so many other arcade favourites, it found its way on to a home micro. Now loads of software houses have clones written or planned, the first being Gyroscope from Melbourne "We've never seen Marble Madness, and anyway Gyroscope is totally different" House.

Now we have Spindizzy, a brilliant development of the theme which leaves its rivals for dead and, even so early into 1986, must surely be a contender for Game of the Year.

Spindizzy is a huge game, 400 screensful, which takes the gridded slopes of Marble Madness, complicates them with all manner of ramps, walls, tunnels, lifts and trampolines (honest!), stirs in some fiendish logic puzzles and tops the whole thing off with beautiful graphics and animation which will have owners of other computers drooling. This game is an Amstrad original, and although there will doubtless be conversions, it's hard to see how they can match this.

The object of Spindizzy is to explore the map and collect the flashing jewels which are scattered about it. Some are easily accessible, others perched in devious locations which will need all your skills at problem-solving and joystick control of your spinner, known as Gerald the upside-down triangle.

Often it is not just a matter of selecting the correct route, you need to alter the actual characteristics of parts of the maze by deducing the functions of the icons which litter the floor of the map. These icons are activated by running Gerald over them, but it isn't always that simple – some icons deactivate others, or need to be switched in the right order or at specific times.

Some examples. One icon you'll encounter quite early in the game is a lift, activated by moving on to it. It raises you to a higher walkway leading to an adjacent screen, and lowers you back again when you return.

A much tougher problem is posed by the castle area, which is initially sealed off. How to get the door open? It involves finding which screen elsewhere on the map has the door control, activating this icon, and then finding out how to get back off the screen without deactivating the door. Naturally, the deactivation icon lies on the only exit . . .

Game play is against the clock, and there are no lives to lose as such. Normally the clock counts down slowly, but each spinner destroyed decreases the time left by five. Collecting a crystal increases the time and it's a good idea to hit the brake sparingly because it penalises you with a much faster clock rate during use.

It's only too easy to lose spinners – much of the map is set over water, or a drop to infinity, and a misstep results in death. And as the game features true inertia and momentum, if you fall too far on to a solid surface your spinner disintegrates into four pieces with a lovely snapping sound. Conversely a good run-up to a ramp lets you leap wide gulfs.


The game uses Mode 1 to great effect. The restriction to four colours is hardly a limitation, as clever stippling creates a range of hues and shading effects. Moreover, the colour scheme changes in different parts of the map, giving a welcome variety.


The overall map can be called up at any time to check your progress: it shows your current position, which screens you have visited and which of those still have jewels left in them.

The program is full of delightful touches which gives it real class. For example, the spinner's initial appearance is an upturned, spinning pyramid (see the photographs). But if you tire of this, a keypress changes it to either a marble or a gyroscope. Other keys alter your 3D viewpoint to any of the compass points, which is often essential.

Many scenes have tall walls and ramps and the true 3D animation means that crystals, and your spinner, may be hidden from sight in some directions. A compass block indicates true north so you don't lose your bearings on the map. Finally, any monochrome Arnolds out there can relax, as the programmer has provided a green-screen option which fixes the colour scheme to a set that works best on such monitors.

Addictive, surreal, challenging, professional – do yourself and your Amstrad a favour, and get a copy of Spindizzy today.






AUTHOR Activision / Electric Dreams
PRICE £9.95

GRAPHICS	19	FIRST IMPRESSION	18
SOUND	16	LASTING IMPRESSION	20
POLISH	19	VALUE	19

COMMENT Simply brilliant

SENSATIONAL SOFTWARE FROM

MIKRO-GEN




Three Weeks in Paradise

AMSTRAD CPC 464/664/128 £9.95

Unit 15, The Western Centre, Bracknell, Berkshire

Tel: 0344 427317



ZORRO

I suppose every character of popular fiction is destined to appear in some computer game or other. Now it's the turn of Zorro, the masked avenger. In this game from US Gold, Zorro has to free the señorita from the wicked Captain who has abducted her and imprisoned. I expect you get the drift.

Anyway, the whole idea is to get past various obstacles on various screens with the aid of various objects. The Captains' men are patrolling the town, so watch out or you will have to fence them off. Sorry, I mean fight them off. Zorro can run left and right and jump. There are ladders and vines to climb up. Also there are hand rails that Zorro can use to span gaps, paratrooper style.

Dotted around the town are a number of objects such as sofas and big red rubber balls on which Zorro can bounce. The objects that can be found have special purposes. However, despite long hours of game play the only item out of a key, a bottle, a rubber plant, and a square thingy (that might be a step ladder or a pair of trousers), that I can find a use for, is the key, which opens a door.

The graphics are quite good but they look very like the Commodore 64 variety. This is not really surprising as Amstrad Zorro is bound to be a conversion of the code developed on the Commodore.

Sound is fairly sparse with only a few actions being accompanied by sound effects.

Zorro is a game of average proportions. Average sound, average graphics, average addictiveness. It is neither stunning or very original. Some will find it entertaining and will keep at their keyboard for a long while trying to sort out which object does what, but I think most game players will find it a bore.

AUTHOR US Gold
PRICE £7.95

GRAPHICS	9	FIRST IMPRESSION	11
SOUND	8	LASTING IMPRESSION	14
POLISH	17	VALUE	14

COMMENT Slish, Slash, Slish

LE 5EME AXE

A quick sortie to the Paris Amstrad Computer Show bagged a couple of really good games previously unseen in Britain. This is one of them.


Professor Gern B. Dick has been involuntarily déclenchéd on a planétoïde artificiel. This is probably a huge inconvenience for him but it won't bother you much. However it does provide you with the excuse to explore a large underground world and beat the daylights out of assorted robots.

The game starts with you, a normal looking and presumably French humanoid, standing on level one of a multi-level world. The humanoid sprite remains in the centre of the screen with the world scrolling by. Joystick control will also allow you to leap the holes in the floor. If you don't succeed you'll fall through to the next level. There are blue zebra-crossings that will hurl you up a level. Dotted around are square, round, and diamond shaped black objects. These correspond to holes in the wall near the holes in the floor. The right object will allow you to cross the holes and reach other parts of the complex.

While skipping around in your carpet slippers you'll probably bump into the odd robot or two. And when I say odd I mean odd, but beautifully animated. To dispose of them, a few Karate kicks or a dash of Kung Fu will convert them to scrap.

After a certain number of objects have been collected you go to an intermediate stage between games. This has you running along a temple corridor while unseen foes hurl spears at you. You can jump, duck, or fend off the spears but if you fail to get the timing right you'll end up with one through your head, stomach or feet.

Should Le 5ème Axe make its way across the Channel you can look forward to seeing its brilliantly animated sprites. I think it has some of the most imaginative creatures I've seen in computer games and I look forward to being able to read the instructions and play the game properly.



AUTHOR LORKIELS
PRICE UK price to be decided

GRAPHICS	19	FIRST IMPRESSION	18
SOUND	19	LASTING IMPRESSION	20
POLISH	19	VALUE	20

COMMENT Brill french prog

Evesham Micros

THE UTILITY SPECIALISTS

DISCMASTER V1.0

At last a **POWERFUL disc backup and utility** package for the 464/664/6128 series. Incorporates the following:

"DUPLICATOR" . . . A new standard of protected disc backup for the Amstrad. A **very powerful** program that will operate with one **or two** drives. We aren't saying that it will copy every disc available but our extensive tests have been **unable to find one that it won't**. We are sure that the DUPLICATOR is the **best disc backup program available**. Make no mistake many similar utilities are very limited. Future updates will be available as and when necessary at nominal cost.

"MENU MAKER" . . . A tremendously useful utility that allows you to make a menu on all your own discs **completely automatically**. You select which files are to be included on the finished menu and all the rest is done for you.

"RECOVER" . . . This program allows you to recover any files that may accidentally be erased from a disc. Very useful in case of accident.

"EXTENDED CATALOGUE" . . . Gives an extended CAT that includes the start address and length in bytes of both BASIC and machine code files.

ONLY £19.95

WARNING: Do not be misled by other adverts. There is only one "DUPLICATOR", it is the most powerful program of its type.

DOUBLER

HAVING PROBLEMS BACKING UP THE LATEST LOADING TECHNIQUES?

DOUBLER+
Will solve ALL your problems

After **enormous success** on the CBM 64 and Spectrum we now have "Doubler" available for the CPC464. Designed by DRAYSOFT, inventors of the **infamous** "Interface III", this superb unit will operate with **100% success guaranteed**. It requires the use of an auxiliary cassette deck.

Simply plug in the "Doubler" on the expansion port, connect a tape player to it with the lead supplied. LOAD the software supplied in the normal way and you are **ready to start**.

Using digital techniques "Doubler" will create a brand new machine back up of **ALL** software **100% success GUARANTEED**.

As a bonus **"Speedcop" is included** in the package. This is a superb conventional back up copier that will handle **all normal AMSTRAD loaders**. It has all the usual options like choice of save speed deprotect basic etc.

Solve all your back up problems in one move, remember we guarantee success.

ONLY £16.95

PRINTERS

SHINWA/MICRO P CPA80+

This is our most popular printer. Features include superb NLQ mode (switch selectable), high quality draft mode at 100cps, friction and tractor feed, external dipswitches and EPSON compatibility. Our price includes receipted delivery and lead to suit your micro. Must be the best printer value available

ONLY £189.95

TAXAN KAGA KP810

A chance to buy perhaps the most popular NLQ printer on the market at a very special price. Features include 140cps draft mode and 27cps NLQ, friction and tractor feed, Epson compatible etc. This printer is essentially the same as the Canon PW1080. Our price is fully inclusive of VAT, receipted delivery and lead.

ONLY £219.95

3" DISCS

Fed up with paying silly prices?

1–9 £4.25 each

10 for £39.00

Buy 10 and we will put "Excat" on one of the discs for you free of charge.

Disc User? EXCAT

Is a ***very useful*** *utility that will give you the start and end addresses of all files on your discs, including binary. At little more than the cost of the disc that it is supplied on this is a worthwhile purchase. (The rest of the disc can be used as normal.)*

ONLY £6.95


All prices include P&P and VAT. Send cheque, Postal Order of Credit Card No. Credit Card order accepted by phone. Callers welcome. Wide range of goods stocked. Trade enquiries welcome. European orders send price as advertised. Outside Europe £2.00 for airmail. Mail order to Evesham Shop please.

EVESHAM MICROS
BRIDGE STREET, EVESHAM, WORCS., WR11 4RY.
Tel: 0386 41989

MICRO CENTRE
1756 PERSHORE ROAD, COTTERIDGE, BIRMINGHAM.
Tel: 021-458 4564

WITHOUT OUR 'LEARN BASIC' YOUR COMPUTER IS ONLY PLAYING GAMES...

LOGIC 3's COMPLETE TEACHING PACK FOR TODAYS MOST POPULAR MICROS



Based on the teaching methods developed by Professor Andrew Colin of Strathclyde University, Logic 3 is the most comprehensive guide to Basic programming currently available.

Logic 3 is designed for people who want to keep abreast of the computer age, for people who realise that understanding computers is a key to future success at work, at school and as a parent.

If you are thinking of buying, expecting a present, or already have an Amstrad CPC 464/664 you need Logic 3 'Learn Basic' too.

Each Logic 3 pack contains a 190 page work-book, 2 cassette tapes containing 20 programs plus a flow-chart stencil.

QTY	COMPUTER	PRICE	TOTAL
	AMSTRAD CPC 464/664	17.95	
CHEQUES/P.O. PAYABLE TO: LOGIC 3 LTD.		TOTAL	

NAME:_____

ADDRESS:_____

_____

_____

TEL NO:_____

LOGIC 3
THE KEY TO THE WORLD OF TOMORROW

☐ **PLEASE TICK BOX IF MORE INFORMATION IS REQUIRED**

Logic 3 Ltd,
165 Garth Road, Morden, Surrey SM4 4LH, UK. Telephone: 01-330 0101,
Telex: 28704 MMH VANG, Facsimile: 01-337 5532

AU4

Agents/distributors required outside UK. Export enquiries welcome.

AMSTRAD

NEW CROWN COMPUTERS LTD.

(T/A CHILTERN COMPUTER CENTRE)

AMSTRAD

SPECIAL OFFERS FOR THIS MONTH

3-IN-1 ACCOUNTS

- Consists of Stock Control, Invoicing, Sales ledger
- Easy to use Booking in and out system
- Stock Check facilities
- Stock commitment Report
- Immediate update of stock level on production of invoice
- 20 fields per record
- Up to 30 characters per field
- FAST SORT
- Runs under CP/M
- Plus many other features

Price: £34.95

on disc

TOP SELLERS

Boulderdash	£8.46
Bruce Lee	£8.46
Computer Hits 10	£8.46
Everyones A Wally	£8.46
Fighting Warrior	£7.61
Finders Keepers	£1.69
Highway Encounter	£7.61
Nonterraqueous	£1.69
Raid	£8.46
Soul of a Robot	£1.69
Spy v Spy	£8.46
The Hit Squad	£8.46
Tau Ceti	£8.46
Friday The 13th	£7.61
3D Boxing	£8.46
3D Grand Prix	£7.61
3D Voice Chess	£11.01
Cyrus II Chess	£8.46
Daly Thompsons Supertest	£7.61
Formula I Simulator	£1.69
Glenn Hoddle Soccer	£7.61
Hyper Sports	£7.61
Scrabble	£8.46
Spitfire 40	£8.46
Yie Ar Kung Fu	£7.61
Chemistry '0' Level Examiner	£8.46
Mathematics '0' Level Examiner	£8.46
Physics '0' Level Examiner	£8.46
The French Mistress (A or B)	£7.61
The German Master (A or B)	£7.61
The Spanish Tutor (A or B)	£7.61
Bored of the Rings	£5.94
Dragon Torc	£6.76
Gremlins	£8.46
Lord of the Rings	£13.56
Lords of Midnight	£8.46
Robin of Sherwood	£8.46
Home Accounts Manager	£12.71
Masterfile	£21.21
Mastercalc	£16.96
Tasword 464	£16.96
Transmat	£6.76

DISK BEST SELLERS

Highway Encounter	£12.71
Sorcery +	£11.86
Triple Pack	£12.71
Lords of Midnight	£11.86
Bruce Lee	£12.71
Yie Ar Kung Fu	£11.01
Spitfire 40	£12.71
Spy v Spy	£11.01
Devpac-80	£33.96
Home Accounts Manager	£16.96
Mastercalc	£20.36
Masterfile	£25.46
Pascal-80	£33.96
Pitman Typing Tutor	£11.01
Screen Designer	£16.11
Supercalc 2	£42.46
Tasword-6128	£21.21
Tasword-D	£21.21

AMSTRAD HARDWARE

PCW 8256	£435.90
CPC6128 colour	£379.95
CPC6128 green	£284.95
CPC464 colour	£284.95
CPC464 green	£189.95
DD1-1 Disc Drive	£151.95
FD-1 Disc Drive	£94.95
FD-2 for 8256	£151.95
MP 2 Modulator	£28.45
JY-2 Joystick	£13.25
3" Discs (box 10)	£42.75
DMP 2000 Printer	£151.95
Extension cable	£9.45
Data Recorder (DR101)	£33.20
RS232 for 464, 6128	£47.45
RS232 for 8256	£56.05

Up to £50 Trade in on your old computer when you buy a new Amstrad Computer from us, please ring for details.

"All prices include VAT & Postage in the UK only. Prices are valid for orders received for this month only. Overseas customers please add 50p for Europe and 75p for the rest of the world per tape. Overseas hardware prices on request. Please ring for availability of software and prices.
Please send large S.A.E. For our latest Catalogue.

DISC EDITOR

- Discards faulty sectors
- Allows faulty diskettes to be used
- Recover accidently deleted files
- Dump sectors in Hex and Ascii
- Examine and modify data on disc
- Many other useful features

Price £14.95

on disc

MAIL ORDER
Please make Cheques & Postal Orders Payable to:

NEWCROWN COMPUTERS LTD.
98/100 HIGH TOWN ROAD,
LUTON, BEDS LU2 03P
Tel: (0582) 455684

Overseas trade & mail order enquiries welcome.

ACCESS VISA

★ CP/M SOFTWARE & SUPPORT FROM DRA ★

POCKET PROSTAR SUITE

£199.00

Includes Pocket WordStar, Pocket CalcStar, Pocket DataStar and Pocket ReportStar—PLUS the DRA independent Pocket ProStar Guide. Available for Amstrad 8256 (or 6128 with 2 drives), BBC Z80, etc.

- ★ MicroPro's integrated family of software programs
- ★ Pocket WordStar for word processing and mail merging
- ★ Pocket CalcStar spread sheet for calculations, projections and analysis
- ★ Pocket DataStar database filing and retrieval system
- ★ Pocket ReportStar the powerful report generator and data sorting program
- ★ Pocket ProStar Guide for the complete beginner to the most experienced MicroPro user
- ★ Support from DRA – the MicroPro software experts

Using the MicroPro Pocket programs and the Pocket ProStar Guide, you will be able to design complete systems for your small business, professional practise (e.g. medical, legal), for office administration, or for education at all levels from primary school business/computer studies to university research departments. The MicroPro reference manuals are available at extra cost.

FREE SOFTWARE HANDBOOK PLUS 70 CP/M PROGRAMS ON DISC

- ★ A comprehensive selection of favourite Public Domain CP/M programs – with excellent documentation in the form of the Handbook
- ★ Chapters on Family Fun, Directory Assistance, Useful Utilities, Libraries and Catalogues, Communications, and a Hacker's Toolbox.


3" disks/book set **£39.95**

Send Cheque (or VISA/ACCESS number) to:

DAVIS RUBIN ASSOCIATES LTD
1 Canonbourne, Weston sub Edge, Glos. GL55 6QH
VISA/ACCESS orders: TEL (0386) 841181 All prices include VAT and Postage

★★★★ SEND FOR OUR FULL LIST ★★★★

TLL



Hot on the heels of Highway Encounter, the last release from Vortex, comes TLL. This consists of a semi-3D view of a landscape filled with trees, houses, lakes and the like. You control a tornado fighter on a bombing sortie, the aim being to drop bombs on strategically placed targets shown as a small circle on the map. As your plane flies across the landscape the background scrolls in all four directions allowing you to move this scrolling window over the much larger map.

One great feature is the shadow of the aircraft that is cast on the ground. As you fly over a building the shadow is seen to go up the side then across the roof in a very lifelike fashion. This is quite important, as it allows your height to be judged.

Once the target has been located you must go down low both to be sure of hitting the target and also so that your speed drops to a manageable level. If you pull back on the joystick the aircraft gains height and speed until it is flying supersonically and the swing wings are pulled in. When you are flying fast you have to be very careful where you choose to push the joystick forward to slow down for the sudden loss of height will probably leave you splattered up the side of one of the buildings.

Left and right movement of the joystick causes the plane to bank and hence turn in 45 degree steps giving the eight possible directions for flight. Pushing the M key shows a mode one status screen which includes a complete map.

Graphically the game is quite brilliant and its concept is reasonably novel. Technically it is a masterpiece. The speed at which the 16k of screen memory is scrolled about, especially in supersonic flight, is quite outstanding.

I don't doubt that you can probably learnt to become pretty good at controlling the fighter, but for the first time user it doesn't exactly instill confidence when you can get through your three jets faster than you can say Super Etandard.

AUTHOR VORTEX
PRICE £8·95

GRAPHICS	17	FIRST IMPRESSION	15
SOUND	17	LASTING IMPRESSION	18
POLISH	18	VALUE	17

COMMENT Bombing for Beginners



THEATRE EUROPE

Theatre Europe is the latest release for the Amstrad in the PSS Wargames Series. It simulates the battle for Europe when the Third World War comes. This is not the happiest of subjects for a computer game, and some people will consider it in bad taste. My opinion is that any scenario that challenges the intellect and educates is valid provided it doesn't trivialise serious matters.

The game shows you a map of Europe on which the Nato and Warsaw Pact units are lined up against each other across the East German border. There are four stages to every game turn – movement, attack, supply and air phase.

The game can be played almost entirely with the joystick. A cursor is moved around the screen and over the required unit. As the cursor passes over each square the terrain or the details about the unit are displayed. Pressing the fire button selects a unit if it belongs to your force. The cursor is then moved to an adjacent square and fire moves the piece or selects a unit to attack.

The next stage is called special missions. Among the options are strategic chemical launches, strategic nuclear launches and all-out blanket attacks. Your enemy gets the chance to strike back so there seems little advantage in initiating a nuclear or chemical attack unless it is to break the opposition attack.

After each attack phase there is a supply stage in which a number of supply points can be distributed to bolster up individual units. The air phase gives you the chance to try and retain air superiority by careful management of your air force resources.

The screen at the end of the game says something like "Civilisation destroyed – press any key to try again".

If only it was that simple . . .

AUTHOR PSS
PRICE £8·95

GRAPHICS	11	FIRST IMPRESSION	14
SOUND	12	LASTING IMPRESSION	16
POLISH	11	VALUE	16

COMMENT Advanced Warfare


GOLD

TANK COMMAND

Amsoft

© MAGIC LOGIC 1986

A MULTI - SCREEN GAME OF *ACTION, STRATEGY & BATTLE*



£13.95

Disc only

SOFT 07023

CLUEDO

OK, so it plays Cluedo now. Hands up all you people who have played computerised board games before? Right, now how many played the next round on good, old-fashioned printed cardboard? I think I have just proved a point.


These Waddington games are wonderful – in their original form. The Amstrad versions are a pale shadow of the real thing, probably not helped by them being really awful Spectrum conversions. This game asks you if you are using a colour *television?* Methinks they missed that one.

So let's see what you get for your er . . . how much does it cost Ed? *(£9.95 – Ed).* Thank you. Right, a genuine green cardboard box, a lot of plastic moulding that holds the cassette and fills up most of the box, a distruction leaflet (mostly a mass of ©s, ®s, and TMs), a sticker advertising the film of the game, and a little booklet of detective note sheets that everyone will shove through a photocopier.

You get to roll a computer generated dice down the left-hand side of the screen, though it looks more like it is having a fit than rolling. You then move your character the requisite number of places. Be warned! if you cheat by moving it too far too often it seems to forfeit you your move. This may be a feature or a bug, I'm not sure.

Anyhow, accusations fly back and forth like Sikorsky vs. the European consortium as per your usual Cluedo, except you can't see your clue cards. These are stored in the computer until you want to look at them. Then you tell everybody else to look at the ceiling while you put your mit over the corner of the screen and see what you got.

This is indeed a computerised version of Cluedo and is a direct take-off of the original, but with less cheating. I prefer the original board games on boards, though the computer version does have one advantage – little brother doesn't nick the gun for his Action Man.



AUTHOR LEISURE GENIUS
PRICE £9·95

GRAPHICS	11	FIRST IMPRESSION	5
SOUND	10	LASTING IMPRESSION	2
POLISH	4	VALUE	7

COMMENT Loses in the translation



Send to: **Global Software, PO Box 67, London SW11.**

Please rush me ..... copy(ies) of
Operation Caretaker The Beer Hunter
Old Scores (delete where necessary)
for my _____ computer

I enclose a cheque/PO for _____
Name _____
Address _____

ACU 4/86

DOORS OF DOOM





SOFT 07047 DISC

£13.95
DISC

Extended version Available on disc

£9.95
TAPE

SOFT 06047 TAPE





ACTION AND ADVENTURE FROM AMSOFT GOLD

ROMANTIC ROBOT present



Where can you find a unique combination of arcade and adventure played within an intricate maze of over 250 hi-res colour screens with superb graphics and animation, stereo music and sound effects, dozens of creatures and objects including flying spider invaders and lurking killer spiders, flobs from outer space, intelligent ants, erratic wasps, moving floors and rising heads, lifts in bottomless shafts, various keys to various doors, spaceships, acid drops and acid helmets, ant sprays, moneybags, parachutes, energy replenishable with milkshakes, bowls of cherries, iced buns, apples, cups of tea, cornflakes and ice-cream ?







All this and much more in the greatest ever maggot marathon, in the combat against time and fellow maggots where there are many routes to the finish, where you will go through Hell, Dungeons, Garden, Mansion, Underground, Basement, Scrubland and Planet Surface, where each object can play a vital role, where the hazardous labyrinth race requires all your arcade skills, quick fingers, fast thinking, perfect timing, problem solving logic, orientation and also a good sense of humor. ALL THIS AND MUCH MORE in the







Wriggler



'*It is very different from anything I have seen before.*' Crash

'The grahics and sound are excellent and the game is totally addictive.' Computer & Video Games

'Great game, good music, well recommended.' What Micro

'*The graphics are excellent.*' Computer Gamer

'Wriggler is a totally original game.' Crash

'*The game is crazy, the graphics are a delight.*' PCN

'The range of problems and the 265 locations lift this well above the norm. A winner.' PC Weekly



'If you've any sense you'll order your copy now.' PCN

'Well worth buying.' ZX Computing

'The graphics, animation and choice of colour are superb.' Crash

'*One of the best games for any machine I've seen for very long time.*' PCN

'Overall, a very good game worth buying.' Crash

'The amount of different screens makes the game very playable, enjoyable, and more importantly, addictive. I would recommend this to any child between the ages of 8 and 80.' AMSTRAD USER

'Graphics 9/10 Sound 9/10 Value 10/10 Playability 10/10' Computer & Video Games





'Wriggler is one of the most attractive arcade adventure games I have seen for a very long time.' AMTIX

'The music is excellent' AMTIX

Plus a bonus:
Original music to wriggle to the Wriggler

THE MOONS OF JUPITER



SPECTRUM tape £ 4.95
AMSTRAD tape £ 7.95
disc £ 11.95

Available from Boots, W.H. Smiths, TBD, Thorn EMI, Centresoft, GEM, R&R, Vanguard Leisure, Warwick Distribution, Micro Dealer, and any good computer stockist or direct from ROMANTIC ROBOT, 77 Dyne Road, London NW6 7DR or phone 0892 834783

cascade CASSETTE 50



50 COMPUTER GAMES ON ONE CASSETTE

YOURS FOR £9.95

including FREE Watch and Postage

CASSETTE 50 IS AVAILABLE ON

BBC A/B ATARI DRAGON ELECTRON
VIC 20 ORIC-1 ZX81 apple Atmos
Spectrum commodore 64 AMSTRAD

Amstrad CPC 464

Avoid the rockets and anti-aircraft guns and DYNAMITE the dam, only the most skilful pilots succeed. Find yourself in different scenario's in this original adventure to search for the KINGS ORB. NEMESIS a sophisticated version of Othello with many colourful options and levels of play.
To mention only three of the 50 games on the Amstrad Cassette 50, which includes arcade type games, war games, adventure games, logical, tactical, and educational games, a flight simulator, and a business strategy game. Cassette 50 features multicoloured and user-defined graphics, joystick compatibility, sound and music utilising the amazing power of your Amstrad.

1. Maze Eater
2. Cyclons
3. Space Mission
4. Lunar Landing
5. Fantasy Land
6. Startrek
7. Whirly
8. Attacker
9. Tanks
10. Galactic Attack
11. Ivasive Action
12. Noughts and Crosses
13. Royal Rescue
14. Play Your Cards Right
15. Creepy Crawley
16. Hangman
17. Pontoon Bet
18. Thin Ice
19. 3D Maze
20. Colony 9
21. Force Field
22. Solit
23. Tunnel Escape
24. Barrel Jump
25. Trucking
26. Rally 3000
27. Sitting Targ
28. Nemesis
29. Space Ship
30. Jet Flight
31. King's Orb
32. Intruder
33. Inferno
34. Ghosts
35. Submarines
36. Space Base
37. Planets
38. Black Hole
39. Dynamite
40. Timebomb
41. Day at the Races
42. Space Search
43. Trivia Quiz
44. Rats
45. Tanker
46. Dungeon Adventure
47. Jet Mobile
48. High Rise
49. The Force
50. Exchange

(Supplied on cassette, compatible with 664 and 6128 when used with cassette player and suitable leads.)

Names and games may vary for each type of computer.

FREE

20 KEY, MULTIFUNCTION CALCULATOR WATCH
with every order for a Cassette 50

- Normal 12 and 24 hour time mode
- Calendar mode
- Alarm mode
- Calculator mode

WORTH OVER £10



FREE *calculator watch with every Cassette 50*

EXPRESS DELIVERY-ORDER NOW!

ONLY £9.95

Name _____

Address _____

_____

_____ Post Code _____

Country _____ AU 4/86

Postage Free in UK add £1.00 for overseas orders.
Free watch and tape will be despatched within 28 days.

I enclose a cheque/ postal order for £ _____ made payable to Cascade Games Ltd.


or through any Post Office by TRANSCASH (Giro No. 655 6655)
For even faster ordering when charging to Access, Barclaycard and Trustcard Visa use our 24 hour service. (0423) 504663.

VISA No. _____

AMSTRAD	☐	ATARI	☐	ORIC 1	☐	BBC A/B	☐
SPECTRUM	☐	VIC 20	☐	ZX 81	☐	APPLE	☐
COMMODORE 64	☐	ATMOS	☐	DRAGON	☐	ELECTRON	☐

Cascade Games Ltd., 1-3 Haywra Crescent, Harrogate, North Yorkshire, HG1 5BG, England.
Telephone: (0423) 504663. *Registered Number 1755554*

SPECIAL DELIVERY: Our excl



There could be few things worse than missing your monthly dose of *Amstrad Computer User*. One way of ensuring you don't suffer this fate is to subscribe to *ACU*. You can make sure of getting the next 12 copies of *ACU* for only £12 including postage and packing.

Amstrad Computer User is the ideal source of reference for every user of Amstrad computers. Keep your magazines tidy and in tip-top condition by using our top quality binder. The *Amstrad Computer User* binder holds 12 issues. Each binder is black with the *ACU* logo embossed in a bright silver. Only £3.95.

RAM Expansion

Expand your CPC memory with a DK'Tronics Rampack. Available as either a 64k or 256k unit the Rampack makes the CPC464 and CPC664 hardware compatible with the CPC6128. The extra RAM can be used to store screens, text or data. The unit comes with a full set of RSXes to make using the extra RAM as easy as possible. For prices see order form on the right.

Keep your equipment free from dust and grime with an *Amstrad Computer User* dustcover, made from clear pliable vinyl and bound by strong red cotton and sporting the *ACU* logo.

CPC 464/664 keyboard cover	£3.95
CPC 6128 keyboard cover	£3.95
Green screen monitor cover	£5.95
Colour screen monitor cover	£5.95
PCW 8256 keyboard, monitor and printer set	£11.95

Amstrad User program listings on tape and disc

Tapes contain all the major listings from *Amstrad Computer User.* Discs offer better value for money as they also contain public domain software from the CP/M users' group. Contents for the last two months:

January: Mode 3, how to use the Amstrad's secret 8k screen mode.
Sorcery, Plus Pokes and Sprite editor.
Shaded Dump, utility for Epson compatible printers.
Pak Caverns, machine code and Basic game.

February Animation: make your own computer titles.
Roland takes a running Jump. Game and Screen designer.
Galaxians Revenge. Space Shoot-em-up.

March: Roland Takes a Running Jump source code.
Racer: Prize winning Grand Prix game.

Tapes £3.50 **Discs £6.50**

sive reader offers



Issues 1 and 2 sold out.
Issue 3 (Jan/Feb '85): Listings special, Amthello, Up the Beanstalk.
Issue 4 (March '85): Software checklist, simple screen dump with events.
Issue 5 (April '85): Games special, Sorcery and more.
Issue 6 (May '85): The CPC 664, first full review
Issue 7 (June '85): Rock Hopper listing. Plotter & Printer reviews.
Issue 8 (July '85): Speech Synths reviewed, 664 & 6128 to 464 conversion program.
Issue 9 (August '85): Drawing packages compared, Screen designer Vs Artwork and Artist.
Issue 10 (Sep '85): Jet Set Willy Map & Pokes, Knightlore Map.
Issue 11 (Oct '85): CPC6128 full review, PCW 8256 Preview.
Issue 12 (Nov '85): DMP 2000, Full review.
Issue 13 (Dec '85): Making a telly ad, Wally map & Pokes.
Issue 14 (Jan '86): Mode 3, simple screen switching.
Issue 15 (Feb '86): RAM expansions reviewed, Bumper business supplement.
Issue 16 (March '86): Reviews: Modems, Music System, Dart light pen, Hitch Hikers, Laser Basic, Racer Listing.

All back issues £1.25 incl. p&p.

AMSTRAD COMPUTER USER

ORDER FORM

Valid to 30.4.86

All prices include postage packing & VAT.
All overseas items despatched by air mail.
Offers subject to availability.

Subscription

	(✓)	£ p
UK and Eire £12	8000	
Europe £25	8001	
Overseas £40	8002	

Backnumbers

Issue	Month			
Issue 3	Jan/Feb '85	£1.25	8003	
Issue 4	March	£1.25	8004	
Issue 5	April	£1.25	8005	
Issue 6	May	£1.25	8006	
Issue 7	June	£1.25	8007	
Issue 8	July	£1.25	8008	
Issue 9	August	£1.25	8009	
Issue 10	September	£1.25	8010	
Issue 11	October	£1.25	8011	
Issue 12	November	£1.25	8012	
Issue 13	December	£1.25	8013	
Issue 14	January '86	£1.25	8014	
Issue 15	February	£1.25	8015	
Issue 16	March	£1.25	8016	

Tapes & Discs

		Tape	Disc
January '86	8044/45		
February '86	8046/47		
March '86	8048/49		
April '86	8050/51		

Tapes £3.50; Discs £6.50

ACU Dustcovers

CPC 464/664 keyboard	8100	
CPC 6128 keyboard	8101	
£3.95 UK; £4.50 Overseas		
CPC range green screen	8102	
CPC range colour monitor	8103	
£5.95 UK; £7.45 Overseas		
PCW 8256 keyboard, monitor and printer set	8104	
£11.95 UK; £14.20 Overseas		

ACU Binders

£3.95 UK £6.95 Overseas	8106	

DK'Tronics RAM Expansions

CPC 464/664 64k Rampack	£45.95	8107	
CPC 464/664 256k Rampack	£89.95	8108	
CPC 6128 256k Rampack	£89.95	8110	
CPC 464/664 Silicon Disc	£89.95	8111	
CPC 6128 Silicon Disc	£89.95	8112	

Overseas readers, please add £1 per item unless otherwise indicated

TOTAL

Send to:
Amstrad Computer User,
Freepost,
36 St Petersgate,
Stockport
SK1 1HL.

Telephone orders 061-429 7931 *24 hours*
Enquiries 061-480 0171 *9am-5pm*

Payment please indicate method (✓)

☐ Access/Mastercharge/Eurocard

☐ Barclaycard/Visa

Expiry date /

☐ Cheque PO made payable to Amstrad Computer User

Name _____

Address _____


_____

Please allow up to 28 days for delivery

ACU3

FEATURE

How to get your screens in a twist ...



By Alexander Martin. Original Bankman code and airoplane concept by Roland Perry

When the 664 and 6128 were produced, parts of the operating system were altered to make it possible to do things that the old firmware wasn't flexible enough to allow. Using the new flexible firmware a smooth screen animation effect can be produced from Basic. This article includes RSXs that will allow a Basic programmer to use this feature and also a Basic program that illustrates its use.

We have provided the code to allow users of the 664 to set up the RSXs. If you have a 6128 then the RSXs are already provided for you as part of the Bank Manager package. This is explained in the section for 6128 owners. You can follow the procedures below to set up the example without having to know how it works.

664 owners

Type in the Hexloader program and save it. Then run it. It will produce and save a binary file containing the RSXs which you then load and run with the RSXloader program. Type in the example program and save it. You should now have all four programs on disc. Reset the machine for a 'clean start'. Now run the RSXloader program. Next run the example program.

6128 Owners

Filecopy Bankcode.bin onto a disc. Type in the Bankmanloader program and save it. Type in the example program and save it. You should have the three files on a disc. Reset the machine for a 'clean start'. Now run the Bankmanloader

HEXLOADER


```
10 ' hexloader for 664 owners
20 '
30 MEMORY &7FFF
40 addr=&8000
50 FOR ln=1000 TO 1370 STEP 10
60   READ bigdata$
70   checksum=VAL(MID$(bigdata$,18))
80   checkall=checkall+checksum
90   FOR pointer=1 TO 16 STEP 2
100     byte$=MID$(bigdata$,pointer,2)
110     c$=MID$(byte$,1,1):GOSUB 210:c$=
    MID$(byte$,2,1):GOSUB 210
120     result=VAL("&"+byte$)
130     POKE addr,result
140     addr=addr+1
150     checksum=checksum-result
160 NEXT pointer
170 IF checksum<>0 THEN PRINT"CHECKSUM E
    RROR IN LINE";ln,bigdata$:STOP
180 NEXT ln
190 IF checkall=28581 THEN SAVE"democode
    ",b,&8000,&130 ELSE PRINT"Incorrect
    number of data lines"
200 STOP
210 IF INSTR("0123456789ABCDEF",UPPER$(c
    $))=0 THEN PRINT"TYPING ERROR IN LIN
    E";ln,bigdata$ :STOP :ELSE RETURN
220 '
230 '
1000 DATA 21E1E9223000F7EB 1055
1010 DATA 212100194E234623 309
1020 DATA 79B02855E5606919 877
1030 DATA E54E234660691944 706
1040 DATA 4DE1712370E118E4 1039
1050 DATA 600063006A007500 418
1060 DATA 78007B007E009900 522
1070 DATA 9C009F00AC00B400 667
1080 DATA BA00BF00C900CE00 784
1090 DATA E000E800EE00F600 940
1100 DATA FB00030110011701 296
1110 DATA 1B01000000000000 28
1120 DATA 00000000 3EC932F9 562
1130 DATA FF21A100CDD4BCD8 1270
1140 DATA 21F9FF110080B7ED 1102
1150 DATA 523006218300C31D 524
1160 DATA 0101990021590 0C3 472
1170 DATA D1BC546F6F204C6F 922
1180 DATA 770D0A4261642043 504
1190 DATA 6F6D6D616E640D0A 659
1200 DATA A100C3A900C3DD00 941
1210 DATA 564945D75644D500 810
1220 DATA FE01C21A01DD7E00 823
1230 DATA FE02D21A01B7280F 731
1240 DATA CD0801E5F52A5700 817
1250 DATA CD05BC3EC0180DCD 894
1260 DATA 0801E5F52A5500CD 815
1270 DATA 05BC3E40CD08BCF1 961
1280 DATA E1C355BDFE01C21A 1169
1290 DATA 01DD7E00FE02D21A 840
1300 DATA 01B7280DCD08013E 513
1310 DATA C0CD08BC2A570018 746
1320 DATA 0BCD08013E40CD08 564
1330 DATA BC2A5500C305BCCD 908
1340 DATA 0BBCFEC020042257 802
1350 DATA 00C9FE40C0225500 830
1360 DATA C9218C007E23CD5A 830
1370 DATA BBFE0A20F7C90000 931
```

RSXLOADER

```
10 'rsx loader for 664
20 '
30 MEMORY &3FFF
40 LOAD"democode.bin",&8000
50 CALL &8000
60 PRINT"now RUN the EXAMPLE program"
```

EXAMPLE PROGRAM

```
15 ENT-1,1,1,1
20 REM mountains
30 DEFINT a-z
40 INK 0,1:INK 1,26
50 INK 2,6:INK 3,6
60 FOR i=4 TO 7:INK i,9:NEXT
70 FOR i=8 TO 15:INK i,20:NEXT
80 SYMBOL 252,0,0,&C,&1F,&30,&7F,&FF
90 SYMBOL 253,0,6,&E,&F2,2,&F2,&FE
100 SYMBOL 254,0,&60,&70,&7F,&7F,&7F,&7F
110 SYMBOL 255,0,0,0,&F8,&EC,&FE,&FF
120 pr$=CHR$(254)+CHR$(255)
130 pl$=CHR$(252)+CHR$(253)
140 FOR scr=0 TO 1:|VDU,scr:MODE 0
150 RANDOMIZE 1:RANDOMIZE RND
160 DEG:ORIGIN 0,150:CLG:MOVE 0,150
170 FOR x=16 TO 640 STEP 16
180  DRAW x,COS(x)*150+RND*100,4
```



program. Next run the example program.

Now it can be told

The RSXs used in the example program are hidden away inside Bankcode.bin. When RSXs are used, they have to be loaded into memory as a binary file and then CALLed to log them on. If you CALL the Bank Manager RSX code with a parameter this will automatically log on the two additional RSXs. To simplify the Bankmanager explanation in the 6128 manual, these additional commands were hidden away and undocumented.

```
BANKMANLOADER

10 'rsx loader for 6128
20 '
30 MEMORY &3FFF
40 LOAD"BANKMAN.BIN",&8000
50 CALL &8000,1
60 PRINT"now RUN the EXAMPLE program"
```

How does it all work?

There are two 16k areas of RAM that can be used as screen memory. The default is the area above &C000 which we've called Screen 0. The other is referred to as Screen 1 and resides at &4000 up. It is the process of switching between these two screens that allows the animation effect to be achieved. The firmware on the 664 and 6128 differs from the 464. The 464 firmware assumes that a read or write to the screen operates on the currently displayed screen. The 6128 and 664 firmware does not make this assumption and writes to the screen it has been told to write to.

This is the documentation for the two RSXs:

|VDU,n

This changes the screen area being used. The parameter n should be either 1 or 0.

|VIEW,n

This changes the screen area being displayed. This command does not change the screen being written to (by commands like PRINT, PLOT, DRAW) or read from (like TEST and COPYCHR$). The parameter n should be either 1 or 0.

About the example program

Within the example program |VDU is used for two purposes. To select the screen to display and to select the screen to write to. |VDU is immediately followed by |VIEW in several places. This is so the firmware is set to write into one screen and then told to display the other. |VDU will always set the screen to write to and the screen to display.

The animation is achieved by setting the computer to display one screen while erasing the old image on the other. The new image is then drawn in and the displayed screen changed to reveal it. This requires that the old position of the character for each screen is recorded making the animation technique horrendously complicated.

You can see how the program works by 'REMing out' the RANDOMIZE commands in line 150. This draws a slightly different range of mountains in each screen producing a 'Rhubarb and Custard' effect.

Using the RSXs in your own programs

You can use the RSXs in your own programs by using the loaders to load and log on the RSXs. Both Bankcode.bin and the code created by Hexloader are relocateable. You will have to be careful about where in memory you place the RSXs as the lower screen space &4000 to &7FFF must be clear. This is the reason HIMEM is set to &3FFF using the MEMORY command.

ACU

```
190 NEXT x
200 MOVE 0,0:FILL 4
210 cx=175:GOSUB 270
220 cx=525:GOSUB 270
230 NEXT scr:|VIEW,0
240 GOTO 350
250 '
260 '
270 MOVE cx,100
280 FOR x=0 TO 360 STEP 10
290  DRAW cx+SIN(x)*50+10*RND,100+COS(x)
    *25+10*RND,1
300 NEXT
310  DRAW cx,100:MOVE cx,90:FILL 1
320 RETURN
330 '
340 '
350 TAG:MOVE 0,0,,1
370 rx=-32:ry=100:x=rx:y=ry:GOSUB 610:or
    x1=rx:ory1=ry
380 lx=672:ly=100:x=lx:y=ly:GOSUB 620:ol
    x1=lx:oly1=ly
390 |VDU,0:|VIEW,1:GOTO 470
400 |VDU,0:|VIEW,1
410 x=orx0:y=ory0:GOSUB 610 'erase old p
    lanes  on 0
420 x=olx0:y=oly0:GOSUB 620
430 rx=rx+4:ry=50*SIN(rx)+100:lx=lx-8:ly
    =ly+crash*2
440  IF lx<-64 THEN lx=672
450  IF rx>672 THEN rx=-32
460 scr=0:GOSUB 630
470 x=rx:y=ry:GOSUB 610:orx0=rx:ory0=ry
    'draw new on 0
480 x=lx:y=ly:GOSUB 620:olx0=lx:oly0=ly
490 |VDU,1:|VIEW,0
500 x=orx1:y=ory1:GOSUB 610 'erase old p
    lanes on 1
510 x=olx1:y=oly1:GOSUB 620
520 rx=rx+4:ry=50*SIN(rx)+100:lx=lx-8:ly
    =ly+crash*2
530  IF lx<-64 THEN lx=672
540  IF rx>672 THEN rx=-32
545 IF ly<-150 THEN INK 0,26:FRAME:FRAME
    :INK 0,1:ly=100:lx=672:crash=0
550 scr=1:GOSUB 630
560 x=rx:y=ry:GOSUB 610:orx1=rx:ory1=ry
    'draw new on 1
570 x=lx:y=ly:GOSUB 620:olx1=lx:oly1=ly
580 GOTO 400
590 '
600 '
610 MOVE x,y,2:PRINT pr$;:RETURN
620 MOVE x,y,8:PRINT pl$;:RETURN
630 FRAME:IF scr=1 THEN |VDU,0 ELSE |VDU
    ,1
640 found=TEST(lx+4,ly-12):IF found=2 OR
     found=3 THEN crash=-4:SOUND 129,25,
    400,15,,1,15
650 |VDU,scr
655 IF scr=1 THEN |VIEW,0 ELSE |VIEW,1
660 RETURN
```

RSD CONNECTIONS LTD

MONITOR LEADS

BBC to Microvitec	£2.20
TV to Computer	£1.25
Green Screen	£2.95
BBC to Fidelity etc.	£4.95
QL to Fidelity etc.	£4.95
Phone to Phono	£1.25
BBC to Ferguson	£2.50
QL to Microvitec	£2.50
QL to mono monitor	£1.50
BBC to Sony/Kaga	£5.95
BNC to BNC	£2.95
COMMODORE to Ferguson	£2.50
BBC to Hitachi	£2.50
SONY to Fidelity etc.	£6.50
MSX to Ferguson	£2.50
QL to Ferguson	£2.50

IDC AMPHENOL

36-way plug	£4.95
36-way socket	£5.95
36-way plug (solder type)	£4.95

DISK DRIVE LEADS

Dual disk drive power lead	£4.50
Dual disk drive lead 1m	£10.25
Single disk drive power lead	£2.75
Single disk drive extn. lead 1m	£7.25
Disk drive extn. lead 1m	£7.25
AMSTRAD 2nd DRIVE	£6.95

CASSETTE LEADS

BBC to cassette	£2.25
DRAGON to cassette	£2.20
SPECTRUM to cassette	£1.25
BBC to Acorn cassette	£2.25
AMSTRAD to cassette	£2.20

PRINTER LEADS
ALL 1 METRE LENGTH

BBC	£9.95
BBC serial	£8.95
AMSTRAD	£10.75
MEMOTECH	£12.75
EINSTEIN	£12.75
IBM PC	£12.75
SPECTRUM interface One to RS 232	£9.75
ATARI	£15.25
MSX	£13.95
APRICOT	£15.20
DRAGON	£9.95
QL	£10.75

ANY COMBINATION OF LEADS MADE TO ORDER

AMSTRAD EXPANSION PORT EXTENSION LEADS

NEW!

6" Single F to m	£10.50
Double F to 2M's	£14.75

Suitable for 664 & 6128
The easy way to connect your add-on's

AMSTRAD MONITOR EXTENSION LEADS

To 464, 1m.	£6.50
To 664 & 6128	£7.50

AMSTRAD PRINTER LEADS

1 metre	£10.75.
2 metres	£12.50

AMSTRAD 2nd DRIVE LEAD

Suitable 664 & 6128. 1m	£6.95

AMSTRAD 8256

1m. Printer Extn. lead	£9.50

AMSTRAD CASSETTE LEAD

1m. 5-pin to 3-Jack	£2.20

IDC SHROUDED HEADERS WITH EJECTING LOCKING ARMS

	Straight	Right Angle
10-way	.85	.90
14-way	£1.00	£1.20
16-way	£1.25	£1.45
20-way	£1.40	£1.60
26-way	£1.70	£1.95
34-way	£2.00	£2.30
40-way	£2.15	£2.45
50-way	£2.30	£2.65
60-way	£2.45	£2.85

DISTRIBUTION SOCKET

4-WAY MAINS

4-way top quality mains trailing sockets. Supplied wired up with mains plug ready for use. Can be screwed to floor or wall if required. Very useful for tidying up all the mains leads from your peripherals. Allows the whole system to be switched on from one plug.
ONLY £9.50

IDC D CONNECTORS

	Male	Female
9-way	£2.70	£3.20
15-way	£3.20	£3.70
25-way	£3.80	£4.45
37-way	£5.90	£6.80

RIBBON CABLE (Price per ft)

	Grey	Rainbow
9-way	.13	.24
10-way	.15	.28
14-way	.18	.32
15-way	.20	.36
16-way	.22	.40
20-way	.30	.50
24-way	.36	.60
25-way	.40	.65
26-way	.45	.70
34-way	.60	.80
37-way	.65	.85
40-way	.70	.90
50-way	.95	£1.25
60-way	£1.10	£1.40
64-way	£1.15	£1.50

TELEPHONE CONNS

Surface master jack socket	£3.75
Surface extn socket	£2.50
Dual outlet adaptor	£4.25
Line jack cord 3mr	£1.85
4 core cable per metre	15p

BT Plugs each 48p

CONNECTORS IDC

	Card Edge	Trans PCB	2 Row Socket
10-way	£1.20	£0.95	£0.80
14-way	-	-	£0.90
16-way	£1.60	£1.20	£1.00
20-way	£1.90	£1.35	£1.20
26-way	£2.40	£1.60	£1.45
34-way	£3.10	£1.95	£1.60
40-way	£3.40	£2.00	£1.85
50-way	£3.85	£2.25	£2.00
60-way	£4.80	£2.60	£2.25

D CONNECTORS

Solder	Bucket	Male	Female
9-way		.75	£1.00
15-way		.95	£1.50
25-way		£1.50	£1.90
37-way		£2.40	£3.25

HOODS .95

TRADE ENQUIRIES WELCOME

75p P&P IN UK. Access & Visa accepted. Add 15% VAT to all orders
Cheques made payable to
RSD Connections Ltd, Dept AU4 PO Box 1, Ware, Herts.
Tel: 0920 5285/66284

TYPESETTING+PRINT FROM YOUR AMSTRAD DISKS



ThamesLink Limited,
ThamesLink House,
38 Thames Street,
Windsor,
Berkshire. SL4 1PR
Telephone: Windsor 863356
Telex: 847723
Comms: Windsor 851989
Prestel: 735363356

SOFT-MACHINE

INTRODUCE

META-BASIC

The most comprehensive BASIC utilities package yet!

Features:
* **!BPRINT** – All text sent to the screen enlarged by any amount.
* **!UNLOCK** – Unprotects AMSTRAD programs.
* **!SPEED** – Fast save and load up to 4000 baud.
* **!HILITE** – Highlight any string in a program or listing.
* **!UDG** – On screen design of character set.
* **!FILL** – Very fast fill. Any shape, any colour.
* **!CIRCLE** – Fast circle drawing.
* **!SCREEN** – Switch between 2 separate screens at hardware speed.
* **!GETMAT** – Convert drawings etc. on screen into UDG's.

Plus 36 other commands (all the usual ones – !FRAME, !CAPS, etc).
Load and save UDG's CAT tape or disc to printer, Pause, etc, etc.
Includes comprehensive manual and demonstration program.

TAPE £7.95 SAE for more details or CHEQUES/P.O.'s payable to: **DISC £11.45**

SOFT MACHINE, 68 Vicars Hill, London SE13 7JL

POOLSWINNER

THE ULTIMATE POOLS PREDICTION PROGRAM



Boxed, with detailed instruction booklet

- **MASSIVE DATABASE** Poolswinner is a sophisticated Pools prediction aid. It comes complete with the largest database available – 22000 matches over 10 years. The database updates automatically as results come in.
- **PREDICTS** Not just SCOREDRAWS, but AWAYS, HOMES and NO SCORES.
- **SUCCESSFUL** SELEC guarantee that Poolswinner performs significantly better than chance.
- **ADAPTABLE** Probabilities are given on every fixture – choose as many selections as you need for your bet. The precise prediction formula can be set by the user – you can develop and test your own unique method.
- **SIMPLE DATA ENTRY** All team names are in the program. Simply type in the reference numbers from the screen. Or use FIXGEN to produce fixture list automatically (see below).
- **DISC/MICRODRIVE COMPATIBLE** Tapes supplied with conversion instructions.
- **PRINTER SUPPORT** Full hard copy printout of data if you have a printer.

AVAILABLE FOR Spectrum (48K), Commodore 64, VIC 20 (+16K), AMSTRAD, BBC B, Atari (48K), ZX81 (16K), Dragon, Apple II, ELECTRON

PRICE £15.00 (all inclusive)

NOW AVAILABLE

FIXGEN 85/6

AT LAST: No more struggling for hours to get the fixture list into the computer. FIXGEN has been programmed with all English and Scottish fixtures for 1985/6. Simply type in the date, and the full fixture list is generated in seconds. Fully compatible with Poolswinner.

POOLSWINNER with FIXGEN £16.50 (all inclusive)



COURSEWINNER V3

THE PUNTERS COMPUTER PROGRAM

NOT JUST A TIPSTER PROGRAM, Coursewinner V3 can be used by experts and occasional punters alike.

You can develop and test your own unique winning system by adjusting the analysis formula, or use the program in simple mode. Coursewinner V3 uses statistical analysis of major factors including past form, speed ratings, course statistics, prize money, weight, going, trainer and jockey form etc, etc. It outputs most likely winners, good long odds bets, forecasts, tricasts etc. The database includes vital course statistics for all British courses. You can update the database – never goes out of date.

AVAILABLE FOR Spectrum (48K), Commodore 64, BBC (B), AMSTRAD, Atari (48K), Apple II

PRICE £15.00 (all inclusive) includes Flat AND National Hunt versions.

Send Cheques/POs for return of post service to . . .

VISA phone 24 hrs

selec SOFTWARE

phone 24 hrs

37 COUNCILLOR LANE, CHEADLE, CHESHIRE. ☎ 061-428 7425

(Send for full list of our software)

FULLY EXPANDABLE INTERFACE

FOR THE AMSTRAD 464/664/6128

- Dual RS 232 ● 4 Sideways ROM Sockets
- 8 Bit Printer Port ● 8 Bit User Port **£83.95**
- Through Expansion Socket ● Software on ROM

4 SIDEWAYS ROM SOCKETS UNIT with Through Expansion Socket	**£31.05**
3" Disc Box of 10	**£39.75**
SIMPLE ACCOUNTS-Book Keeping (Disc)	**£34.95**
PRO-ED/A Professional Text Editor (Disc)	**£35.00**

Write/Phone for further details:

PANDA ELECTRONICS LIMITED
64 Harding Way, Cambridge CB4 3RR
Telephone: (0223) 354887
All prices are inclusive of VAT and P&P

Dealers Enquiries Welcome

O. J. SOFTWARE

FAST FRIENDLY SERVICE

****** SPECIAL ORDER TWO OR MORE ITEMS AND DEDUCT AN EXTRA 50p PER ITEM ******

ADVENTURE		ARCADE		ARCADE	
RED MOON (664)	£5.95	WHO DARES WINS II (664)	£7.95	WORKING BACK DISC	£13.50
WARLORD (664)	£7.95	HYPERSPORTS (D)	£7.95	COMP HITS 6 DISC ONLY	£13.50
WORM PARADISE (664)	£8.95	GYROSCOPE (664)	£7.95	ELITE (664)	£12.95
ADRIAN MOLE (664)	£8.95	YIE AR KUNG FU (D)	£7.95	**BUS/UTILITIES**	
MARSPORT (D)	£8.95	FIGHTING WARRIOR (664)	£7.95	MINI OFFICE II (D)	£13.50
LORDS MIDNIGHT (D)	£8.95	STRANGELOOP (664)	£7.95	GRAPHIC ADV C'TOR (D)	£19.95
THE HOBBITT (664)	£12.95	T.L.L. (D)	£7.95	LAZER BASIC (D)	£12.95
LORD OF RINGS (664)	£13.95	HIGHWAY ENCOUNTER (D)	£7.95	TASWORD 464D/128	£21.45
STRATEGY/SIMULATION		FRANK BRUNOS (D)	£7.95	MASTERCALC 128	£29.50
BLOCKBUSTERS (664)	£6.95	SOLD A MILLION (D)	£8.95	MASTERFILE (D)	£21.95
MATCHPOINT (664)	£6.95	SPY V SPY (664)	£8.95	MUSIC SYSTEM (D)	£13.50
WORLD BASEBALL (664)	£7.95	BRUCE LEE (664)	£8.95	**ACCESSORIES**	
FIGHTER PILOT (D)	£7.95	3 WEEKS PARADISE (664)	£8.95	BLANK DISCS	£4.50
SPITFIRE 40 (664)	£8.95	RAID!!! (D)	£8.95	QUICKSHOT II JOYSTICK	£8.50
THEATRE EUROPE (664)	£8.95	WAY EXP FIST (664)	£8.95	PRINTER CABLE	£11.95
CYRUS II 3D CHESS (D)	£8.95	MACROCOSMICA (D)	£8.95	SURESHOT JOYSTICK	£14.95
3D GRAND PRIX (D)	£8.95	BATTLE PLANETS (664)	£8.95	ELEC STUDIO LIGHTPEN	£17.95
SCRABBLE/CLUEDO (D)	£8.95	SKYFOX (664)	£8.95	AMSTRAD SPEECH SYN	£27.95

Notes:- (D) = Disc version available (Tape price + £3.50): (664) = Runs 664/128
Most orders despatched by return (out of stock items usually within 1 week)
Cheques/PO's to O. J. SOFTWARE (Prices incl. U.K. p&p.)
273 MOSSY LEA ROAD, WRIGHTINGTON, WIGAN, LANCS. WN6 9RN.
Write or phone (0257) 421915 for FREE LIST and LATEST RELEASES
Overseas orders. Please add 50p Europe, £1.00 others, per item.

VISA

from a selective mailshot to a gardener's year

microfile

stores & retrieves information to your requirements

- Client records • Club Membership
- Music library • Stamp Catalogue
- Fixture lists • Supplier Index

£19.95 including VAT & Carriage (£24.95 on Disk)

CORNIX SOFTWARE LTD.

16 Kneesworth Street, Royston, Herts. SG8 5AA. Tel: Royston (0763) 852989

FAST reliable service of

DATA-DUPLICATION

for most computers. Comprehensive facilities include erasure/re-recording, blank discs/cassettes blank or printed labels/inlays.

COMPETITIVE PRICE LIST from:

SIMON STABLE PROMOTIONS
CASSETTE DUPLICATIONS

The Knightsbridge Stables, 20 West End, Launton, Oxon OX6 0DF. Tel: 086925 2831.

PL395

SOFT INSIGHT (DISCOUNT SOFTWARE)

ALL PRICES INCLUDE FREE FAST DELIVERY IN THE U.K. ONLY. PLEASE ADD 70P PER TAPE ON EUROPEAN ORDERS AND £1.00 PER TAPE ELSEWHERE.

New titles arriving every day, please ring for details

Access orders/enquiries tel: 01-305 0521.

AMSTRAD		
Colossal Adventure	9.95	7.20
Adventure Quest	9.95	7.20
Dungeon Adventure	9.95	7.20
Snowball	9.95	7.20
Lord of Time	9.95	7.20
Return to Eden	9.95	7.20
Emerald Isle	6.95	5.40
Red Moon	6.95	5.40
Grand Prix Rally 2	8.95	7.00
Bridge Player (C.P.)	9.95	7.40
Fighter Pilot	9.95	7.46
Sorcery	8.95	7.00
Football Manager	7.95	6.20
Alien 8	9.95	7.46
Knightlore	9.95	7.46
Dundarach	9.95	7.46
Way of the Exp Fist	9.95	7.46
Everyone's a Wally	9.95	7.46
World Ser. Baseball	8.95	6.71
Airwolf	8.95	6.71
Gremlins	9.95	7.46
Robin of Sherwood	9.95	7.46
Combat Lynx	8.95	7.00
Mac Bumper P'ball	7.95	5.96
Nodes of Yesod	9.95	7.46
Scrabble	9.95	7.46
*Monopoly	9.95	7.46
Lords of Midnight	9.95	7.46
*3D Grand Prix	9.95	7.46
Zaxxon	9.95	7.46
*Buck Rogers	9.95	7.46
*Congo Bongo	9.95	7.46
*Tapper	9.95	7.46
*Spyhunter	9.95	7.46
3D Boxing	9.95	7.46
Cyrus Chess	9.95	7.46
Wizards Lair	8.95	7.00
Highway Encounter	8.95	6.71
Trivia	7.95	6.20
Slapshot	8.95	6.71
The Devils Crown	9.99	7.50
Zoids	8.95	6.71
Bored of the Rings	6.95	5.20
Yie Ar Kung Fu	8.95	6.71
Raid	9.95	7.46
Hypersports	8.95	6.71
G. Capes Strong.	8.95	6.71
Boulderdash	9.95	7.46
Southern Belle	7.95	6.20
* Frankie G.T.H.	9.95	7.46
* Matchday	9.95	7.46
* Never End. Story	9.95	7.46
* Int. Basketball	8.95	6.71
Realm of Imposs.	9.95	7.46
Master of Lamps	9.95	7.46
Battle of Britain	9.95	7.46
World Ser. Baseball	8.95	6.71
Elite	14.95	11.21
Sabrewolf	9.95	7.46
Formula One	8.95	6.71
Maarsport	9.95	7.46
They Sold a Million	9.95	7.46
Cauldron	8.99	6.71
Dynamite Den	7.95	5.96
Adrian Mole	9.95	7.46
Nightshade	9.95	7.46
Sky Fox	9.95	7.46
Who Dares Wins 2	9.95	7.46
Commando	9.95	7.46
Worm in Paradise	9.95	7.46
Theatre Europe	9.95	7.46
Cleudo	9.95	7.46
Sweevo's World	7.95	6.20
Gyroscope	8.95	6.71
Strangeloop	8.95	6.71
Supertest	8.95	6.71
Lord of th Rings	15.95	12.00
Computer Hits 10	14.95	11.50
Bomb Jack	8.95	6.71
Comic Bakery	8.95	6.71
Ping Pong	8.95	6.71
Mikie	8.95	6.71
The Music System	14.95	12.00
Think	8.95	6.71
Match Point	8.95	6.71
Here & There with the Mistermen	8.95	7.50
First Steps with the Mistermen	8.95	7.50
Winter Games	9.95	7.46
Contraption	8.95	6.71
Rescue from Fractalus	9.95	7.46
Spin Dizzy	9.95	7.46
Commando	9.95	7.46
Fair Light	9.95	7.46
Rambo	9.95	7.46
Spy v Spy	9.95	7.46
3 Weeks in Paradise	9.95	7.46
Battle of the Planets	9.95	7.46
Runestone	7.95	6.20
Back to the Future	9.95	7.46
Critical Mass	8.95	6.71
Saboteur	8.95	6.71
Turbo Esprit	8.95	6.71
Forbidden Planet	8.95	6.71
2112 AD	8.95	6.71
Spitfire 40	9.95	7.46
Tau Ceti	9.95	7.46
Lazer Basic	14.95	11.95
Lazer Compiler	19.95	15.95
Doors of Doom	9.95	7.46
Mini Office II	14.95	11.95

DISC BASED SOFTWARE		
Masterfile	29.95	24.95
Mastercalc	29.95	24.95
Graphic Adv. C'tor	24.95	19.95
Sold a Million	14.95	11.50
Computer Hits 6	14.95	11.50
Dun Darach	14.95	11.50
Marrsport	14.95	11.50
Battle of Britain	14.95	11.50
Scrabble	14.95	11.50
Theatre Europe	14.95	11.50
Spy Vs Spy	14.95	11.50
Fighter Pilot	14.95	11.50
Cyrus II Chess	13.95	11.50
3D Grand Prix	13.95	11.50
Raid	13.95	11.50

8256 SOFTWARE		
SuperCalc 2	49.95	44.95
Doctorgraph	49.95	44.95
Doctordraw	49.95	44.95
Hitch Hikers Guide to the Galaxy	24.95	22.95
Zork 1	19.95	17.95
Seastalker	19.95	17.95
Planet Fall	19.95	17.95
Deadline	19.95	17.95

DENOTES NEW TITLES THAT ARE AVAILABLE IN THE NEAR FUTURE. PLEASE RING FOR CONFIRMATION.

WHY NOT COME AND PICK UP YOUR SOFTWARE PERSONALLY FROM OUR DISCOUNT SHOP AT 3 STATION CRESCENT, WESTCOMBE PARK, BLACKHEATH, LONDON SE3 7ER. RIGHT OUTSIDE WESTCOMBE PARK RAILWAY STATION ON THE SOUTHERN REGION. OPEN ON SATURDAYS ONLY FROM 10.30 'TIL 6.00PM.

3 STATION CRESCENT WESTCOMBE PARK BLACKHEATH SE3 7ER.

SCHOOL SOFTWARE LTD.

Meadowvale Estate, Raheen, Limerick, Ireland.
Telephone: (061) 27994, (U.K.) 010—353—61—27994.

EXAM REVISION



MAGIC MATHS (Age 4-8)
A superb arcade style game which holds the attention of children. Learn addition and subtraction while trying to drive a train at 100 m.p.h.

MATHS MANIA (Age 8-12)
This program has the extraordinary effect of making multiplication and division addictive. Maths will never be the same again. An excellent program.

BETTER MATHS 1 (Age 12-16)
Covers a very wide range of popular sections of maths at this level. Contents: Approximation measuration, simple interest, factors, percentages, simple calculations, algebraic factors, sequences and series, tests. The program includes essential formulae. Excellent graphics.

BETTER SPELLING (Age 9-14)
An exciting new way to improve your spelling, this courseware package concentrates on all the key areas of English spelling. Real value for money with up to 16 menu options. Prepared by an English language author.

PHYSICS 1 (Age 12-16) CSE/O LEVEL
An outstanding program which makes excellent use of graphics. Contents: 1. Matter/Density. 2. Law of the Lever. 3. Pressure. 4. States of Matter A. 5. States of Matter B. 6. Heat/Temperature. 7. Current Electricity. 8. Magnetism-Electrostatics. 9. Light/Sound.

BIOLOGY 1 (Age 12-16) CSE/O-Level
This program gives key definitions and promotes interactive learning through the question and answer sessions. Contents: 1. Life & Cells. 2. Mammals & Plants. 3. Photosynthesis and Enzymes. 4. Respiration/Excretion. 5. Transport. 6. Sensitivity. 7. Reproduction. 8. Cycles and Micro-organisms.

CHEMISTRY 1 (Age 12-16) CSE/O-Level
A wide ranging basic course in chemistry. Ideal for first examinations. Contents: 1. Chemical Changes. 2. Oxygen/Hydrogen A. 3. Oxygen/Hydrogen B. 4. Atoms. 5. Carbon/Sulphur. 6. Oxidation/Reduction. 7. Acids/Bases. 8. Ion exchange/Water.

WEATHER/CLIMATE (Age 12-17)
This program uses the multiple choice format for an in depth analysis of this topic. Topics: Weather observation, Instruments, Pressure, Wind, Temperatures, Climates.

Cassettes £9.95 each
Discs £12.95 each

48 hour MAIL ORDER

CPC 464/664/6128/
PCW 8256 (April release)

DUST COVER SETS

Amstrad PCW8256 £11.95 per set

In pale grey-proofed nylon, treated with an anti-static inhibitor, MONITOR & PRINTER covers piped in green.
Name hot foil printed on KEYBOARD cover.

Amstrad CPC 6128/464/664 £7.00 per set


Matching dark grey proofed nylon, treated with anti-static inhibitor, MONITOR cover piped in GREEN for 464, in BLUE for 664 and RED for 6128.

Popular Printer Covers to match above

AMSTRAD DMP2000 BROTHER M1009 CANON PW1080A, EPSON FX80, RX80, LX80, MANNESMAN MT80, SHINWA CPA80, TAXAN P810 ALL £4.50

Prices inc. postage in UK, overseas customers please add Europe 50p, others £2.00 (air-mail), please state model and colour or monochrome.

BBD COMPUTER DUST COVERS
39 Manse Avenue, Wrightington WN6 9RP
Telephone: 0257 42296



This means YOU!

Imagine a program listing. A listing for an amazing action game, about 3k or 4k long. Mostly it is written in Basic but it might have a few machine code routines to do some of the things that need speed. It works on the 464 (with or without disc drive), 664 and 6128. It might run (using Mallard Basic) on the PCW8256. Did I hear you say you have one right here in your pocket? I did? Hand it over. We want to print it!

Yes, that's right, we want lots of shortish programs for our readers to type in. They don't have to be games – we just have a preference for them. They can be anything that we find interesting. The things we don't find interesting are biorythm programs, pools predictors, simple databases, or anything to do with quadratic equations – unless they are written in one line, cellotaped to half a million quid or draw a pretty picture on the screen.

There are a few golden rules for submitting programs. Remember that you are writing a program for publication. Make your program easy to debug. Don't include unlistable characters in the program. Document start addresses and length of code when using machine code. Send the program on tape or cassette and include a SAE if you want it back. If you think the program does something particularly clever, write an explanation of the routine that does it. Don't include commands that work only on one particular machine.

Now you know what to do, get cracking! Send off your program today to:

LIZ TING

Liz Ting
Amstrad Computer User
169 Kings Road
Brentwood CM14 4EF

SHEKHANA COMPUTER SERVICES

	RRP	Our Price		RRP	Our Price
Elite	14.95	12.95	Spy v Spy (disk)	14.95	12.95
Elite (disk)	17.95	15.95	Spy v Spy	9.95	7.50
Bomb Jack	8.95	6.75	Critical Mass	8.95	6.75
Marsport	9.95	7.50	Sabotor	8.95	6.75
Frank Brunos Boxing	8.95	6.75	Turbo Esprit	8.95	6.75
Spitfire 40	9.95	7.50	Grand Prix Rally 2	8.95	6.95
Commando	9.95	7.50	Lords of Midnight (disk)	13.95	11.95
B. McGuigans Boxing	9.95	7.50	*Star Quake	8.95	7.50
Winter Sports	9.95	7.95	Swords and Sorcery	9.95	7.95
Boulder Dash	9.95	7.50	Azimuth (Head Aligment)	8.95	7.50
Fighter Pilot	8.95	6.95	3D Grand Prix (disc)	13.95	11.95
Tornado Low Level (disk)	13.95	11.95	Rock & Wrestle	8.95	7.50
Matchpoint	9.95	7.50	Theatre Europe	9.95	7.95
The Hobbit	14.95	11.95	Bounder	9.95	7.95
Sweevos World	7.95	5.95	Mastercalc	24.95	22.50
3D Voice Chess	12.95	10.95	Hitchhikers Guide to Galaxy		24.95
Night Shades	9.95	7.50	Zork I		19.95
Rambo	8.95	6.75	Deadline		19.95
Lord of The Rings	15.95	12.95	Seastalker		19.95
Southern Belle	8.95	6.95	Planetfall		19.95
Skyfox	9.95	7.50	Tornado Low Level	7.95	5.95
Sorcery	8.95	6.95	Highway Encounter	8.95	6.95
Alien 8	9.95	7.50	Nick Faldo's Golf	9.95	8.50
Beach Head II	9.95	7.50	Glass	9.95	7.95
Arnehem	9.95	7.95	3D Stunt Rider	8.95	7.50
Goonies	9.95	7.50	Raid Over Moscow (disk)	13.95	11.95
Impossible Mission	9.95	7.95	Worm In Paradise	9.95	7.50
Winter Games	9.95	7.50	3D Grand Prix	9.95	7.50
Superbowl	9.95	7.50	Roller Coaster	8.95	6.75
Single 3 inch Disk		4.95	Diary of Adrian Mole	9.99	7.50
Masterfile	24.95	22.50	3D Cyruss II Chess (disk)	13.95	11.95
Yie Ar Kung Fu	8.95	6.75	The Electric Studio Pen	19.95	17.95
Mini Office	5.95	4.99	Bridge Player 3	12.95	10.95
Scrabble	9.95	7.50	Quickshot II-Joystick	12.95	8.99
Lords of Midnight	8.95	7.25	3D Cyruss II Chess	9.95	7.95
Sorcery + (disk)	13.95	11.95	Monopoly	9.95	7.95
Mini Office II	14.95	12.95	Colossus Chess 4.0	9.95	7.95
Mini Office II (disk)	19.95	17.50	3 Weeks in Paradise	9.95	7.50
Fighter Pilot (disk)	12.95	10.95	Battle of the Planets	9.95	7.50
Yabba Dabba Doo	8.95	7.50	Think	8.95	6.95
They Sold A Million	9.95	7.50	Comic Bakery	8.95	6.75
Lazer Basic	14.95	12.95	Friday 13th	8.95	6.75
Way of Exploding Fist	9.95	7.50	Obsidian	8.95	6.75
Way of the Tiger	9.95	7.95	Sir Fred	9.95	7.50
Desert Rats	9.95	7.50	Raid	9.95	4.99

For Mail Order Please send Cheques/P.O. To:
SCS (DEPT AMUS), P.O. BOX 394 LONDON N15 6JL.
(P&P INCLUDED IN UK). EUROPE ADD £1.00 PER TAPE.
ELSEWHERE AT COST. Tel: 01-800 3156. S.A.E. FOR LIST
If you would like to pick up your discount software please bring your copy of this advert to **Compucentre**, **Unit 5, 221 Tottenham Court Road, London W1 (near Goodge St. Tube Station)**.
Open 6 days a week from 10am-6pm.
Access and Visa Card Hot Line please ring: 01-631 4627
Credit Card Orders despatched same day – subject to availability
* Please ring to confirm availability

LANGUAGE TOOLS FOR CP/M

Turbo Pascal 3.0 (inc. editor & OVERLAYS)	69.95
Turbo Toolbox 1.2 (ISAM database tools)	54.95
Turbo-Amstrad Interface (Turbo to Firmware interface for windows, Turtlegraphics, sound, etc)	14.95**
Turbo Tutor	35.95
Pro-Pascal (ISO standard compiler)	85.95*
DR Pascal/MT+	49.95*
DR CBASIC Compiler	49.95*
Tool works C/80 (C compiler	£69.95*
Math Pack (Floats and longs for C/80)	£46.95*
Tool works Lisp/80 (Lisp interpreter)	£69.95*
Micro-Prolog (Interpreter & tutorial)	£79.95*
Modula-2 Compiler	Enquire

APPLICATIONS SOFTWARE FOR CPC6128 & PCW8256

AT LAST a versatile and friendly database program that doesn't cost an arm and a leg and doesn't require you to learn a new language

Varied Field Types/Menu-driven/Form & Report Designer/Field Totals/Multiple Keys/Up to 10 files (cross-referencing)

When you're fed up struggling with inadequate tools, you need AT LAST

At Last	49.95*
DR Graph	49.95*
DR Draw	49.95*
SuperCalc 2	49.95*
Sage Popular Accounts	99.95*
Sage Payroll	69.99*
Sage Combo Pack (Accounts & Payroll)	149.99*
Sage Chit-Chat E-Mail (Electronic mail)	£69.99*
Sage Chit-Chat View Data (Prestel etc)	£69.99*
Sage Chit-Chat Combo (E-Mail & View Data)	£99.99*
Sage Database	£69.99*
Ian Key Crash Course (Typing tutor)	£24.95*
Ian Key Two Fingers (Touch typing conversion course)	£24.95*
Brainstorm (ideas Processor)	49.99*
Touch 'n' go (keyboard trainer)	24.99*
Cardbox (Electronic card index)	99.99*
Smart Key (Keyboard enhancer)	49.99*
Scratchpad (spreadsheet) + Smart Key	69.99*
Any other CP/M program, disc transfers, computers, printers, expansion, manuals	S.A.E.

**CP/M Plus only* ***Not PCW8256*

CONSULTANCY 15.00/hour + VAT

VAT and P&P (Europe) included. Please state model when ordering.
All payments in Sterling drawn on a UK account.
Callers please ring first.

RATIONAL SOLUTIONS
9 ROSEHILL ROAD LONDON SW18 2NY **TEL:01 874 6244**

PERSONAL COMPUTER PRINTER

AMSTRAD 464, 664, 6128



- Quiet Thermal Operation
- RS 232C (can be supplied)
- 80 column
- 8" x 30m paper roll supplied
- 12 months warranty
- Famous manufacturer
- No interface required for Amstrad
- Connects direct to computer.

VISA

Access

(DIXONS ADVERTISED PRICE IS £139.99)

£89 (incl P&P & VAT)
(TRADE ENQUIRIES WELCOME)

- STOP PRESS
  AMSTRAD PCW8256 TELEX CONVERSION £199
  (Includes Modem, Interface, Software, Leads etc).

Robert Edwards & Co (Ref ACU)
236 North Road, Hertford, Hertfordshire SG14 2PW.
Tel: (0992) 54118 (4 lines). **Telex: 946240 CWEASY G Ref: 19007710**
ACCESS/BARCLAYCARD VISA ACCEPTED



What it offers the Amstrad user . . .

Electronic mail is much cheaper than the post

Sending mailbox messages to other subscribers, whose numbers are rapidly growing, is the cheapest form of communication possible. You can send a message of any length to another mailbox for less than the cost of a first-class stamp. And it doesn't cost a penny more to send the same message to 500 different mailboxes! Even a message sent to a mailbox on the other side of the world only costs 30p.

The biggest bulletin board of them all

The number of bulletin boards is growing rapidly. The only snag is that the vast majority are single-user boards – which means lots of other people are also trying to make contact and all too often all you get is the engaged tone. But with the MicroLink bulletin board there is no limit to the number of people using it at the same time. And no limit to the number of categories that can be displayed on the board.

Give your micro mainframe power

With MicroLink your micro becomes a terminal linked directly to the Telecom Gold mainframe computer, and able to tap its tremendous power and versatility. Right away you'll be able to use giant number-crunching programs that can only run on a mainframe.

The mailbox that is always open

MicroLink is in operation 24 hours a day, every day. That means you can access your mailbox whenever you want, and from wherever you are . . . home, office, airport – even a hotel bedroom or golf club! No-one needs to know where you are when you send your message.

We're only a local phone call away

The majority of MicroLink subscribers can connect to our mainframe computer in London by making a local phone call. This is possible because they use British Telecom's PSS system, which has access points all over Britain. A local phone call is all you need, too, for direct access via MicroLink to all the other countries belonging to the international Dialcom system.

Telemessages – at a third off

The modern equivalent of the telegram is the telemessage. Send it before 10pm and delivery is guaranteed by first post the following day (except Sunday). The service was intended for people phoning their message to the operator, which costs £3.50 for 50 words. But you can now use it via MicroLink, for only £1.25 for up to 350 words! For an extra 65p your message can be delivered in an attractive greetings card.

Go teleshopping on your micro

With MicroLink you can study the British Rail timetable – and then buy your ticket in advance. You can book theatre tickets. And even order a bouquet of flowers. It's all part of the tele-shopping revolution!

Send and receive telex messages

With MicroLink you can turn your micro into a telex machine, and can send and receive telex messages of any length. You will be able to communicate directly to 96,000 telex subscribers in the UK, 1½ million worldwide – and even with ships at sea via the telex satellite network. Business people can now send and receive telexes after office hours, from home or when travelling.

What does it all cost?

Considering all the services you have on tap, MicroLink is remarkably inexpensive. You pay a once-only registration fee of £5, and then a standing charge of just £3 a month. On-line costs are 3.5p a minute (between 7pm and 8am) or 11p a minute during office hours. There is an additional 2.5p a minute PSS charge if you are calling from outside the 01- London call area. Charges for telex, telemessages and storage of files are given on the next page.

How much it costs to use MicroLink

Initial registration fee: £5.

Standing charge: £3 per calendar month or part.

Connect charge: 3.5p per minute or part – cheap rate; 11p per minute or part – standard rate.
Applicable for duration of connection to the Service. Minimum charge: 1 minute.
Cheap rate is from 7pm to 8am, Monday to Friday, all day Saturday and Sunday and public holidays; Standard rate is from 8am to 7pm, Monday to Friday, excluding public holidays.

Filing charge: 20p per unit of 2,048 characters per month.
Applicable for storage of information, such as telex, short codes and mail files. The number of units used is an average calculated by reference to a daily sample.

Information Databases: Various charges.
Any charges that may be applicable are shown to you before you obtain access to the database.

MicroLink PSS service: 2.5p per minute or part (300 baud); 3p per minute or part (1200/75 baud).
Only applies to users outside the 01-London call area.

Telex registration: £10.

Outgoing telex: 5.5p per 100 characters (UK); 11p per 100 (Europe); 18p per 100 (N. America); £1.25 per 400 (Rest of world); £2.75 per 400 (Ships at sea).
Deferred messages sent on the night service are subject to a 10 per cent discount.

Incoming telex: 50p for each correctly addressed telex delivered to your mailbox. Obtaining a mailbox reference from the sender incurs a further charge of 50p.
It is not possible to deliver a telex without a mailbox reference. If a telex is received without a mailbox reference the sender will be advised of non-delivery and asked to provide a mailbox address.
Each user validated for telex and using the facility will incur a charge of 6 storage units a month. Further storage charges could be incurred depending on the amount of telex storage and the use made of short code and message file facilities.

Telemessages: £1.25 for up to 350 words.
Telemessages can be sent with an illustrated greetings card for 65p extra.

Radiopaging: No charge.
If you have a BT Radiopager you can be paged automatically whenever a message is waiting in your mailbox.

International Mail: For the first 2,048 characters – 20p to Germany and Denmark; 30p to USA, Australia, Canada, Singapore, Hong Kong and Israel. For additional 1,024 characters – 10p; 15p.
These charges relate to the transmission of information by the Dialcom service to other Dialcom services outside the UK and the Isle of Man. Multiple copies to addresses on the same system host incur only one transmission charge.

Billing and Payment: All charges quoted are exclusive of VAT. Currently all bills are rendered monthly.

Software over the telephone

MicroLink is setting up a central store of software programs which you'll be able to download directly into your micro. The range will include games, utilities, educational and business programs, and will cover all the most popular makes of micros.

Talk to the world – by satellite

MicroLink is part of the international Dialcom network. In the USA, Australia and a growing number of other countries there are many thousands of users with electronic mailboxes just like yours. You can contact them just as easily as you do users in Britain – the only difference is that the messages from your keyboard go speeding around the world via satellite.

What you need to access MicroLink

You must have three things in order to use MicroLink: a computer (it can be any make of micro, hand-held device or even an electronic typewriter provided it has communications facilities), a modem (it can be a simple Prestel type using 1200/75 baud, or a more sophisticated one operating at 300/300 or 1200/1200 baud), and appropriate communications software.

MicroLink

in association with

TELECOM GOLD *

Application Form

I/We hereby apply to join MicroLink

(✓) ☐ I enclose my cheque for £5 payable to Database Publications as registration fee to MicroLink.

(✓) ☐ I also wish to use Telex. I authorise you to charge an additional £10 to my initial bill for validation.

☐ I confirm that I am over 18 years of age.

☑ I confirm that I accept the terms and conditions for the time being in force, a copy of which are available on request.

Signature _____

Date _____

FOR OFFICE USE ONLY:

Mailbox assigned _____

Start date _____

Password _____

CWA 4

SEND TO:
MicroLink
Database Publications
Europa House
68 Chester Road
Hazel Grove
Stockport SK7 5NY.

* *Telecom Gold is a trademark of British Telecommunications plc.*

Name

Position

Company

Address

Postcode Daytime telephone

Commencement of Service
Please indicate month of commencement ☐☐ 19☐☐
Allow 10 days for validation of mailbox

Payment
Whilst Database Publications Ltd is the supplier of all the services to you, the commission and billing thereof will be handled by Telecom Gold as agents for Database Publications Ltd.
Date of first payment to be on 15th of month following commencement.
Please complete billing authorisation form A, B or C below:

A. Direct Debiting Mandate *(Enter full postal address of Bank Branch)*
To

I/We authorise you until further notice in writing to charge to my/our account with you on or immediately after 15th day of each month unspecified amounts which may be debited thereto at the instance of British Telecommunications plc – TELECOM GOLD by Direct Debit. Bills are issued 10 days before debit is processed.

Name of Account to be debited

Account Number

B. Please debit my/our Access/Visa/*American Express account number
** Overseas subscribers only*

I/We authorise you until further notice in writing to charge to my/our account with you on or immediately after 15th day of each month unspecified amounts which may be debited thereto at the instance of British Telecommunications plc – TELECOM GOLD. Bills are issued 10 days before charge is applied to your account.

Signature _____ Date _____

C. Please invoice the company/authority.

(✓) ☐ If you select this option, which is ONLY AVAILABLE to government establishments and Public Limited Companies, you will be sent an authorisation form for completion which will require an official order number to accept unspecified amounts.

Lightwave



TREAT YOUR COMPUTER TO HIGH QUALITY, WEST GERMANY CABLES AND ACCESSORIES.

"THE STICK" JOYSTICK	*464/664/6128*	*£12.99*
PRINTER CABLE (2M)	*464/664/6128*	*£13.95*
EXT. MONITOR CABLES (2M)	*464*	*£5.05*
EXT. MONITOR CABLES (2M)	*664/6128*	*£6.75*
STEREO CABLE 2 x PHONO (2M)	*464/664/6128*	*£4.15*
STEREO CABLE 5-PIN DIN (2M)	*464/664/6128*	*£4.15*
JOYSTICK EXT. CABLE 9-PIN D TYPE (2M)		*£3.25*
JOYSTICK ADAPTOR	*464/664/6128*	*£4.55*

DUST COVERS

KEYBOARD	*464*	*£5.95*
MONITOR GREEN	*464/664/6128*	*£8.95*
MONITOR COLOUR	*464/664/6128*	*£8.95*
DISC DRIVE DDI-1, FD-1	*464/664/6128*	*£4.95*
PRINTER NLQ 401		*£5.95*
KEYBOARD	*664*	*£7.35*
KEYBOARD	*6128*	*£7.35*

SUPERB ANTI-GLARE SCREENS COLOUR/ MONO, 12" + 14" FROM £18.95

ASK YOUR LOCAL DEALER OR SEND DIRECT.

PLEASE ADD £1.00 FOR P + P CHEQUES AND P.O.s TO:

LIGHTWAVE LEISURE LTD
DEPT AU4. P.O. BOX 23
WALLASEY, MERSEYSIDE L44 1EW
051-639 5050

MICROPOWER

YORKSHIRE'S LEADING AMSTRAD SPECIALIST

COMPUTERS PCW 8256 Word Processing Package incl. computer, disc drive and printer. **£458.85**
2nd Disc Drive **£182.85**
Parallel/Serial Interface **£67.85**
CPC 6128 with 128K memory, 3" drive and colour monitor . . **£399.00**
With green screen monitor **£299.00**
CPC 464 with 64K memory, built-in cassette and colour monitor **£299.00**
With green screen monitor **£199.00**
2nd Disc Drive (6128/664/464) **£99.95**
1st Disc Drive (464) **£159.95**

PRINTERS Epson LX80, Amstrad DP 2000, Samleco DX86, Citizen 120D, Juki 6000, Juki 6100, NEC etc.

ACCESSORIES — Speech Synthesis, Light Pens, RS232, TV Modulators, AMX Mouse, Dust Covers, Leads, Printer Ribbons, Paper (ask for details).

SUPERPOWER New Rom-Card (6128/664/464) **£34.95**
Assembler, Disassembler, Monitor (Disc or Roms) **£29.95**
Disc Users Utilities, Programmer's Toolbox & Basic Extensions, Mailing List (Disc or Rom) . . . . . each **£19.95**
(please state computer model).

SOFTWARE — Sagesoft, Delta Database, Supercalc, Amsoft Business Control. Large selection of Games.

SHOWROOM/MAIL ORDER
MICRO POWER LTD.,
Northwood House, North Street,
Leeds LS7 2AA.
Tel. 0532 458800/434006

ACCESS/VISA Welcome. Postage/carriage — small items 95p/total order; Computers/printers etc. £5.00 per item in UK. Eire/Channel Islands/Export at cost.



DISCOUNT SOFTWARE

CHECK OUT THESE PRICES

GAMES		BUSINESS & TUTORIAL		DISC BASED	
Elite	12.95	Guide to Basic 1 & 2	16.95	Wriggler	9.95
Commando	7.50	Concise Basic Spec	10.95	Alex Higgins Pool	10.50
Spitfire 40	7.50	Concise Firmware Spec	16.50	Steve Davis Snooker	10.95
Skyfox	7.50	Concise Firmware DDI	8.75	3D Grand Prix	11.25
Hypersports	6.95	Masterfile	20.95	Sorcery +	11.50
Yie Ar Kung Fu	6.75	Masterfile Ext (MPX)	8.75	Tornado Low Level	11.50
Nightshade	7.50	Mastercalc	16.95	Lords of Midnite	11.50
Strangeloop	6.95	Mastercalc Ext (MCX)	8.75	Screen Designer	16.25
Theatre Europe	7.75	Tasword 464	15.95	Devpac Ass/Diss	24.95
Battle of Britain	7.75	Tascopy	8.95	Hisoft 'C' Compiler	34.95
Lord of the Rings	12.95	Tasprint	8.95	Font 64	11.25
Matchday	7.25	Hisoft 'C' Compiler	30.50	The Knife	11.25
Battle of the Planets	7.25	Devpac Ass/Diss	20.95	The Torch	11.25
Starion	7.75	Pascal (Hisoft)	25.95	Rembrandt	14.75
Bruce Lee	7.95	Font 64	7.25	Tasword 6128	19.95
American Football	7.95	Screen Designer	10.95	Tasprint	10.95
Hacker	7.75	Mini Office II	12.95	Tascopy	10.95
Match Point	6.75	Pitman Typing Tutor	7.95	Taspell	13.75
Steve Davis Snooker	6.25			Masterfile	23.95
Daley Ts Supertest	6.95	**HARDWARE**		Masterfile Ext	12.75
Quiz Quest	4.25	MP2 Modulator	27.50	Mastercalc	23.95
Arabian Nights	4.25	CL1 Cassette Lead	3.50	Mastercalc Ext	12.75
War Lord	4.25	PL1 Printer Lead	7.95	Mastercalc 128	31.95
Message from Andromeda	3.95	DMP2000 Ribbon	5.95	Mini Office II	17.50
Heroes of Karn	3.95	Quickshot II	8.95		
Chopper Squad	3.95	JY2 Joystick	9.95	**CP/M SOFTWARE**	
Willow Pattern	3.50	Single Disc (hard case)	4.25	Devpac 80 (Hisoft)	35.95
Chimera	3.50	Box 10 Discs (hard case)	38.50	Pascal 80 (Hisoft)	35.95
Noterraqueous	1.95	DK Tronics Light Pen – ROM	26.95	Sage Popular Accs	89.95
Formular 1 Simulator	1.95	DK Tronics 64k expansion	45.95	Supercalc 2	44.95

Arnor	Cass	Disc	Eprom	AD2 Cartridge
MAXAM (machine code ass/dis)	17.75	22.95	34.95	44.95
PROTEXT (word processor)	17.75	22.95	34.95	44.95
UTOPIA (utility rom)	—	—	25.75	36.50
PROSPELL (spelling checker)	—	22.95	31.95	—
4 WAY ROM CARD	—	—	13.95	—
664 CONNECTOR	—	—	5.00	—

ALL PRICES INCLUDE POSTAGE, PACKING & VAT IN THE UK
OVERSEAS ORDERS WELCOME – PLEASE WRITE FOR EXPORT PRICES
WRITE FOR A FREE PRICE LIST – GET ON OUR MAILING LIST
PLEASE SEND CHEQUES/POs TO:

M.J.C. SUPPLIES,
'Scoja', London Road, Hitchin, Herts SG4 9EN.
Tel: (0462) 32897 for Enquiries/Orders – 24hr ANSWERPHONE

GREATEST AMSTRAD SALE EVER

Software list includes			
Super Pipeline	2.95	Gems of Stradus	2.95
Alien Break In	2.95	Crazy Golf	2.95
Punchy	2.95	Codename Mat II	3.95
Haunted Hedges	2.95	Harrier Attac	3.95
Manic Miner	3.95	Mutant Monty	3.49
Mr Wongs Loopy Laundry	2.95	View to Kill	3.95
Astro Attack	2.95	Forest at Worlds End	3.45
Classic Adventure	3.45	Heroes of Karn	3.45
Codename Mat	2.95	Jewels of Babylon	3.45
Laserwarp	2.95	Fantastic Voyage	3.45
Splat	2.95	Tripods	4.95
3D Invaders	2.95	Alien	4.95
Hunter Killer	3.95	Gremlins	4.95
Snooker	2.95	Bounty Bob	5.50
Chuckie Egg	3.95	Fu Kung in Las Vegas	4.95
Master Chess	2.95	Alex Higgins World Pool	4.95
Roland Goes Digging	2.95	Alex Higgins Snooker	4.95
Electro Freddie	2.95	Beach Head	4.95
Star Commando	2.95	Centre Court	5.50
Spannerman	2.95	Steve Davis Snooker	6.95
American Football	4.95	Home Budget	9.95
Stockmarket	3.95	Raid	5.50
Amsgolf	2.95	Ship of Doom	4.95
Space Hawks	2.95	Espionage Island	4.95
Blagger	3.45	Inca Curse	4.95
Message from Andromeda	3.45	Planet of Death	4.95
Jet Boot Jack	2.95	3" Discs	4.50 each
Chopper Squad	3.45	Quick Shot II Joysticks	7.95
Hunchback	3.45	5 pin din leads to 3 jack plug leads for Amstrad 6128	3.95
Cub It	2.95		

Plus full range of disc & cassette based software available.
Please ring for a quote.
When ordering please state, machine, software ordered and price.

MAIL ORDER OFFER ONLY
Tel: (0733) 313870
24 hours
LOGIC SALES LTD.
Unit 6, Midgate, Peterborough,
Cambridgeshire PE1 1TN.

INVOICE MANAGER

CPC 464/664/6128

* Auto or manual numbering.
* Up to 100 Customer product file.
* Easy to use – full menu driven.
* Calculates VAT – discount automatically.
* Compatible with stock control program – available late March.
* Includes label printer.

Disk £19.95 Cassette £16.95 (inc)

COX SOFTWARE, The Bungalow, School Road, Salford Priors, Nr. Evesham, Warwickshire WR11 5XD
Tel: (0789) 773022

ASTROLOGY for beginners

Teach yourself astrology using your Amstrad

A Starter Pack comprising a simple program to calculate a horoscope, an introductory booklet and 2 self-teaching programs (how to interpret the horoscope)

£11.50 cassette £15.50 disc
No previous knowledge required

Also many other programs for more experienced astrologers

Please send the Astrology Starter Pack for my Amstrad 464/664/6128/8256. I enclose a cheque/PO, U.K. for £11.50/£15.50 (inc p&p). Outside UK add 50p; or, I enclose a large sae for free catalogue.

Name .....

Address .....

ASTROCALC (Dept A) 67 Peascroft Road
Hemel Hempstead, Herts HP3 8ER Tel: 0442 51809

Micro-Aid

Software:	CASHBOOK Double Entry bookkeeping		£14.95
	MAILING 250 names/addresses for label printing		£14.95
	PAYROLL full system with 1, 2 & 4 weekly & monthly, contracted in and out, 3 overtime etc. etc.		£49.95
*****	SPECIAL OFFER (Last THREE programs on one disc)		£55.00
	Pocket Wordstar famous CP/M Wordprocessor		£109.00
	Pocket Calcstar		£47.50
Printers:	CPA-80 Plus NLQ 100cps Friction & Tractor		£189.95
	CPA-80 cartridge printer ribbon		£5.50
	Epson LX-80 100cps NLQ Friction & Tractor		£269.00
	IBICO LTR-1 Letter Quality Friction		£113.85
Printer Cable suitable for Amstrad to Centronics			£7.95
Disc Drive (2nd) with power supply for CPC machines			£87.95
Discs:	3" Double sided	each	£3.95
	3" Double sided	box of 10	£35.95
Cassettes: C15 boxed in 5's, leaderless,		10 for	£2.50
Listing Paper Box 2,000 sheets 11" x 9.5"			£14.95
Labels for Mailing. 1,000 3 across 2.75" x 1.4375"			£6.50

Prices include VAT. Add 50p for Postage & Packing.

Micro-Aid (Amstrad),
25 Fore Street, Praze, Camborne, Cornwall. TR14 0JX or Telephone 0209-831274 with ACCESS or PRESTEL *2582020

FORECASTING

Full professional quality software with carefully written manual of 56 big pages – more a course in the subject!

WHAT DO YOU NEED TO PREDICT: Sales, finance, workload, demand, prices, competition?

WHAT DO YOU NEED TO ANALYSE: Relationship between social data and transport demand, between time and various dimensions?

Each decision you make means a number of assumptions about the future, take advantage of your Amstrad's power to analyse and predict using:

Polynomial regression, Trend and seasonal variations, Stepwise multiple regression analysis, Transformations, Exponential smoothing, Adaptive filtering

These programs, developed on real problems over a year's teaching and consultancy use the powerful Amstrad graphics to fit curves and analyse patterns as part of a decision process.

Prices for 464, 664, 6128 & 8256 –
Cassette £18.95 Disc £23.95 both inc. P&P.

J.P.C. SOFTWARE
Hatherley Farmhouse, Mill Road, Little Melton, Norwich NR9 3NZ.

Cheshire Micro Design

HOBBYFILE

catalogue your collections:- records, books, tapes, slides, addresses etc. Search/sort/save etc.

EXGEN 1

expert system – symptom/fault diagnosis.

NUMBER SKILLS

2 to 11 year olds: Count, +, –, × and ÷

MUSIC PLAYER

Tape £4.95, Disc £8.95 each, free leaflet.
CPC464, 664 and 6128

CMD, 66 CLOSE LANE, ALSAGER, STOKE-ON-TRENT

PRE-SCHOOL, PRIMARY, JUNIOR

ARC **Education**

By a Teacher. Tested by Pupils
Approved by Parents and Schools
For Home use on all CPC models

Each set contains SEVEN Programs
£5.00 Per Set

Choice of more than FIFTY programs.

SAE for Lists to:

ARC, 53 Bentley Street, CLEETHORPES,
Sth. HUMBERSIDE DN35 8DL. (0472) 699632

PCW 8256

£399
+ VAT

BRANDED DISCS

10 Pack 3" = £38
5 Pack 3" = £20
(Inc. VAT P&P).

CICA (IMPEX) LIMITED
287 Caledonian Road, London N1 1EG.

VISA **01-700 4004** Access

SIMPLE ACCOUNTS


Book-Keeping Made Easy For The Small Business

- **Full Analysis of Income and Expenditure**
- **Constant Update of Creditors and Debtors**
- **Quarterly Totals for VAT Returns**
- **Monthly and Year to Date Reports**
- **Printer or Screen Output**


"Most definitely this system removes most of the chore from doing the books, including the dreaded VAT" . . . CWTA, Dec. 1985.

Only £29.95 including VAT & Carriage (£34.95 on Disc).

CORNIX SOFTWARE LTD.
16 Kneesworth Street, Royston, Herts. SG8 5AA. Tel: Royston (0763) 852989



Amstrad User Awards



This first Amstrad User Awards proved very popular, the results seem to reflect the sales of programs as much as their popularity. Sorcery and Sorcery Plus walked away with the top prizes, it was voted program of the year, game of the year, arcade strategy game of the year, best graphics, and original program. Virgin took the prize for Software House of the Year. Original program is probably not deserved since it is a conversion, but as most Amstrad programs are conversions of one kind or another to disallow it would have left very few options.

Mini Office seemed to be the equivalent business program, showing that a lot of Arnolds are being used for semi-serious purposes.

The worst program of the year shows how right Amsoft are to concentrate on the Amsoft Gold range, "3D invaders" is used as an expletive in the magazine office.

Book of the Year was biased by having an Amazing Amstrad Omnibus competition in the same issue. It is good, but not so good that it should get more than twice as many votes as the nearest rival. The fourth place for the firmware manual was well deserved, it is good to see Soft 158 being noticed even if it was not first put on sale in 1985.

One of the nicest surprises was the third place for Defend or Die. This has been one of the Editor's favourite games for a long time but no one else seems to have noticed it.

Program of the Year
1. Sorcery/Sorcery Plus
2. Way of The Exploding Fist
3. Knight Lore
4. Starion

Game of the Year
1. Sorcery/Sorcery Plus
2. Way of the Exploding Fist
3. Daley Thompsons Decathlon
4. Hyper Sports

Utility of the Year
1. Mini Office
2. Dk'Tronics Light Pen Software
3. Maxam
4. Quill

Peripheral of the Year
=1. DD1, DMP 2000
2. Dk'Tronics Lightpen
3. Dk'Tronics Speech Synthesiser
4. AMX Mouse

Business Program of the Year
1. Mini Office
2. Amsword/Tasword
3. Masterfile
4. New Word
5. Protext

Software House of the Year
1. Virgin
2. Ultimate
3. Melbourne House
4. Level 9

Worst Program of the Year
1. Grand Prix Driver
2. 3D Invaders
3. North Sea Bullion Adventure
=4. Assault on Port Stanley, View to A Kill, Sultans Maze

Bargain of the Year
1. Non Terraqueous
2. Soul of A Robot
3. They Sold A Million
4. Computer Hits 10

Shoot 'Em Up of the Year
1. 3D Starstrike
2. Starion
3. Defend or Die
4. Harrier Attack

Book of the Year
1. Amazing Amstrad Omnibus
=2. Amstrad Computing
3. The Working Amstrad
4. Firmware Specifications Manual

Arcade Strategy Game of the Year
1. Sorcery
=2. Lords of Midnight, Knight Lore
=4. Alien 8, Dun Darach, Pyjamarama

Best Adventure of the Year
1. Red Moon
=2. Lords Of Midnight, Return to Eden
4. Dun Darach

Best Music of the Year
1. Ghostbusters
2. Sorcery
3. Jet Set Willy
4. Jammin'

Best Graphics of the Year
1. Sorcery
2. Knight Lore
=3. Starion, Pyjamarama, Way of the Exploding Fist

Original Program of the Year
1. Sorcery
2. Decathlon
3. Highway Encounter
=4. Knight Lore, Psychadelia, Hacker

The Least Significant Bit

I'll start off by saying that this hasn't been much of a month for happenings. No magazines bought and sold, no new Amstrad computers launched, no significant events at all. *(What do you mean? Jane Nolan got her hair cut – Ed.)*

Sinclair "launched" (ha!) the Spectrum 128 for £40 more than they will be charging as soon as the Spectrum Plus stocks have subsided. Will there be a clamour from Spectrum Plus Owners for upgrades (remember the CPC664? Amstrad do . . .)?

Acorn discovered that once you are locked into the British educational "system" you have become institutionalised and can get away with almost anything.

The one event

Amstrad made £27 million on their first half year trading, representing net margins of 21 per cent. This is almost unheard of in any business, let alone one as volatile as the computer marketplace. Anyone in the Amstrad orbit should be delighted, since although your first reaction may be that Amstrad is overcharging (yet everyone is amazed how cheap the PCW 8256 is) it means that Amstrad is here to stay. Stability in this business is a very valuable commodity for users.

These results are very significant. They show just how much more vicious the pricing could get if someone was foolish enough to take them on – and they also show that Amstrad has got plenty of reserves to take product development further forward if they so choose. And judging by the meanness of the dividend, they certainly intend to do something with the money!

In a spin

Games on disc are a serious issue to the CPC6128 owner, yet why are so few available? The cost to publishers to invest in stocking the outlets with discs is horrific, hence Amstrad and their clout have cornered the market for the time being.

It's about time some alternative approach to distributing games on disc made them more readily accessible to disc system owners. This might also stem the publishers' concern about the piracy arising from transferring from cassette to disc.

It is a lot easier to copy protect an original disc than a cassette (tape to tape duplication is always possible – that's how the things are made in the first place).

The Queen's English

The primary dictionary with the spell checker provided with NewWord's companion Spell Plus program has recently been Anglicised (Anglicized?). You will also find that words like Amstrad are present. however, it's a big job to do and the current releases could still use a little weeding, so NewStar are offering a refund of the purchase price of £69 to the user sending in the most Americanisms still present in the latest release.

Pin the tail on the donkey!

No prizes for guessing what everyone is suggesting Amstrad will launch next. The only uncertainty concerns the final configuration and the final price.

Well, we'll let you into a little secret, it has a 500 mbyte sequential filing optical disc, tape backup and removable hard disc unit. Honestly. *(And a built-in teasmade –Ed.)*

ACU

ACU ADVERTISERS' INDEX

Advantage 65
Amsoft 36
Amstrad 28, 74/76
Arc 88
Arnor 24/25
Ash & Newman 71
Astrocalc 88
BBD Dust Covers 83
Campbell Software Design 45
Cascade Games 77
Cheshire Micro Design 88
Chiltern Computers Limited 72
CICA (Impex) Ltd 88
Cirkit Distribution 66
Colleen Limited 42
Cornix Software 83/88
Cox Software 88
CP Software 4
Datastar 35
Davis Rubin 72
Digital Integration ..... IBC
Digital Research 13/15
DK Tronics ..... OBC
E G Graphics 59
Evesham Micro 71
Garwood 46
Global Software 75
Graf Sales 32
Hi-Soft 53
Interlock Services 65
John Wylie & Sons 40/41
JPC 83
KDS 58
Kuma Computers 23
Lerm 65
Lightwave Leisure 87
Load & Run 44
Logic Sales 77
Micro Power 57/87
Micro-Aid 88
Mikro-Gen 69
MJC Supplies 87
Northern Computers 65
O.J. Software 82
Opus 66
Panda Electronics 82
Pride Utilities 60
Probe Software ..... IFC
Prospero 16
Rational Solutions 84
Robert Edwards & Co 84
Romantic Robot 77
RSD Connections 82
Saxon Computing 60
School Software 83
Selec Software 82
Shekhana 84
Siren Software 59
SJB Discs 6
Soft Insight 84
Soft Machine 82
Spectradraw 58
Squirrels Byte 58
Tasman Software 10/11
Thames Link 82
The Electric Studio 48
Timatic Systems 20
Transform 21

BUSINESS SECTION

Amstrad ..... (VIII/IX)
Box ..... (XXVII)
Camsoft ..... (XXXI)
Caxton ..... (XV) (XXIII)
Celcom ..... (XXXII)
Compact ..... (XXVII)
Connect ..... (XXVIII)
Data Soft ..... (XII)
DK Tronics ..... (XVI/XVII)
Greyfield ..... (XXVII)
Metyclean ..... (XVIII)
Micro-Way ..... (XXXII)
Newstar ..... (IV)
Northern Comp ..... (II)
Pace ..... (VII)
Quest ..... (XXIV/XXV)
Rad Systems ..... (XXXII)
Sage Soft ..... (XI)
Software City ..... (XXX)
Speedysoft ..... (XXI)
Wrexham ..... (XXVIII)

Compatible with 464, 664 & 6128

FIGHTER PILOT

ALSO AVAILABLE ON 48K SPECTRUM, CBM 64 & ATARI

BY D.K. MARSHALL
ADAPTED BY DARRELL D.

AMSTRAD



AMSTRAD CPC 464, 664, 6128

Fighter Pilot	☐	£8.95
Fighter Pilot Disk	☐	£13.95
ATARI		
Fighter Pilot Disk	☐	£12.95
Fighter Pilot	☐	£9.95
SPECTRUM		
Tomahawk 48K	☐	£9.95
Night Gunner 48K	☐	£6.95
Fighter Pilot 48K	☐	£7.95
COMMODORE 64		
Speed King Disk	☐	£12.95
Speed King Cassette	☐	£9.95
Fighter Pilot Disk	☐	£14.95
Fighter Pilot Cassette	☐	£9.95

Cheques payable to Digital Integration Ltd

I enclose a cheque/P.O. for_____Total

Name_____

Address_____

Please debit my Access/Visa card no.

Access VISA

Tele Sales
(0276) 684959

Expiry date_____

Please send to Digital Integration,
Watchmoor Trade Centre, Watchmoor Road, Camberley, Surrey GU15 3AJ.
VAT and p. & p. inclusive within UK. (Overseas inc. 55p. per cassette)

DIGITAL INTEGRATION

Watchmoor Trade Centre,
Watchmoor Road,
Camberley, Surrey
GU15 3AJ

Trade and Export enquiries welcome. Lifetime Guarantee.

Computer Trade Reader Awards 1984 Winner

POWER BEHIND YOUR AMSTRAD





You can order by phone quoting your Barclaycard or Access number, orders are normally despatched in 24 hours.





DK Tronics products are available in all good computer stores. If you have any local problems obtaining them contact us directly.

dk'tronics

MANUFACTURERS OF POWERFUL PERIPHERALS

DK Tronics Limited
Englands Lane, Gorleston-on-Sea, Great Yarmouth, Norfolk NR31 6BE
Phone 0493 602926 (24 Hours), Telex 975408